Gulf Breeze RV Resort

Florida (statewide factor)

TOTAL PROJECT COST	PER SF	PER SITE	HARD / SOFT / LAND
$9,487,485	**—**	**$63,250**	**72 / 19 / 8%**

COST SUMMARY

Construction hard cost	**$5,476,399**
FF&E	**$224,224**
Design + construction contingency	**$1,172,466**
Hard cost subtotal	**$6,873,089**
Soft costs	**$714,762**
Impact & tap fees	**$503,558**
Developer fee	**$326,075**
Financing (interest + fees)	**$209,733**
Soft cost contingency	**$60,469**
Soft cost subtotal	**$1,814,597**
Land & acquisition	**$799,800**
Total project cost	**$9,487,485**

BASIS

Location	**Florida (factor 0.870)**
Gross building SF	**—**
Site acres	**12.50**
Cost per acre	**$758,999**
Research data version	**2026.0c737c8255**
Engine	**budget-engine-2.0.0**

All defaults come from the research data shipped with the app (2026.0c737c8255), escalated to the construction midpoint and adjusted to the project location. Values marked "Derived estimate — verify" have no direct published source.

Cost by Component

COMPONENT	TYPE	SIZE	HARD (INCL. FF&E, CONT.)	SOFT (INCL. FIN.)	LAND	TOTAL	PER PRIMARY UNIT	PER SF	RANGE CHECK
RV resort	RV park / resort	150 sites	$6,873,089	$1,814,597	$799,800	$9,487,485	$63,250	—	within ($19,594–$152,400)
TOTAL			**$6,873,089**	**$1,814,597**	**$799,800**	**$9,487,485**			

Cost by Phase

PHASE	START	MONTHS	MIDPOINT	ESCALATION	HARD	SOFT	LAND	TOTAL	LOAN	INTEREST
Phase 1	2027-03	13	2027-10	5.2%	$6,873,089	$1,814,597	$799,800	$9,487,485	$5,692,491	$152,808
TOTAL					**$6,873,089**	**$1,814,597**	**$799,800**	**$9,487,485**		

Line-Item Detail

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
RV resort	Phase 1	Construction	01 00 00	General Requirements	—	—	—	$314,848	—
RV resort	Phase 1	Construction	03 00 00	Concrete	—	—	—	$157,424	—
RV resort	Phase 1	Construction	07 00 00	Thermal & Moisture Protection	—	—	—	$118,068	—
RV resort	Phase 1	Construction	08 00 00	Openings	—	—	—	$59,034	—
RV resort	Phase 1	Construction	09 00 00	Finishes	—	—	—	$98,390	—
RV resort	Phase 1	Construction	10 00 00	Specialties	—	—	—	$59,034	—
RV resort	Phase 1	Construction	23 00 00	HVAC	—	—	—	$47,227	—
RV resort	Phase 1	Construction	26 00 00	Electrical — balance	—	—	—	$269,892	—
RV resort	Phase 1	Construction	31 00 00	Earthwork	—	—	—	$287,298	—
RV resort	Phase 1	Construction	32 00 00	Exterior Improvements — balance	—	—	—	$607,919	—
RV resort	Phase 1	Construction	33 00 00	Utilities — balance	—	—	—	$31,017	—
RV resort	Phase 1	Construction	26 00 00	RV power pedestal (50/30/20A) incl. setting and connection (within baseline)	150	ea	$1,913.92	$287,088	—
RV resort	Phase 1	Construction	33 00 00	Water and sewer hookups per site (riser, hose bib, 4in sewer inlet, laterals) (within baseline)	150	ea	$4,883.11	$732,467	—
RV resort	Phase 1	Construction	32 00 00	RV pad and patio (gravel, asphalt or concrete pad; concrete patio) (within baseline)	150	ea	$3,188.97	$478,345	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
RV resort	Phase 1	Construction	32 00 00	Interior park roads (20-24 ft, gravel to asphalt) (within baseline)	6,000	LF	$99.66	$597,949	—
RV resort	Phase 1	Construction	22 00 00	Bathhouse / comfort station with showers and laundry (within baseline)	1	ea	$697,587.48	$697,587	—
RV resort	Phase 1	Construction	06 00 00	Office / camp store / clubhouse (within baseline)	1	LS	$597,932.12	$597,932	—
RV resort	Phase 1	Construction	33 00 00	RV dump (sanitary) station with rinse water (within baseline)	1	ea	$34,879.37	$34,879	—
RV resort	Phase 1	FF&E	12 00 00	Furniture, fixtures & equipment	150	site	$1,494.83	$224,224	—
RV resort	Phase 1	Contingency	99 02 00	Design contingency	10	% of hard	—	$547,640	—
RV resort	Phase 1	Contingency	99 03 00	Hard cost (construction) contingency	10	% of hard	—	$624,826	—
RV resort	Phase 1	Soft costs	SC	Architecture & engineering (basic services, design + CA)	6	% of hard	—	$331,827	—
RV resort	Phase 1	Soft costs	SC	Civil engineering, ALTA/topo survey, geotechnical report	1	% of hard	—	$51,050	—
RV resort	Phase 1	Soft costs	SC	Building permit & plan review fees (excl. impact / tap fees)	1	% of hard	—	$51,050	—
RV resort	Phase 1	Soft costs	SC	Legal, accounting, cost certification	1	% of hard	—	$35,735	—
RV resort	Phase 1	Soft costs	SC	Builder's risk insurance	0	% of hard	—	$20,420	—
RV resort	Phase 1	Soft costs	SC	Owner's general liability / OCIP-OCP during construction	0	% of hard	—	$15,315	—
RV resort	Phase 1	Soft costs	SC	Marketing, lease-up / rent-up (excl. commercial leasing commissions)	1	% of hard	—	$40,840	—
RV resort	Phase 1	Soft costs	SC	Construction-loan title, closing & recording	0	% of hard	—	$20,420	—
RV resort	Phase 1	Soft costs	SC	Special inspections, materials testing, commissioning	1	% of hard	—	$40,840	—
RV resort	Phase 1	Soft costs	SC	Owner's representative / project management	1	% of hard	—	$76,576	—
RV resort	Phase 1	Soft costs	SC	Third-party reports (appraisal, Phase I ESA, market study, PCA/CNA)	1	project	$21,750.00	$21,750	—
RV resort	Phase 1	Impact & tap fees	SC	Total impact fees — hotel room	150	unit	$3,357.05	$503,558	—
RV resort	Phase 1	Contingency	SC	Soft cost contingency	5	% of soft	—	$60,469	—
RV resort	Phase	Land	LAND	Land / acquisition	—	—	—	$750,000	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
	1								
RV resort	Phase 1	Land	LAND	Land closing costs	—	—	—	$15,000	—
RV resort	Phase 1	Land	LAND	Land due diligence	—	—	—	$34,800	—
RV resort	Phase 1	Soft costs	SC	Real estate taxes during construction	1	years	$8,250.00	$8,938	—
RV resort	Phase 1	Developer fee	DEV	Developer fee	4	% of cost excl. land	—	$326,075	—
RV resort	Phase 1	Financing	FIN	Construction loan interest (capitalized)	—	—	—	$152,808	—
RV resort	Phase 1	Financing	FIN	Construction loan fee	—	—	—	$56,925	—
TOTAL				**Total project cost**				**$9,487,485**	

Draw Schedules

PHASE 1 — MONTHLY DRAWS

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE
2027-03	$0	$923,500	$799,800	$1,780,225	$0	$0	$0
2027-04	$99,860	$52,413	$0	$152,272	$0	$0	$0
2027-05	$293,776	$52,413	$0	$346,188	$0	$0	$0
2027-06	$470,619	$52,413	$0	$523,031	$0	$0	$0
2027-07	$620,111	$52,413	$0	$672,523	$0	$0	$0
2027-08	$733,564	$52,413	$0	$320,754	$465,223	$0	$465,223
2027-09	$804,386	$52,413	$0	$0	$856,798	$2,714	$1,324,735
2027-10	$828,459	$52,413	$0	$0	$880,872	$7,728	$2,213,335
2027-11	$804,386	$52,413	$0	$0	$856,798	$12,911	$3,083,044
2027-12	$733,564	$52,413	$0	$0	$785,977	$17,984	$3,887,005
2028-01	$620,111	$52,413	$0	$0	$672,523	$22,674	$4,582,203
2028-02	$470,619	$52,413	$0	$0	$523,031	$26,730	$5,131,964
2028-03	$293,776	$52,413	$0	$0	$346,188	$29,936	$5,508,088
2028-04	$99,860	$52,413	$0	$0	$152,272	$32,131	$5,692,491

Sources & Assumptions

ASSUMPTIONS

RV resort — baseline price	**$45,720 / site · Researched (specialty-residential/rv-park-resort.json)**
RV resort — factors	**regional 0.87 · quality 1 · size 0.9681 · escalation 1.0523**
RV resort — research note	**Cost per site is driven by wastewater (municipal sewer vs. septic/drainfield vs. package plant), electrical service (50A pedestals and distribution), road and pad surfacing (gravel vs. asphalt/concrete) and how much building (bathhouse, clubhouse, store, pool) is spread over the sites. Public-sector bid-grade evidence (Missouri, Utah state parks) runs $50k-$112k per site; private-developer itemizations run roughly $15k-$40k per site. The default sits between them, weighted toward private development; confidence is medium.**
Phase 1 — schedule	**2027-03, 13 months, midpoint 2027-10, escalation 5.23% (forecast rates from _indices/escalation.json)**
Phase 1 — financing	**LTC 60%, rate 7.00%, fee 1.00%**

SOURCES (51)

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_common/fees.json#e3	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	8034 USD/unit (2019)	high	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/fees.json#e5	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	5408 USD/1000sf (2019)	high	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/financing.json#e1	Secured Overnight Financing Rate (SOFR)	Federal Reserve Bank of St. Louis (FRED)	0.039 pct (2026)	high	https://fred.stlouisfed.org/series/SOFR
_common/financing.json#e2	30-Day Average SOFR (SOFR30DAYAVG)	Federal Reserve Bank of St. Louis (FRED)	0.03889 pct (2026)	high	https://fred.stlouisfed.org/series/SOFR30DAYAVG
_common/financing.json#e3	Bank Prime Loan Rate (DPRIME)	Federal Reserve Bank of St. Louis (FRED)	0.07 pct (2026)	high	https://fred.stlouisfed.org/series/DPRIME
_common/financing.json#e4	Federal Funds Target Range - Upper Limit (DFEDTARU)	Federal Reserve Bank of St. Louis (FRED)	0.0375–0.04 pct (2026)	high	https://fred.stlouisfed.org/series/DFEDTARU
_common/financing.json#e5	12 CFR Appendix A to Subpart A of Part 365 - Interagency Guidelines for Real Estate Lending Policies	Legal Information Institute, Cornell Law School (text of FDIC regulation)	0.8 pct	high	https://www.law.cornell.edu/cfr/text/12/appendix-A_to_subpart_A_of_part_365
_common/financing.json#e6	The July 2026 Senior Loan Officer Opinion Survey on Bank Lending Practices	Board of Governors of the Federal Reserve System	text (2026)	high	https://www.federalreserve.gov/data/sloos/sloos-202607.htm
_common/land-closing.json#e1	Title Rate Chart (effective March 1, 2026)	Texas Department of Insurance	5226 USD/policy (2026)	high	https://www.tdi.texas.gov/title/titlerates2026.html
_common/land-closing.json#e2	Real estate excise tax	Washington State Department of Revenue	0.0128 pct (2026)	high	https://dor.wa.gov/taxes-rates/other-taxes/real-estate-excise-tax
_common/land-closing.json#e3	Realty Transfer Tax	Pennsylvania Department of Revenue	0.01 pct (2026)	high	https://www.pa.gov/en/agencies/revenue/resources/tax-types-and-information/realty-transfer-tax.html
_common/land-closing.json#e4	Documentary Stamp Tax	Florida Department of Revenue	0.007 pct (2026)	high	https://floridarevenue.com/taxes/taxesfees/Pages/doc_stamp.aspx

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_common/land-closing.json#e5	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	text (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e1	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0852 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e10	Builders Risk Insurance in 2026: What It Costs, Who Pays, and the Exclusions That Wreck Commercial Projects	Terrapin Construction Group	0.0035–0.009 pct (2026)	low	https://terrapincg.com/news/builders-risk-insurance-commercial-construction-cost-2026
_common/soft-costs.json#e11	Builders Risk Insurance in 2026: What It Costs, Who Pays, and the Exclusions That Wreck Commercial Projects	Terrapin Construction Group	0.0007–0.0019 pct (2026)	low	https://terrapincg.com/news/builders-risk-insurance-commercial-construction-cost-2026
_common/soft-costs.json#e13	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	text (2025)	medium	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e14	What are Typical Developer Fees on a Multifamily Development?	HelloData	0.03–0.05 pct (2025)	low	https://www.hellodata.ai/help-articles/what-are-typical-developer-fees-on-a-multifamily-development
_common/soft-costs.json#e15	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	0.15 pct (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
_common/soft-costs.json#e16	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	0.15 pct (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e17	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	1200 USD/unit (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e18	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	500 USD/unit (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
_common/soft-costs.json#e19	Title Rate Chart (effective March 1, 2026)	Texas Department of Insurance	0.005226 pct (2026)	high	https://www.tdi.texas.gov/title/titlerates2026.html
_common/soft-costs.json#e2	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0988 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e20	Documentary Stamp Tax	Florida Department of Revenue	0.0035 pct (2026)	high	https://floridarevenue.com/taxes/taxesfees/Pages/doc_stamp.aspx
_common/soft-costs.json#e21	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.01 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e3	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0716 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_common/soft-costs.json#e4	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	0.0483 pct (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e5	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.06 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e6	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.12 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e7	Building Valuation Data – August 2025	International Code Council (posted by City of Kirkland, WA)	0.0075 pct (2025)	low	https://www.kirklandwa.gov/files/sharedassets/public/v/2/development-services/pdfs/building-pdfs/icc-august-2025.pdf
_common/soft-costs.json#e8	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	175000 USD/project (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e9	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	150000 USD/project (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
specialty-residential/rv-park-resort.json#e1	Lake of the Ozarks State Park - Campground Upgrade Project (revenue bond project sheet)	Missouri State Parks (Missouri DNR)	78622 USD/site (2020)	high	https://web.archive.org/web/2022id_/https://mostateparks.com/sites/mostateparks/files/LOSP-campground-project.pdf
specialty-residential/rv-park-resort.json#e10	How much does it cost to build a campground or RV park?	Outdoor Hospitality Weekly (Substack)	5000–10000 USD/site (2024)	low	https://ohweekly.substack.com/p/how-much-does-it-cost-to-build-a
specialty-residential/rv-park-resort.json#e11	Campgrounds - Freakonomics	Freakonomics Radio Network - The Economics of Everyday Things, Ep. 112 (Oct 26, 2025)	15000–25000 USD/site (2025)	low	https://freakonomics.com/podcast/campgrounds/
specialty-residential/rv-park-resort.json#e12	Menahga City Council Advances Plans for 10 Permanent Campsites at Memorial Forest Park	Modern Campground	9200 USD/site (2025)	low	https://moderncampground.com/?p=68943
specialty-residential/rv-park-resort.json#e13	Menahga City Council Advances Plans for 10 Permanent Campsites at Memorial Forest Park	Modern Campground	500–600 USD/ea (2025)	low	https://moderncampground.com/?p=68943
specialty-residential/rv-park-resort.json#e16	Oregon State Parks and Recreation Commission, Nov. 20, 2024, Agenda Item 8d - Ft. Stevens Utility Upgrade Construction Contract	Oregon Parks and Recreation Department	1100000 USD/ea (2024)	high	https://oregon.gov/oprd/CAC/Documents/2024-11-8d.pdf
specialty-residential/rv-park-resort.json#e17	Bid Tabulation - Campground Development Phase II, Comfort Station - Rebid, Palisades State Park, GFP Project No. Pali23Oa	South Dakota Department of Game, Fish and Parks	705540 USD/ea (2023)	high	https://gfp.sd.gov/UserDocs/nav/Bid_Tab_Comfort_Station_Rebid.pdf
specialty-residential/rv-park-resort.json#e18	Table Rock State Park - Campground Upgrade Project (revenue bond project sheet)	Missouri State Parks (Missouri DNR)	0.114 pct (2020)	high	https://web.archive.org/web/2022id_/https://mostateparks.com/sites/mostateparks/files/table-rock-campground-project.pdf

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
specialty-residential/rv-park-resort.json#e19	Lake of the Ozarks State Park - Campground Upgrade Project (revenue bond project sheet)	Missouri State Parks (Missouri DNR)	0.15 pct (2020)	high	https://web.archive.org/web/2022id_/https://mostateparks.com/sites/mostateparks/files/LOSP-campground-project.pdf
specialty-residential/rv-park-resort.json#e2	St. Francois State Park - Campground Upgrade Project (revenue bond project sheet)	Missouri State Parks (Missouri DNR)	65780 USD/site (2020)	high	https://web.archive.org/web/2022id_/https://mostateparks.com/sites/mostateparks/files/st-francois-campground-project.pdf
specialty-residential/rv-park-resort.json#e21	RV Park construction in West TD could move forward with $1 million state grant	Columbia Community Connection	39269 USD/site (2026)	low	https://columbiacommunityconnection.com/the-dalles/rv-park-construction-in-west-td-could-move-forward-with-1-million-state-grant
specialty-residential/rv-park-resort.json#e3	Table Rock State Park - Campground Upgrade Project (revenue bond project sheet)	Missouri State Parks (Missouri DNR)	67472 USD/site (2020)	high	https://web.archive.org/web/2022id_/https://mostateparks.com/sites/mostateparks/files/table-rock-campground-project.pdf
specialty-residential/rv-park-resort.json#e4	Long Branch State Park - Campground Upgrade Project (revenue bond project sheet)	Missouri State Parks (Missouri DNR)	94445 USD/site (2020)	high	https://web.archive.org/web/2022id_/https://mostateparks.com/sites/mostateparks/files/long-branch-campground-project.pdf
specialty-residential/rv-park-resort.json#e5	Roaring River State Park - Campground Upgrade Project (revenue bond project sheet)	Missouri State Parks (Missouri DNR)	49768 USD/site (2020)	medium	https://web.archive.org/web/2022id_/https://mostateparks.com/sites/mostateparks/files/RRSP-campground-project.pdf
specialty-residential/rv-park-resort.json#e6	Lake of the Ozarks State Park - Campground Upgrade Project (revenue bond project sheet)	Missouri State Parks (Missouri DNR)	55000 USD/site (2020)	high	https://web.archive.org/web/2022id_/https://mostateparks.com/sites/mostateparks/files/LOSP-campground-project.pdf
specialty-residential/rv-park-resort.json#e7	Division of Facilities Construction and Management 22223510 - Bud Mahas Construction, Inc. | Govly	Govly (public award record of Utah DFCM)	112037 USD/site (2022)	medium	https://app.govly.com/public/awards/e357f38dba36a5dcac9434618dbba1fb
specialty-residential/rv-park-resort.json#e8	How much does it cost to build a campground or RV park?	Outdoor Hospitality Weekly (Substack)	30000–40000 USD/site (2024)	medium	https://ohweekly.substack.com/p/how-much-does-it-cost-to-build-a
specialty-residential/rv-park-resort.json#e9	How much does it cost to build a campground or RV park?	Outdoor Hospitality Weekly (Substack)	4000 USD/site (2024)	low	https://ohweekly.substack.com/p/how-much-does-it-cost-to-build-a

Sample output — revenue, land and exit-cap inputs are illustrative. Engine budget-engine-2.0.0.