Brazos Crossing — 3-phase master plan

Fort Worth, TX

TOTAL PROJECT COST	PER SF	PER ACRE	HARD / SOFT / LAND
$168,894,726	**$285.20**	**$2,724,108**	**72 / 21 / 7%**

COST SUMMARY

Construction hard cost	**$108,856,805**
FF&E	**$2,687,919**
Design + construction contingency	**$10,824,388**
Hard cost subtotal	**$122,369,113**
Soft costs	**$18,347,167**
Impact & tap fees	**$5,741,031**
Developer fee	**$4,758,332**
Financing (interest + fees)	**$5,383,795**
Soft cost contingency	**$1,194,687**
Soft cost subtotal	**$35,425,014**
Land & acquisition	**$11,100,600**
Total project cost	**$168,894,726**

BASIS

Location	**Fort Worth, TX (factor 0.840)**
Gross building SF	**592,200**
Site acres	**62.00**
Cost per acre	**$2,724,108**
Research data version	**2026.0c737c8255**
Engine	**budget-engine-2.0.0**

All defaults come from the research data shipped with the app (2026.0c737c8255), escalated to the construction midpoint and adjusted to the project location. Values marked "Derived estimate — verify" have no direct published source.

Cost by Component

COMPONENT	TYPE	SIZE	HARD (INCL. FF&E, CONT.)	SOFT (INCL. FIN.)	LAND	TOTAL	PER PRIMARY UNIT	PER SF	RANGE CHECK
Garden apartments	Garden multifamily	300 units	$61,247,112	$20,061,093	$5,219,173	$86,527,377	$288,425	$274.69	within ($150,000–$420,000)
Rental townhomes	Townhomes	80 units	$24,093,253	$5,381,159	$2,551,595	$32,026,007	$400,325	$222.40	within ($177,704–$627,192)
Grocery-anchored center	Grocery-anchored shopping center	65000 SF	$15,417,682	$4,291,723	$2,487,806	$22,197,210	$341	$341.50	within ($130–$400)
Select-service hotel	Select-service hotel	110 keys	$21,611,066	$5,691,039	$842,027	$28,144,132	$255,856	$412.67	within ($146,345–$334,502)
TOTAL			**$122,369,113**	**$35,425,014**	**$11,100,600**	**$168,894,726**			

SHARED ELEMENTS

SHARED ELEMENT	ALLOCATION	COST	SHARES
Spine road (private, 2-lane)	sf	$1,139,492	Garden apartments $606,113; Rental townhomes $277,080; Grocery-anchored center $125,071; Select-service hotel $131,228
Regional detention	sf	$2,903,680	Garden apartments $1,544,511; Rental townhomes $706,062; Grocery-anchored center $318,709; Select-service hotel $334,399
Off-site water & sewer extension	units	$1,288,711	Garden apartments $5,903; Rental townhomes $1,574; Grocery-anchored center $1,279,069; Select-service hotel $2,165
Resident amenity center (MF + townhomes)	manual	$1,468,172	Garden apartments $1,101,129; Rental townhomes $367,043

Cost by Phase

PHASE	START	MONTHS	MIDPOINT	ESCALATION	HARD	SOFT	LAND	TOTAL	LOAN	INTEREST
Phase 1 — infrastructure + apartments	2027-04	25	2028-05	7.7%	$65,124,220	$20,923,231	$5,219,173	$91,266,624	$54,759,974	$2,860,560
Phase 2 — townhomes + retail	2029-05	14	2029-12	14.6%	$36,149,567	$8,937,083	$5,039,401	$50,126,050	$30,075,630	$884,041
Phase 3 — hotel	2030-07	19	2031-05	21.1%	$21,095,326	$5,564,700	$842,027	$27,502,052	$16,501,231	$625,826
TOTAL					**$122,369,113**	**$35,425,014**	**$11,100,600**	**$168,894,726**		

Line-Item Detail

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Garden apartments	Phase 1 — infrastructure + apartments	Construction	01 00 00	General Requirements — balance	—	—	—	$5,493,575	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	03 00 00	Concrete	—	—	—	$1,917,334	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	04 00 00	Masonry	—	—	—	$1,054,534	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Garden apartments	Phase 1 — infrastructure + apartments	Construction	05 00 00	Metals	—	—	—	$1,006,601	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	06 00 00	Wood, Plastics & Composites	—	—	—	$9,299,072	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	07 00 00	Thermal & Moisture Protection	—	—	—	$2,588,401	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	08 00 00	Openings	—	—	—	$1,246,267	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	09 00 00	Finishes	—	—	—	$4,409,869	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	10 00 00	Specialties	—	—	—	$239,667	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	11 00 00	Equipment	—	—	—	$1,438,001	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	12 00 00	Furnishings	—	—	—	$1,821,468	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	21 00 00	Fire Suppression	—	—	—	$575,200	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	22 00 00	Plumbing	—	—	—	$3,307,402	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	23 00 00	HVAC	—	—	—	$1,725,601	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	26 00 00	Electrical	—	—	—	$3,978,469	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	27 00 00	Communications	—	—	—	$191,733	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	28 00 00	Electronic Safety & Security	—	—	—	$191,733	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	31 00 00	Earthwork	—	—	—	$2,204,934	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	33 00 00	Utilities	—	—	—	$1,102,467	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	32 00 00	On-site land development (grading, paving, on-site utilities) (within baseline)	283,500	NRSF	$13.10	$3,712,464	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	32 00 00	Site amenity package (pool, dog park, grills, playground) (within baseline)	283,500	NRSF	$2.93	$830,690	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	01 00 00	Clubhouse / leasing center with fitness (3,000-6,000 SF) (within baseline)	1	LS	$1,266,101.99	$1,266,102	—
Garden apartments	Phase 1 — infrastructure + apartments	Construction	32 00 00	Surface parking (asphalt, striping, lighting, drainage share) (within baseline)	510	space	$4,521.79	$2,306,114	—
Garden	Phase 1 — infrastructure	FF&E	12 00	Furniture, fixtures & equipment	300	unit	$1,356.54	$406,961	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
apartments	+ apartments		00						
Rental townhomes	Phase 2 — townhomes + retail	Construction	01 00 00	General Requirements	—	—	—	$2,480,117	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	03 00 00	Concrete	—	—	—	$1,446,735	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	04 00 00	Masonry	—	—	—	$248,012	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	05 00 00	Metals	—	—	—	$103,338	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	06 00 00	Wood, Plastics & Composites — balance	—	—	—	$1,025,766	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	07 00 00	Thermal & Moisture Protection	—	—	—	$2,066,764	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	08 00 00	Openings	—	—	—	$1,033,382	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	09 00 00	Finishes	—	—	—	$1,963,426	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	10 00 00	Specialties	—	—	—	$124,006	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	11 00 00	Equipment	—	—	—	$413,353	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	12 00 00	Furnishings	—	—	—	$930,044	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	22 00 00	Plumbing	—	—	—	$1,756,749	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	23 00 00	HVAC	—	—	—	$1,240,058	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	26 00 00	Electrical	—	—	—	$1,550,073	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	31 00 00	Earthwork	—	—	—	$516,691	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	32 00 00	Exterior Improvements	—	—	—	$930,044	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	33 00 00	Utilities	—	—	—	$248,012	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	21 00 00	Residential fire sprinklers (NFPA 13D/13R) (within baseline)	144,000	SF	$3.02	$435,113	—
Rental townhomes	Phase 2 — townhomes + retail	Construction	06 00 00	Attached/tuck-under garage (2 car) (within baseline)	80	ea	$30,177.32	$2,414,185	—
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	01 00 00	General Requirements	—	—	—	$898,789	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	03 00 00	Concrete	—	—	—	$1,460,532	—
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	04 00 00	Masonry	—	—	—	$449,395	—
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	05 00 00	Metals	—	—	—	$1,348,184	—
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	06 00 00	Wood, Plastics & Composites	—	—	—	$112,349	—
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	07 00 00	Thermal & Moisture Protection	—	—	—	$1,011,138	—
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	08 00 00	Openings	—	—	—	$674,092	—
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	09 00 00	Finishes	—	—	—	$337,046	—
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	10 00 00	Specialties	—	—	—	$112,349	—
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	21 00 00	Fire Suppression	—	—	—	$224,697	—
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	22 00 00	Plumbing	—	—	—	$337,046	—
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	23 00 00	HVAC	—	—	—	$449,395	—
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	26 00 00	Electrical	—	—	—	$674,092	—
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	27 00 00	Communications	—	—	—	$56,174	—
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	28 00 00	Electronic Safety & Security	—	—	—	$56,174	—
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	31 00 00	Earthwork	—	—	—	$561,743	—
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	32 00 00	Exterior Improvements	—	—	—	$1,797,578	—
Grocery-anchored center	Phase 2 — townhomes + retail	Construction	33 00 00	Utilities	—	—	—	$674,092	—
Grocery-anchored center	Phase 2 — townhomes + retail	Specialty & site	09 00 00	In-line landlord TI allowance	26,000	SF	$33.68	$875,692	—
Grocery-anchored center	Phase 2 — townhomes + retail	Specialty & site	10 00 00	Multi-tenant pylon signs	2	ea	$75,443.28	$150,887	—
Select-service hotel	Phase 3 — hotel	Construction	01 00 00	General Requirements	—	—	—	$1,314,829	—
Select-service	Phase 3 — hotel	Construction	03 00	Concrete	—	—	—	$986,122	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
hotel			00						
Select-service hotel	Phase 3 — hotel	Construction	04 00 00	Masonry	—	—	—	$328,707	—
Select-service hotel	Phase 3 — hotel	Construction	05 00 00	Metals	—	—	—	$657,415	—
Select-service hotel	Phase 3 — hotel	Construction	06 00 00	Wood, Plastics & Composites	—	—	—	$1,807,890	—
Select-service hotel	Phase 3 — hotel	Construction	07 00 00	Thermal & Moisture Protection	—	—	—	$986,122	—
Select-service hotel	Phase 3 — hotel	Construction	08 00 00	Openings	—	—	—	$821,768	—
Select-service hotel	Phase 3 — hotel	Construction	09 00 00	Finishes	—	—	—	$1,972,244	—
Select-service hotel	Phase 3 — hotel	Construction	10 00 00	Specialties — balance	—	—	—	$305,659	—
Select-service hotel	Phase 3 — hotel	Construction	11 00 00	Equipment	—	—	—	$328,707	—
Select-service hotel	Phase 3 — hotel	Construction	12 00 00	Furnishings	—	—	—	$328,707	—
Select-service hotel	Phase 3 — hotel	Construction	14 00 00	Conveying Equipment	—	—	—	$328,707	—
Select-service hotel	Phase 3 — hotel	Construction	21 00 00	Fire Suppression	—	—	—	$328,707	—
Select-service hotel	Phase 3 — hotel	Construction	22 00 00	Plumbing	—	—	—	$1,314,829	—
Select-service hotel	Phase 3 — hotel	Construction	23 00 00	HVAC	—	—	—	$1,150,476	—
Select-service hotel	Phase 3 — hotel	Construction	26 00 00	Electrical	—	—	—	$1,314,829	—
Select-service hotel	Phase 3 — hotel	Construction	27 00 00	Communications	—	—	—	$328,707	—
Select-service hotel	Phase 3 — hotel	Construction	28 00 00	Electronic Safety & Security	—	—	—	$164,354	—
Select-service hotel	Phase 3 — hotel	Construction	31 00 00	Earthwork	—	—	—	$493,061	—
Select-service hotel	Phase 3 — hotel	Construction	32 00 00	Exterior Improvements	—	—	—	$657,415	—
Select-service hotel	Phase 3 — hotel	Construction	33 00 00	Utilities	—	—	—	$493,061	—
Select-service hotel	Phase 3 — hotel	Construction	10 00 00	Brand monument sign (within baseline)	1	ea	$23,048.10	$23,048	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Select-service hotel	Phase 3 — hotel	Specialty & site	01 00 00	Pre-opening, OS&E and working capital	110	key	$4,785.23	$526,375	—
Select-service hotel	Phase 3 — hotel	FF&E	12 00 00	Furniture, fixtures & equipment	110	key	$20,735.98	$2,280,958	—
Garden apartments	Phase 1 — infrastructure + apartments	Shared elements	32 00 00	Spine road (private, 2-lane) (share)	4,200	LF	$271.31	$606,113	—
Rental townhomes	Phase 1 — infrastructure + apartments	Shared elements	32 00 00	Spine road (private, 2-lane) (share)	4,200	LF	$271.31	$277,080	—
Grocery-anchored center	Phase 1 — infrastructure + apartments	Shared elements	32 00 00	Spine road (private, 2-lane) (share)	4,200	LF	$271.31	$125,071	—
Select-service hotel	Phase 1 — infrastructure + apartments	Shared elements	32 00 00	Spine road (private, 2-lane) (share)	4,200	LF	$271.31	$131,228	—
Garden apartments	Phase 1 — infrastructure + apartments	Shared elements	33 00 00	Regional detention (share)	62	acre	$46,833.56	$1,544,511	—
Rental townhomes	Phase 1 — infrastructure + apartments	Shared elements	33 00 00	Regional detention (share)	62	acre	$46,833.56	$706,062	—
Grocery-anchored center	Phase 1 — infrastructure + apartments	Shared elements	33 00 00	Regional detention (share)	62	acre	$46,833.56	$318,709	—
Select-service hotel	Phase 1 — infrastructure + apartments	Shared elements	33 00 00	Regional detention (share)	62	acre	$46,833.56	$334,399	—
Garden apartments	Phase 1 — infrastructure + apartments	Shared elements	33 00 00	Off-site water & sewer extension (share)	3,800	LF	$339.13	$5,903	—
Rental townhomes	Phase 1 — infrastructure + apartments	Shared elements	33 00 00	Off-site water & sewer extension (share)	3,800	LF	$339.13	$1,574	—
Grocery-anchored center	Phase 1 — infrastructure + apartments	Shared elements	33 00 00	Off-site water & sewer extension (share)	3,800	LF	$339.13	$1,279,069	—
Select-service hotel	Phase 1 — infrastructure + apartments	Shared elements	33 00 00	Off-site water & sewer extension (share)	3,800	LF	$339.13	$2,165	—
Garden apartments	Phase 1 — infrastructure + apartments	Shared elements	01 00 00	Resident amenity center (MF + townhomes) (share)	6,500	SF	$225.87	$1,101,129	—
Rental townhomes	Phase 1 — infrastructure + apartments	Shared elements	01 00 00	Resident amenity center (MF + townhomes) (share)	6,500	SF	$225.87	$367,043	—
Select-service hotel	Phase 1 — infrastructure + apartments	Contingency	99 02 00	Design contingency	5	% of hard	—	$23,390	—
Select-service hotel	Phase 1 — infrastructure + apartments	Contingency	99 03 00	Hard cost (construction) contingency	5	% of hard	—	$24,559	—
Select-service hotel	Phase 1 — infrastructure + apartments	Soft costs	SC	Architecture & engineering (basic services, design + CA)	8	% of hard	—	$36,306	—
Select-service hotel	Phase 1 — infrastructure + apartments	Soft costs	SC	Civil engineering, ALTA/topo survey, geotechnical report	1	% of hard	—	$5,586	—
Select-service	Phase 1 — infrastructure	Soft costs	SC	Building permit & plan review fees (excl.	1	% of hard	—	$5,586	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
hotel	+ apartments			impact / tap fees)					
Select-service hotel	Phase 1 — infrastructure + apartments	Soft costs	SC	Legal, accounting, cost certification	1	% of hard	—	$3,910	—
Select-service hotel	Phase 1 — infrastructure + apartments	Soft costs	SC	Builder's risk insurance	0	% of hard	—	$2,234	—
Select-service hotel	Phase 1 — infrastructure + apartments	Soft costs	SC	Owner's general liability / OCIP-OCP during construction	0	% of hard	—	$1,676	—
Select-service hotel	Phase 1 — infrastructure + apartments	Soft costs	SC	Marketing, lease-up / rent-up (excl. commercial leasing commissions)	1	% of hard	—	$4,468	—
Select-service hotel	Phase 1 — infrastructure + apartments	Soft costs	SC	Construction-loan title, closing & recording	0	% of hard	—	$2,234	—
Select-service hotel	Phase 1 — infrastructure + apartments	Soft costs	SC	Special inspections, materials testing, commissioning	1	% of hard	—	$4,468	—
Select-service hotel	Phase 1 — infrastructure + apartments	Soft costs	SC	Owner's representative / project management	2	% of hard	—	$8,378	—
Select-service hotel	Phase 3 — hotel	Contingency	99 02 00	Design contingency	5	% of hard	—	$848,087	—
Select-service hotel	Phase 3 — hotel	Contingency	99 03 00	Hard cost (construction) contingency	5	% of hard	—	$1,004,539	—
Select-service hotel	Phase 3 — hotel	Soft costs	SC	Architecture & engineering (basic services, design + CA)	8	% of hard	—	$1,493,463	—
Select-service hotel	Phase 3 — hotel	Soft costs	SC	Civil engineering, ALTA/topo survey, geotechnical report	1	% of hard	—	$229,764	—
Select-service hotel	Phase 3 — hotel	Soft costs	SC	Building permit & plan review fees (excl. impact / tap fees)	1	% of hard	—	$229,764	—
Select-service hotel	Phase 3 — hotel	Soft costs	SC	Legal, accounting, cost certification	1	% of hard	—	$160,835	—
Select-service hotel	Phase 3 — hotel	Soft costs	SC	Builder's risk insurance	0	% of hard	—	$91,905	—
Select-service hotel	Phase 3 — hotel	Soft costs	SC	Owner's general liability / OCIP-OCP during construction	0	% of hard	—	$68,929	—
Select-service hotel	Phase 3 — hotel	Soft costs	SC	Marketing, lease-up / rent-up (excl. commercial leasing commissions)	1	% of hard	—	$183,811	—
Select-service hotel	Phase 3 — hotel	Soft costs	SC	Construction-loan title, closing & recording	0	% of hard	—	$91,905	—
Select-service hotel	Phase 3 — hotel	Soft costs	SC	Special inspections, materials testing, commissioning	1	% of hard	—	$183,811	—
Select-service hotel	Phase 3 — hotel	Soft costs	SC	Owner's representative / project management	2	% of hard	—	$344,645	—
Select-service hotel	Phase 3 — hotel	Soft costs	SC	Third-party reports (appraisal, Phase I ESA, market study, PCA/CNA)	1	project	$21,000.00	$21,000	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Select-service hotel	Phase 3 — hotel	Impact & tap fees	SC	Total impact fees — hotel room	110	key	$3,357.05	$369,276	—
Select-service hotel	Phase 3 — hotel	Impact & tap fees	SC	Water capacity / tap / impact fee	17	EDU	$3,407.22	$58,093	—
Select-service hotel	Phase 3 — hotel	Impact & tap fees	SC	Sewer (wastewater) capacity / tap / impact fee	17	EDU	$3,407.22	$58,093	—
Garden apartments	Phase 1 — infrastructure + apartments	Contingency	99 02 00	Design contingency	5	% of hard	—	$2,758,268	—
Garden apartments	Phase 1 — infrastructure + apartments	Contingency	99 03 00	Hard cost (construction) contingency	5	% of hard	—	$2,916,529	—
Garden apartments	Phase 1 — infrastructure + apartments	Soft costs	SC	Architecture & engineering (basic services, design + CA)	8	% of hard	—	$4,582,642	—
Garden apartments	Phase 1 — infrastructure + apartments	Soft costs	SC	Civil engineering, ALTA/topo survey, geotechnical report	1	% of hard	—	$705,022	—
Garden apartments	Phase 1 — infrastructure + apartments	Soft costs	SC	Building permit & plan review fees (excl. impact / tap fees)	1	% of hard	—	$705,022	—
Garden apartments	Phase 1 — infrastructure + apartments	Soft costs	SC	Legal, accounting, cost certification	1	% of hard	—	$493,515	—
Garden apartments	Phase 1 — infrastructure + apartments	Soft costs	SC	Builder's risk insurance	1	% of hard	—	$282,009	—
Garden apartments	Phase 1 — infrastructure + apartments	Soft costs	SC	Owner's general liability / OCIP-OCP during construction	0	% of hard	—	$211,507	—
Garden apartments	Phase 1 — infrastructure + apartments	Soft costs	SC	Marketing, lease-up / rent-up (excl. commercial leasing commissions)	1	% of hard	—	$564,018	—
Garden apartments	Phase 1 — infrastructure + apartments	Soft costs	SC	Construction-loan title, closing & recording	1	% of hard	—	$282,009	—
Garden apartments	Phase 1 — infrastructure + apartments	Soft costs	SC	Special inspections, materials testing, commissioning	1	% of hard	—	$564,018	—
Garden apartments	Phase 1 — infrastructure + apartments	Soft costs	SC	Owner's representative / project management	2	% of hard	—	$1,057,533	—
Garden apartments	Phase 1 — infrastructure + apartments	Soft costs	SC	Third-party reports (appraisal, Phase I ESA, market study, PCA/CNA)	1	project	$21,000.00	$21,000	—
Garden apartments	Phase 1 — infrastructure + apartments	Impact & tap fees	SC	Total impact fees — multifamily unit	300	unit	$7,874.30	$2,362,290	—
Garden apartments	Phase 1 — infrastructure + apartments	Impact & tap fees	SC	Water capacity / tap / impact fee	180	EDU	$3,407.22	$613,300	—
Garden apartments	Phase 1 — infrastructure + apartments	Impact & tap fees	SC	Sewer (wastewater) capacity / tap / impact fee	180	EDU	$3,407.22	$613,300	—
Grocery-anchored center	Phase 1 — infrastructure + apartments	Contingency	99 02 00	Design contingency	5	% of hard	—	$86,142	—
Grocery-	Phase 1 — infrastructure	Contingency	99 03	Hard cost (construction) contingency	5	% of hard	—	$90,450	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
anchored center	+ apartments		00						
Grocery-anchored center	Phase 1 — infrastructure + apartments	Soft costs	SC	Architecture & engineering (basic services, design + CA)	8	% of hard	—	$133,714	—
Grocery-anchored center	Phase 1 — infrastructure + apartments	Soft costs	SC	Civil engineering, ALTA/topo survey, geotechnical report	1	% of hard	—	$20,571	—
Grocery-anchored center	Phase 1 — infrastructure + apartments	Soft costs	SC	Building permit & plan review fees (excl. impact / tap fees)	1	% of hard	—	$20,571	—
Grocery-anchored center	Phase 1 — infrastructure + apartments	Soft costs	SC	Legal, accounting, cost certification	1	% of hard	—	$14,400	—
Grocery-anchored center	Phase 1 — infrastructure + apartments	Soft costs	SC	Builder's risk insurance	0	% of hard	—	$8,229	—
Grocery-anchored center	Phase 1 — infrastructure + apartments	Soft costs	SC	Owner's general liability / OCIP-OCP during construction	0	% of hard	—	$6,171	—
Grocery-anchored center	Phase 1 — infrastructure + apartments	Soft costs	SC	Marketing, lease-up / rent-up (excl. commercial leasing commissions)	1	% of hard	—	$16,457	—
Grocery-anchored center	Phase 1 — infrastructure + apartments	Soft costs	SC	Construction-loan title, closing & recording	0	% of hard	—	$8,229	—
Grocery-anchored center	Phase 1 — infrastructure + apartments	Soft costs	SC	Special inspections, materials testing, commissioning	1	% of hard	—	$16,457	—
Grocery-anchored center	Phase 1 — infrastructure + apartments	Soft costs	SC	Owner's representative / project management	2	% of hard	—	$30,857	—
Grocery-anchored center	Phase 2 — townhomes + retail	Contingency	99 02 00	Design contingency	5	% of hard	—	$613,072	—
Grocery-anchored center	Phase 2 — townhomes + retail	Contingency	99 03 00	Hard cost (construction) contingency	5	% of hard	—	$643,726	—
Grocery-anchored center	Phase 2 — townhomes + retail	Soft costs	SC	Architecture & engineering (basic services, design + CA)	8	% of hard	—	$951,634	—
Grocery-anchored center	Phase 2 — townhomes + retail	Soft costs	SC	Civil engineering, ALTA/topo survey, geotechnical report	1	% of hard	—	$146,405	—
Grocery-anchored center	Phase 2 — townhomes + retail	Soft costs	SC	Building permit & plan review fees (excl. impact / tap fees)	1	% of hard	—	$146,405	—
Grocery-anchored center	Phase 2 — townhomes + retail	Soft costs	SC	Legal, accounting, cost certification	1	% of hard	—	$102,484	—
Grocery-anchored center	Phase 2 — townhomes + retail	Soft costs	SC	Builder's risk insurance	0	% of hard	—	$58,562	—
Grocery-anchored center	Phase 2 — townhomes + retail	Soft costs	SC	Owner's general liability / OCIP-OCP during construction	0	% of hard	—	$43,922	—
Grocery-anchored center	Phase 2 — townhomes + retail	Soft costs	SC	Marketing, lease-up / rent-up (excl. commercial leasing commissions)	1	% of hard	—	$117,124	—
Grocery-anchored center	Phase 2 — townhomes + retail	Soft costs	SC	Construction-loan title, closing & recording	0	% of hard	—	$58,562	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Grocery-anchored center	Phase 2 — townhomes + retail	Soft costs	SC	Special inspections, materials testing, commissioning	1	% of hard	—	$117,124	—
Grocery-anchored center	Phase 2 — townhomes + retail	Soft costs	SC	Owner's representative / project management	2	% of hard	—	$219,608	—
Grocery-anchored center	Phase 2 — townhomes + retail	Soft costs	SC	Third-party reports (appraisal, Phase I ESA, market study, PCA/CNA)	1	project	$21,000.00	$21,000	—
Grocery-anchored center	Phase 2 — townhomes + retail	Impact & tap fees	SC	Total impact fees — retail	65	1,000 SF	$7,020.26	$456,317	—
Grocery-anchored center	Phase 2 — townhomes + retail	Impact & tap fees	SC	Water capacity / tap / impact fee	16	EDU	$3,407.22	$55,367	—
Grocery-anchored center	Phase 2 — townhomes + retail	Impact & tap fees	SC	Sewer (wastewater) capacity / tap / impact fee	16	EDU	$3,407.22	$55,367	—
Rental townhomes	Phase 1 — infrastructure + apartments	Contingency	99 02 00	Design contingency	3	% of hard	—	$40,553	—
Rental townhomes	Phase 1 — infrastructure + apartments	Contingency	99 03 00	Hard cost (construction) contingency	5	% of hard	—	$69,616	—
Rental townhomes	Phase 1 — infrastructure + apartments	Soft costs	SC	Architecture & engineering (basic services, design + CA)	7	% of hard	—	$95,077	—
Rental townhomes	Phase 1 — infrastructure + apartments	Soft costs	SC	Civil engineering, ALTA/topo survey, geotechnical report	1	% of hard	—	$14,627	—
Rental townhomes	Phase 1 — infrastructure + apartments	Soft costs	SC	Building permit & plan review fees (excl. impact / tap fees)	1	% of hard	—	$14,627	—
Rental townhomes	Phase 1 — infrastructure + apartments	Soft costs	SC	Legal, accounting, cost certification	1	% of hard	—	$10,239	—
Rental townhomes	Phase 1 — infrastructure + apartments	Soft costs	SC	Builder's risk insurance	0	% of hard	—	$5,851	—
Rental townhomes	Phase 1 — infrastructure + apartments	Soft costs	SC	Owner's general liability / OCIP-OCP during construction	0	% of hard	—	$4,388	—
Rental townhomes	Phase 1 — infrastructure + apartments	Soft costs	SC	Marketing, lease-up / rent-up (excl. commercial leasing commissions)	1	% of hard	—	$11,702	—
Rental townhomes	Phase 1 — infrastructure + apartments	Soft costs	SC	Construction-loan title, closing & recording	0	% of hard	—	$5,851	—
Rental townhomes	Phase 1 — infrastructure + apartments	Soft costs	SC	Special inspections, materials testing, commissioning	1	% of hard	—	$11,702	—
Rental townhomes	Phase 1 — infrastructure + apartments	Soft costs	SC	Owner's representative / project management	2	% of hard	—	$21,941	—
Rental townhomes	Phase 2 — townhomes + retail	Contingency	99 02 00	Design contingency	3	% of hard	—	$627,776	—
Rental townhomes	Phase 2 — townhomes + retail	Contingency	99 03 00	Hard cost (construction) contingency	5	% of hard	—	$1,077,682	—
Rental	Phase 2 — townhomes	Soft costs	SC	Architecture & engineering (basic services,	7	% of hard	—	$1,471,838	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
townhomes	+ retail			design + CA)					
Rental townhomes	Phase 2 — townhomes + retail	Soft costs	SC	Civil engineering, ALTA/topo survey, geotechnical report	1	% of hard	—	$226,437	—
Rental townhomes	Phase 2 — townhomes + retail	Soft costs	SC	Building permit & plan review fees (excl. impact / tap fees)	1	% of hard	—	$226,437	—
Rental townhomes	Phase 2 — townhomes + retail	Soft costs	SC	Legal, accounting, cost certification	1	% of hard	—	$158,506	—
Rental townhomes	Phase 2 — townhomes + retail	Soft costs	SC	Builder's risk insurance	0	% of hard	—	$90,575	—
Rental townhomes	Phase 2 — townhomes + retail	Soft costs	SC	Owner's general liability / OCIP-OCP during construction	0	% of hard	—	$67,931	—
Rental townhomes	Phase 2 — townhomes + retail	Soft costs	SC	Marketing, lease-up / rent-up (excl. commercial leasing commissions)	1	% of hard	—	$181,149	—
Rental townhomes	Phase 2 — townhomes + retail	Soft costs	SC	Construction-loan title, closing & recording	0	% of hard	—	$90,575	—
Rental townhomes	Phase 2 — townhomes + retail	Soft costs	SC	Special inspections, materials testing, commissioning	1	% of hard	—	$181,149	—
Rental townhomes	Phase 2 — townhomes + retail	Soft costs	SC	Owner's representative / project management	2	% of hard	—	$339,655	—
Rental townhomes	Phase 2 — townhomes + retail	Soft costs	SC	Third-party reports (appraisal, Phase I ESA, market study, PCA/CNA)	1	project	$21,000.00	$21,000	—
Rental townhomes	Phase 2 — townhomes + retail	Impact & tap fees	SC	Total impact fees — single-family detached	80	unit	$6,930.92	$554,474	—
Rental townhomes	Phase 2 — townhomes + retail	Impact & tap fees	SC	Water capacity / tap / impact fee	80	EDU	$3,407.22	$272,578	—
Rental townhomes	Phase 2 — townhomes + retail	Impact & tap fees	SC	Sewer (wastewater) capacity / tap / impact fee	80	EDU	$3,407.22	$272,578	—
Select-service hotel	Phase 1 — infrastructure + apartments	Contingency	SC	Soft cost contingency	5	% of soft	—	$3,742	—
Select-service hotel	Phase 3 — hotel	Contingency	SC	Soft cost contingency	5	% of soft	—	$179,265	—
Garden apartments	Phase 1 — infrastructure + apartments	Contingency	SC	Soft cost contingency	5	% of soft	—	$652,859	—
Grocery-anchored center	Phase 1 — infrastructure + apartments	Contingency	SC	Soft cost contingency	5	% of soft	—	$13,783	—
Grocery-anchored center	Phase 2 — townhomes + retail	Contingency	SC	Soft cost contingency	5	% of soft	—	$127,494	—
Rental townhomes	Phase 1 — infrastructure + apartments	Contingency	SC	Soft cost contingency	5	% of soft	—	$9,800	—
Rental townhomes	Phase 2 — townhomes + retail	Contingency	SC	Soft cost contingency	5	% of soft	—	$207,744	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Garden apartments	Phase 1 — infrastructure + apartments	Land	LAND	Land / acquisition	—	—	—	$5,101,348	—
Rental townhomes	Phase 2 — townhomes + retail	Land	LAND	Land / acquisition	—	—	—	$2,493,992	—
Grocery-anchored center	Phase 2 — townhomes + retail	Land	LAND	Land / acquisition	—	—	—	$2,431,642	—
Select-service hotel	Phase 3 — hotel	Land	LAND	Land / acquisition	—	—	—	$823,017	—
Garden apartments	Phase 1 — infrastructure + apartments	Land	LAND	Land closing costs	—	—	—	$102,027	—
Rental townhomes	Phase 2 — townhomes + retail	Land	LAND	Land closing costs	—	—	—	$49,880	—
Grocery-anchored center	Phase 2 — townhomes + retail	Land	LAND	Land closing costs	—	—	—	$48,633	—
Select-service hotel	Phase 3 — hotel	Land	LAND	Land closing costs	—	—	—	$16,460	—
Garden apartments	Phase 1 — infrastructure + apartments	Land	LAND	Land due diligence	—	—	—	$15,798	—
Rental townhomes	Phase 2 — townhomes + retail	Land	LAND	Land due diligence	—	—	—	$7,723	—
Grocery-anchored center	Phase 2 — townhomes + retail	Land	LAND	Land due diligence	—	—	—	$7,530	—
Select-service hotel	Phase 3 — hotel	Land	LAND	Land due diligence	—	—	—	$2,549	—
Garden apartments	Phase 1 — infrastructure + apartments	Soft costs	SC	Real estate taxes during construction	2	years	$56,114.83	$116,906	—
Rental townhomes	Phase 2 — townhomes + retail	Soft costs	SC	Real estate taxes during construction	1	years	$27,433.91	$32,006	—
Grocery-anchored center	Phase 2 — townhomes + retail	Soft costs	SC	Real estate taxes during construction	1	years	$26,748.07	$31,206	—
Select-service hotel	Phase 3 — hotel	Soft costs	SC	Real estate taxes during construction	2	years	$9,053.19	$14,334	—
Select-service hotel	Phase 1 — infrastructure + apartments	Developer fee	DEV	Developer fee	4	% of cost excl. land	—	$23,773	—
Select-service hotel	Phase 3 — hotel	Developer fee	DEV	Developer fee	4	% of cost excl. land	—	$994,969	—
Garden apartments	Phase 1 — infrastructure + apartments	Developer fee	DEV	Developer fee	4	% of cost excl. land	—	$3,002,962	—
Grocery-anchored center	Phase 1 — infrastructure + apartments	Developer fee	DEV	Developer fee	4	% of cost excl. land	—	$87,555	—
Grocery-	Phase 2 — townhomes	Developer fee	DEV	Developer fee	4	% of cost	—	$649,073	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
anchored center	+ retail					excl. land			
Select-service hotel	Phase 1 — infrastructure + apartments	Financing	FIN	Construction loan interest (capitalized)	—	—	—	$20,125	—
Garden apartments	Phase 1 — infrastructure + apartments	Financing	FIN	Construction loan interest (capitalized)	—	—	—	$2,712,018	—
Grocery-anchored center	Phase 1 — infrastructure + apartments	Financing	FIN	Construction loan interest (capitalized)	—	—	—	$74,118	—
Rental townhomes	Phase 1 — infrastructure + apartments	Financing	FIN	Construction loan interest (capitalized)	—	—	—	$54,299	—
Select-service hotel	Phase 1 — infrastructure + apartments	Financing	FIN	Construction loan fee	—	—	—	$3,852	—
Garden apartments	Phase 1 — infrastructure + apartments	Financing	FIN	Construction loan fee	—	—	—	$519,164	—
Grocery-anchored center	Phase 1 — infrastructure + apartments	Financing	FIN	Construction loan fee	—	—	—	$14,188	—
Rental townhomes	Phase 1 — infrastructure + apartments	Financing	FIN	Construction loan fee	—	—	—	$10,395	—
Grocery-anchored center	Phase 2 — townhomes + retail	Financing	FIN	Construction loan interest (capitalized)	—	—	—	$349,773	—
Rental townhomes	Phase 2 — townhomes + retail	Financing	FIN	Construction loan interest (capitalized)	—	—	—	$534,268	—
Grocery-anchored center	Phase 2 — townhomes + retail	Financing	FIN	Construction loan fee	—	—	—	$118,995	—
Rental townhomes	Phase 2 — townhomes + retail	Financing	FIN	Construction loan fee	—	—	—	$181,761	—
Select-service hotel	Phase 3 — hotel	Financing	FIN	Construction loan interest (capitalized)	—	—	—	$625,826	—
Select-service hotel	Phase 3 — hotel	Financing	FIN	Construction loan fee	—	—	—	$165,012	—
TOTAL				**Total project cost**				**$168,894,726**	

Draw Schedules

PHASE 1 — INFRASTRUCTURE + APARTMENTS — MONTHLY DRAWS

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE
2027-04	$0	$9,427,176	$5,219,173	$15,193,949	$0	$0	$0
2027-05	$256,762	$323,516	$0	$580,278	$0	$0	$0
2027-06	$766,237	$323,516	$0	$1,089,752	$0	$0	$0
2027-07	$1,263,627	$323,516	$0	$1,587,143	$0	$0	$0

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE
2027-08	$1,741,090	$323,516	$0	$2,064,606	$0	$0	$0
2027-09	$2,191,094	$323,516	$0	$2,514,610	$0	$0	$0
2027-10	$2,606,544	$323,516	$0	$2,930,059	$0	$0	$0
2027-11	$2,980,887	$323,516	$0	$3,304,403	$0	$0	$0
2027-12	$3,308,219	$323,516	$0	$3,631,735	$0	$0	$0
2028-01	$3,583,379	$323,516	$0	$3,610,116	$296,779	$0	$296,779
2028-02	$3,802,027	$323,516	$0	$0	$4,125,543	$1,731	$4,424,053
2028-03	$3,960,714	$323,516	$0	$0	$4,284,230	$25,807	$8,734,090
2028-04	$4,056,939	$323,516	$0	$0	$4,380,455	$50,949	$13,165,494
2028-05	$4,089,184	$323,516	$0	$0	$4,412,700	$76,799	$17,654,992
2028-06	$4,056,939	$323,516	$0	$0	$4,380,455	$102,987	$22,138,435
2028-07	$3,960,714	$323,516	$0	$0	$4,284,230	$129,141	$26,551,806
2028-08	$3,802,027	$323,516	$0	$0	$4,125,543	$154,886	$30,832,234
2028-09	$3,583,379	$323,516	$0	$0	$3,906,895	$179,855	$34,918,983
2028-10	$3,308,219	$323,516	$0	$0	$3,631,735	$203,694	$38,754,412
2028-11	$2,980,887	$323,516	$0	$0	$3,304,402	$226,067	$42,284,882
2028-12	$2,606,544	$323,516	$0	$0	$2,930,060	$246,662	$45,461,603
2029-01	$2,191,094	$323,516	$0	$0	$2,514,610	$265,193	$48,241,406
2029-02	$1,741,090	$323,516	$0	$0	$2,064,606	$281,408	$50,587,420
2029-03	$1,263,627	$323,516	$0	$0	$1,587,143	$295,093	$52,469,656
2029-04	$766,237	$323,516	$0	$0	$1,089,752	$306,073	$53,865,481
2029-05	$256,762	$323,516	$0	$0	$580,278	$314,215	$54,759,974

PHASE 2 — TOWNHOMES + RETAIL — MONTHLY DRAWS

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE
2029-05	$0	$4,616,847	$5,039,401	$9,957,005	$0	$0	$0
2029-06	$453,173	$223,960	$0	$677,132	$0	$0	$0
2029-07	$1,336,794	$223,960	$0	$1,560,754	$0	$0	$0
2029-08	$2,153,382	$223,960	$0	$2,377,342	$0	$0	$0
2029-09	$2,861,992	$223,960	$0	$3,085,951	$0	$0	$0
2029-10	$3,427,089	$223,960	$0	$2,392,236	$1,258,813	$0	$1,258,813
2029-11	$3,820,337	$223,960	$0	$0	$4,044,297	$7,343	$5,310,453
2029-12	$4,022,018	$223,960	$0	$0	$4,245,978	$30,978	$9,587,408
2030-01	$4,022,018	$223,960	$0	$0	$4,245,978	$55,927	$13,889,312

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE
2030-02	$3,820,337	$223,960	$0	$0	$4,044,297	$81,021	$18,014,630
2030-03	$3,427,089	$223,960	$0	$0	$3,651,048	$105,085	$21,770,763
2030-04	$2,861,992	$223,960	$0	$0	$3,085,951	$126,996	$24,983,711
2030-05	$2,153,382	$223,960	$0	$0	$2,377,342	$145,738	$27,506,791
2030-06	$1,336,794	$223,960	$0	$0	$1,560,754	$160,456	$29,228,001
2030-07	$453,173	$223,960	$0	$0	$677,132	$170,497	$30,075,630

PHASE 3 — HOTEL — MONTHLY DRAWS

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE
2030-07	$0	$2,298,618	$842,027	$3,305,656	$0	$0	$0
2030-08	$143,856	$130,276	$0	$274,132	$0	$0	$0
2030-09	$427,645	$130,276	$0	$557,921	$0	$0	$0
2030-10	$699,769	$130,276	$0	$830,045	$0	$0	$0
2030-11	$952,805	$130,276	$0	$1,083,081	$0	$0	$0
2030-12	$1,179,850	$130,276	$0	$1,310,126	$0	$0	$0
2031-01	$1,374,713	$130,276	$0	$1,504,989	$0	$0	$0
2031-02	$1,532,077	$130,276	$0	$1,662,353	$0	$0	$0
2031-03	$1,647,650	$130,276	$0	$472,518	$1,305,408	$0	$1,305,408
2031-04	$1,718,279	$130,276	$0	$0	$1,848,555	$7,615	$3,161,578
2031-05	$1,742,038	$130,276	$0	$0	$1,872,314	$18,443	$5,052,335
2031-06	$1,718,279	$130,276	$0	$0	$1,848,555	$29,472	$6,930,362
2031-07	$1,647,650	$130,276	$0	$0	$1,777,926	$40,427	$8,748,715
2031-08	$1,532,077	$130,276	$0	$0	$1,662,353	$51,034	$10,462,102
2031-09	$1,374,713	$130,276	$0	$0	$1,504,989	$61,029	$12,028,120
2031-10	$1,179,850	$130,276	$0	$0	$1,310,126	$70,164	$13,408,410
2031-11	$952,805	$130,276	$0	$0	$1,083,081	$78,216	$14,569,706
2031-12	$699,769	$130,276	$0	$0	$830,045	$84,990	$15,484,741
2032-01	$427,645	$130,276	$0	$0	$557,921	$90,328	$16,132,990
2032-02	$143,856	$130,276	$0	$0	$274,132	$94,109	$16,501,231

Sources & Assumptions

ASSUMPTIONS

Garden apartments — baseline price	**$195,000 / unit · Researched (residential/garden-multifamily.json)**
Garden apartments — factors	**regional 0.84 · quality 1 · size 0.9855 · escalation 1.0766**
Garden apartments — research note	**2-4 story Type V wood-frame walk-ups on surface parking - the lowest-cost multifamily product; cost is driven by framing, MEP, finishes and a meaningful (~12-14%) on-site development share. Good data: an elemental breakdown from RAND (Trammell Crow Residential garden projects), RLB city ranges, RSMeans, a Florida HFA hard-cost factor and several developer/contractor ranges; per-unit market-rate data are thinner than per-SF data.**
Rental townhomes — baseline price	**$282,236 / unit · Researched (residential/townhomes.json)**
Rental townhomes — factors	**regional 0.84 · quality 1 · size 0.9631 · escalation 1.1456**
Rental townhomes — research note	**Attached 2–3 story wood-frame townhouses, for sale or rent. Shared party walls save exterior envelope and lot area. Rated fire separations, more stairs and higher kitchen/bath density per SF offset part of that, so per-SF cost is close to detached homes. National data is indirect: Census sale prices for attached homes, translated with NAHB cost shares. The only direct cost points are permit valuations and a builder survey from Washington State. Confidence is medium.**
Grocery-anchored center — baseline price	**$175 / SF · Derived estimate — verify (commercial/grocery-anchored-center.json)**
Grocery-anchored center — factors	**regional 0.84 · quality 1 · size 1.0264 · escalation 1.1456**
Grocery-anchored center — research note	**Neighborhood center (60,000–150,000 SF) with a 40,000–65,000 SF supermarket anchor plus in-line shops and outparcels. The landlord typically delivers the anchor as a shell/pad (grocer funds refrigeration and fixtures) and builds a large parking field. No public development budget was retrieved; cost is derived from RLB strip/center ranges and RSMeans supermarket/store models.**
Select-service hotel — baseline price	**$146,345 / key · Researched (hospitality/hotel-select-service.json)**
Select-service hotel — factors	**regional 0.84 · quality 1 · size 1.0036 · escalation 1.211**
Select-service hotel — research note	**Branded 4–5 story select/limited-service hotel (Hampton / Courtyard class) of ~80–160 keys with breakfast area, small meeting room, fitness and pool; cost is driven by guestroom count, framing system (wood vs. concrete/steel) and market. Data quality is good: four editions of the HVS U.S. Hotel Development Cost Survey (2022–2025 data) give national per-key medians by component, cross-checked with RLB Q2 2026 3-star $/SF and an HVS feasibility budget. HVS building costs include permits, engineering and hard contingency, so they are scaled to our hard-cost definition.**
Phase 1 — infrastructure + apartments — schedule	**2027-04, 25 months, midpoint 2028-05, escalation 7.66% (forecast rates from _indices/escalation.json)**
Phase 1 — infrastructure + apartments — financing	**LTC 60%, rate 7.00%, fee 1.00%**
Phase 2 — townhomes + retail — schedule	**2029-05, 14 months, midpoint 2029-12, escalation 14.56% (forecast rates from _indices/escalation.json)**
Phase 2 — townhomes + retail — financing	**LTC 60%, rate 7.00%, fee 1.00%**
Phase 3 — hotel — schedule	**2030-07, 19 months, midpoint 2031-05, escalation 21.10% (forecast rates from _indices/escalation.json)**
Phase 3 — hotel — financing	**LTC 60%, rate 7.00%, fee 1.00%**

SOURCES (96)

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_blocks/ amenities.json#e18	Community Center — RSMeans model page	Gordian / RSMeans	145.11 USD/sf (2019)	medium	https://www.rsmeans.com/model-pages/community-center

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_blocks/amenities.json#e19	Country Club — RSMeans model page	Gordian / RSMeans	221.79 USD/sf (2019)	medium	https://www.rsmeans.com/model-pages/country-club
_blocks/amenities.json#e20	Social Club — RSMeans model page	Gordian / RSMeans	168.47 USD/sf (2019)	medium	https://www.rsmeans.com/model-pages/social-club
_blocks/paving.json#e1	Item Average Unit Cost, From 2025/09/01 to 2026/08/31, Statewide (historical-item-averages-statewide-12-months)	Florida Department of Transportation	136.23 USD/ton (2026)	high	https://fdotwww.blob.core.windows.net/sitefinity/docs/default-source/fpo/fpc/reports/historicalitemaveragecost/moving/statewide/pdf/historical-item-averages-statewide-12-months.pdf?sfvrsn=32501f5b_15
_blocks/paving.json#e2	Item Average Unit Cost, From 2025/09/01 to 2026/08/31, Statewide (historical-item-averages-statewide-12-months)	Florida Department of Transportation	17.5 USD/sy (2026)	high	https://fdotwww.blob.core.windows.net/sitefinity/docs/default-source/fpo/fpc/reports/historicalitemaveragecost/moving/statewide/pdf/historical-item-averages-statewide-12-months.pdf?sfvrsn=32501f5b_15
_blocks/paving.json#e4	Item Average Unit Cost, From 2025/09/01 to 2026/08/31, Statewide (historical-item-averages-statewide-12-months)	Florida Department of Transportation	38.56 USD/lf (2026)	high	https://fdotwww.blob.core.windows.net/sitefinity/docs/default-source/fpo/fpc/reports/historicalitemaveragecost/moving/statewide/pdf/historical-item-averages-statewide-12-months.pdf?sfvrsn=32501f5b_15
_blocks/paving.json#e5	Weighted Average Unit Prices from 6/25/2025 to 6/24/2026	Arkansas Department of Transportation, Program Management Division	31.25 USD/lf (2025)	high	https://media.ark.org/ardot/June-24-2026-Weighted-Averages-Prices.pdf
_blocks/signage.json#e2	Signage Cost for Business: How Much Should You Expect to Pay?	BlinkSigns	5000–15000 USD/ea (2023)	low	https://blinksigns.com/signage-cost-for-business-how-much-should-you-expect-to-pay/
_blocks/stormwater.json#e1	Stormwater Best Management Practice: Dry Detention Ponds (EPA-832-F-21-031A, December 2021)	U.S. Environmental Protection Agency, Office of Water (NPDES)	45000–80000 USD/acre (2021)	medium	https://www.epa.gov/system/files/documents/2021-11/bmp-dry-detention-ponds.pdf
_blocks/stormwater.json#e2	Stormwater Best Management Practice: Wet Ponds (EPA-832-F-21-031BB, December 2021)	U.S. Environmental Protection Agency, Office of Water (NPDES)	35000–75000 USD/acre (2021)	medium	https://www.epa.gov/system/files/documents/2021-11/bmp-wet-ponds.pdf
_blocks/utilities.json#e1	Item Average Unit Cost, From 2025/09/01 to 2026/08/31, Statewide (historical-item-averages-statewide-12-months)	Florida Department of Transportation	115.6 USD/lf (2026)	medium	https://fdotwww.blob.core.windows.net/sitefinity/docs/default-source/fpo/fpc/reports/historicalitemaveragecost/moving/statewide/pdf/historical-item-averages-statewide-12-months.pdf?sfvrsn=32501f5b_15
_blocks/utilities.json#e7	Item Average Unit Cost, From 2025/09/01 to 2026/08/31, Statewide (historical-item-averages-statewide-12-months)	Florida Department of Transportation	8295.47 USD/ea (2026)	high	https://fdotwww.blob.core.windows.net/sitefinity/docs/default-source/fpo/fpc/reports/historicalitemaveragecost/moving/statewide/pdf/historical-item-averages-statewide-12-months.pdf?sfvrsn=32501f5b_15

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_common/fees.json#e1	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	13627 USD/unit (2019)	high	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/fees.json#e2	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	6460 USD/unit (2019)	medium	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/fees.json#e3	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	8034 USD/unit (2019)	high	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/fees.json#e4	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	6760 USD/1000sf (2019)	high	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/fees.json#e5	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	5408 USD/1000sf (2019)	high	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/fees.json#e8	Impact Fee Primer (March 2025)	National Association of Home Builders (by Launch Development Finance Advisors)	13627 USD/unit (2019)	medium	https://www.nahb.org/advocacy/industry-issues/land-use-101/tools-and-research/tools-pages/impact-fee-primer
_common/fees.json#e9	It All Adds Up: The Cost of Housing Development Fees in Seven California Cities	Terner Center for Housing Innovation, UC Berkeley (March 2018)	12000–75000 USD/unit (2018)	high	https://ternercenter.berkeley.edu/wp-content/uploads/2020/08/Development_Fees_Report_Final_2.pdf
_common/financing.json#e1	Secured Overnight Financing Rate (SOFR)	Federal Reserve Bank of St. Louis (FRED)	0.039 pct (2026)	high	https://fred.stlouisfed.org/series/SOFR
_common/financing.json#e2	30-Day Average SOFR (SOFR30DAYAVG)	Federal Reserve Bank of St. Louis (FRED)	0.03889 pct (2026)	high	https://fred.stlouisfed.org/series/SOFR30DAYAVG
_common/financing.json#e3	Bank Prime Loan Rate (DPRIME)	Federal Reserve Bank of St. Louis (FRED)	0.07 pct (2026)	high	https://fred.stlouisfed.org/series/DPRIME
_common/financing.json#e4	Federal Funds Target Range - Upper Limit (DFEDTARU)	Federal Reserve Bank of St. Louis (FRED)	0.0375–0.04 pct (2026)	high	https://fred.stlouisfed.org/series/DFEDTARU
_common/financing.json#e5	12 CFR Appendix A to Subpart A of Part 365 - Interagency Guidelines for Real Estate Lending Policies	Legal Information Institute, Cornell Law School (text of FDIC regulation)	0.8 pct	high	https://www.law.cornell.edu/cfr/text/12/appendix-A_to_subpart_A_of_part_365
_common/financing.json#e6	The July 2026 Senior Loan Officer Opinion Survey on Bank Lending Practices	Board of Governors of the Federal Reserve System	text (2026)	high	https://www.federalreserve.gov/data/sloos/sloos-202607.htm
_common/land-closing.json#e1	Title Rate Chart (effective March 1, 2026)	Texas Department of Insurance	5226 USD/policy (2026)	high	https://www.tdi.texas.gov/title/titlerates2026.html
_common/land-	Real estate excise tax	Washington State	0.0128 pct	high	https://dor.wa.gov/taxes-rates/other-taxes/real-estate-excise-tax

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
closing.json#e2		Department of Revenue	(2026)		
_common/land-closing.json#e3	Realty Transfer Tax	Pennsylvania Department of Revenue	0.01 pct (2026)	high	https://www.pa.gov/en/agencies/revenue/resources/tax-types-and-information/realty-transfer-tax.html
_common/land-closing.json#e4	Documentary Stamp Tax	Florida Department of Revenue	0.007 pct (2026)	high	https://floridarevenue.com/taxes/taxesfees/Pages/doc_stamp.aspx
_common/land-closing.json#e5	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	text (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e1	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0852 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e10	Builders Risk Insurance in 2026: What It Costs, Who Pays, and the Exclusions That Wreck Commercial Projects	Terrapin Construction Group	0.0035–0.009 pct (2026)	low	https://terrapincg.com/news/builders-risk-insurance-commercial-construction-cost-2026
_common/soft-costs.json#e11	Builders Risk Insurance in 2026: What It Costs, Who Pays, and the Exclusions That Wreck Commercial Projects	Terrapin Construction Group	0.0007–0.0019 pct (2026)	low	https://terrapincg.com/news/builders-risk-insurance-commercial-construction-cost-2026
_common/soft-costs.json#e13	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	text (2025)	medium	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e14	What are Typical Developer Fees on a Multifamily Development?	HelloData	0.03–0.05 pct (2025)	low	https://www.hellodata.ai/help-articles/what-are-typical-developer-fees-on-a-multifamily-development
_common/soft-costs.json#e15	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	0.15 pct (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
_common/soft-costs.json#e16	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	0.15 pct (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e17	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	1200 USD/unit (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e18	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	500 USD/unit (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
_common/soft-costs.json#e19	Title Rate Chart (effective March 1, 2026)	Texas Department of Insurance	0.005226 pct (2026)	high	https://www.tdi.texas.gov/title/titlerates2026.html

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_common/soft-costs.json#e2	Chapter 08: Architect/ Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0988 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e20	Documentary Stamp Tax	Florida Department of Revenue	0.0035 pct (2026)	high	https://floridarevenue.com/taxes/taxesfees/Pages/doc_stamp.aspx
_common/soft-costs.json#e21	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.01 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e3	Chapter 08: Architect/ Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0716 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e4	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	0.0483 pct (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e5	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.06 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e6	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.12 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e7	Building Valuation Data – August 2025	International Code Council (posted by City of Kirkland, WA)	0.0075 pct (2025)	low	https://www.kirklandwa.gov/files/sharedassets/public/v/2/development-services/pdfs/building-pdfs/icc-august-2025.pdf
_common/soft-costs.json#e8	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	175000 USD/ project (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e9	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	150000 USD/ project (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
commercial/grocery-anchored-center.json#e1	North America Quarterly Construction Cost Report, Q3 2026 (Indicative Construction Costs table)	Rider Levett Bucknall (RLB)	200–270 USD/sf (2026)	high	https://www.rlb.com/wp-content/uploads/sites/4/2026/09/Q3-2026-QCR.pdf
commercial/grocery-anchored-center.json#e2	North America Quarterly Construction Cost Report, Q3 2026 (Indicative Construction Costs table)	Rider Levett Bucknall (RLB)	215–355 USD/sf (2026)	high	https://www.rlb.com/wp-content/uploads/sites/4/2026/09/Q3-2026-QCR.pdf
commercial/grocery-	Construction Cost Estimates	Gordian / RSMeans	141.15 USD/sf	medium	https://www.rsmeans.com/model-pages/supermarket.aspx

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
anchored-center.json#e3	for a Supermarket in National, US (2019 RSMeans data)		(2019)		
commercial/grocery-anchored-center.json#e4	2022 Project Costs — 50 17 00 Project Costs per S.F.	Gordian / RSMeans	171 USD/sf (2022)	high	https://www.rsmeans.com/media/wysiwyg/quarterly_updates/2022-Project-Costs-per-Square-Foot.pdf
commercial/grocery-anchored-center.json#e5	U.S. Retail Fit Out Cost Guide (2026)	Cushman & Wakefield	157 USD/sf (2026)	high	https://www.cushmanwakefield.com/en/united-states/insights/retail-fit-out-cost-guide
commercial/grocery-anchored-center.json#e6	Construction Cost Estimates for a Store, Retail in National, US (2019 RSMeans data)	Gordian / RSMeans	151.29 USD/sf (2019)	medium	https://www.rsmeans.com/model-pages/retail-store.aspx
commercial/grocery-anchored-center.json#e7	Office building construction costs for 2026	Building Design + Construction (data: Gordian RSMeans)	253.63 USD/sf (2026)	medium	https://www.bdcnetwork.com/construction-costs/article/55389026/office-building-construction-costs-for-2026
commercial/grocery-anchored-center.json#e8	Construction Cost Trends / 2025 — Houston	Kirksey Architecture	16–22 USD/sf (2025)	medium	https://www.kirksey.com/CMSPages/GetFile.aspx?guid=1c8a21ff-de0e-4629-b9b0-7f38f62c502b
hospitality/hotel-select-service.json#e1	HVS U.S. Hotel Development Cost Survey 2026	HVS	126900 USD/key (2025)	high	https://www.hvs.com/article/10509-HVS-US-Hotel-Development-Cost-Survey-2026
hospitality/hotel-select-service.json#e11	Hotel, 4-7 Story with Brick Veneer / Reinforced Concrete — square foot model	Gordian RSMeans	197.45 USD/sf (2019)	medium	https://www.rsmeans.com/model-pages/hotel-4-7-story
hospitality/hotel-select-service.json#e12	HVS U.S. Hotel Development Cost Survey 2026	HVS	18321 USD/key (2025)	high	https://www.hvs.com/article/10509-HVS-US-Hotel-Development-Cost-Survey-2026
hospitality/hotel-select-service.json#e13	HVS U.S. Hotel Development Cost Survey 2026	HVS	16079 USD/key (2025)	high	https://www.hvs.com/article/10509-HVS-US-Hotel-Development-Cost-Survey-2026
hospitality/hotel-select-service.json#e14	HVS U.S. Hotel Development Cost Survey 2025	HVS	22929 USD/key (2024)	high	https://www.hvs.com/article/10219-hvs-us-hotel-development-cost-survey-2025
hospitality/hotel-select-service.json#e15	Feasibility Study — Proposed Limited-Service Hotel, Murrieta, California (May 2022)	HVS for City of Murrieta	17000 USD/key (2022)	high	https://www.murrietaca.gov/DocumentCenter/View/7349/HVS-Feasibility-Study-2022---Proposed-Limited-Service-Hotel-PDF
hospitality/hotel-select-service.json#e16	HVS U.S. Hotel Development Cost Survey 2026	HVS	21002 USD/key (2025)	high	https://www.hvs.com/article/10509-HVS-US-Hotel-Development-Cost-Survey-2026
hospitality/hotel-select-service.json#e17	HVS U.S. Hotel Development Cost Survey 2026	HVS	19896 USD/key (2025)	high	https://www.hvs.com/article/10509-HVS-US-Hotel-Development-Cost-Survey-2026
hospitality/hotel-select-service.json#e18	HVS U.S. Hotel Development Cost Survey 2025	HVS	24833 USD/key (2024)	high	https://www.hvs.com/article/10219-hvs-us-hotel-development-cost-survey-2025
hospitality/hotel-	Feasibility Study — Proposed	HVS for City of	30000 USD/	high	https://www.murrietaca.gov/DocumentCenter/View/7349/HVS-

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
select-service.json#e19	Limited-Service Hotel, Murrieta, California (May 2022)	Murrieta	key (2022)		Feasibility-Study-2022---Proposed-Limited-Service-Hotel-PDF
hospitality/hotel-select-service.json#e2	HVS U.S. Hotel Development Cost Survey 2026	HVS	141143 USD/key (2025)	high	https://www.hvs.com/article/10509-HVS-US-Hotel-Development-Cost-Survey-2026
hospitality/hotel-select-service.json#e20	HVS U.S. Hotel Development Cost Survey 2026	HVS	3561 USD/key (2025)	high	https://www.hvs.com/article/10509-HVS-US-Hotel-Development-Cost-Survey-2026
hospitality/hotel-select-service.json#e21	HVS U.S. Hotel Development Cost Survey 2026	HVS	2900 USD/key (2025)	high	https://www.hvs.com/article/10509-HVS-US-Hotel-Development-Cost-Survey-2026
hospitality/hotel-select-service.json#e22	HVS U.S. Hotel Development Cost Survey 2025	HVS	5894 USD/key (2024)	high	https://www.hvs.com/article/10219-hvs-us-hotel-development-cost-survey-2025
hospitality/hotel-select-service.json#e23	Feasibility Study — Proposed Limited-Service Hotel, Murrieta, California (May 2022)	HVS for City of Murrieta	4000 USD/key (2022)	high	https://www.murrietaca.gov/DocumentCenter/View/7349/HVS-Feasibility-Study-2022---Proposed-Limited-Service-Hotel-PDF
hospitality/hotel-select-service.json#e3	HVS U.S. Hotel Development Cost Survey 2025	HVS	159636 USD/key (2024)	high	https://www.hvs.com/article/10219-hvs-us-hotel-development-cost-survey-2025
hospitality/hotel-select-service.json#e31	Hotel Cost Estimating Guide 2021	Nehmer and HVS Design	11948–17563 USD/ea (2021)	medium	https://www.hvs.com/WebContent/bookstore/HVS%20Hotel%20Cost%20Estimating%20Guide%202021.pdf
hospitality/hotel-select-service.json#e4	HVS U.S. Hotel Development Cost Survey 2025	HVS	111846 USD/key (2024)	high	https://www.hvs.com/article/10219-hvs-us-hotel-development-cost-survey-2025
hospitality/hotel-select-service.json#e5	HVS U.S. Hotel Development Cost Survey 2024	HVS	161216 USD/key (2023)	high	https://www.hvs.com/article/9999-hvs-us-hotel-development-cost-survey-2024
hospitality/hotel-select-service.json#e6	HVS U.S. Hotel Development Cost Survey 2023	HVS	161853 USD/key (2022)	high	https://www.hvs.com/article/9704-hvs-us-hotel-development-cost-survey-2023
hospitality/hotel-select-service.json#e7	Feasibility Study — Proposed Limited-Service Hotel, Murrieta, California (May 2022)	HVS for City of Murrieta	120000 USD/key (2022)	high	https://www.murrietaca.gov/DocumentCenter/View/7349/HVS-Feasibility-Study-2022---Proposed-Limited-Service-Hotel-PDF
hospitality/hotel-select-service.json#e8	North America Quarterly Construction Cost Report, Q2 2026	Rider Levett Bucknall	406 USD/sf (2026)	medium	https://www.rlb.com/wp-content/uploads/sites/4/2026/06/Q2-2026-QCR_7.7.2026.pdf
residential/garden-multifamily.json#e12	Total Development Cost per Unit Limitation Template, Version 09-30-2026 (for all RFAs starting July 2023), 'Data' sheet	Florida Housing Finance Corporation	256000–284000 USD/unit (2026)	medium	https://www.floridahousing.org/docs/default-source/programs/developers-multifamily-programs/competitive/total-development-cost-per-unit-limitation-template-effective-september-30-2026-for-all-rfa-s-starting-july-2023.xlsx
residential/garden-multifamily.json#e15	The High Cost of Producing Multifamily Housing in California (RAND RR-A3743-1, Ward & Schlake, 2025) - copy hosted by San Diego Housing Commission	RAND Corporation	0.19–0.33 ratio	high	https://sdhc.org/wp-content/uploads/2025/04/Att-2_RAND_RRA3743-1.pdf

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
residential/garden-multifamily.json#e16	Making apartments more affordable starts with understanding the costs of building them (Hoyt & Schuetz, May 5, 2020)	Brookings Institution	0.2–0.3 pct	medium	https://www.brookings.edu/research/making-apartments-more-affordable-starts-with-understanding-the-costs-of-building-them/
residential/garden-multifamily.json#e17	The High Cost of Producing Multifamily Housing in California (RAND RR-A3743-1, Ward & Schlake, 2025) - copy hosted by San Diego Housing Commission	RAND Corporation	1.98 USD/nrsf (2019)	high	https://sdhc.org/wp-content/uploads/2025/04/Att-2_RAND_RRA3743-1.pdf
residential/garden-multifamily.json#e2	RLB Construction Cost Report North America Q3 2026 (PDF), Indicative Construction Costs table	Rider Levett Bucknall	195–285 USD/sf (2026)	high	https://www.rlb.com/wp-content/uploads/sites/4/2026/09/Q3-2026-QCR.pdf
residential/garden-multifamily.json#e3	RLB Construction Cost Report North America Q3 2026 (PDF), Indicative Construction Costs table	Rider Levett Bucknall	205–305 USD/sf (2026)	high	https://www.rlb.com/wp-content/uploads/sites/4/2026/09/Q3-2026-QCR.pdf
residential/garden-multifamily.json#e5	Which multifamily product type is right for your site	LandSouth Construction	130–190 USD/sf (2026)	low	https://landsouth.com/which-multifamily-product-type-is-right-for-your-site/
residential/garden-multifamily.json#e6	Garden vs mid-rise vs high-rise density economics	Apers	150–210 USD/sf (2026)	low	https://apers.app/learn/asset-classes/multifamily/garden-vs-midrise-vs-highrise-density-economics
residential/garden-multifamily.json#e7	Multi-Family Wood-Frame Construction Cost Per Unit (2026): Type V, Podium, and Mid-Rise	Terrapin Construction Group	195000–425000 USD/unit (2026)	low	https://terrapincg.com/news/multi-family-wood-frame-construction-cost-per-unit-2026
residential/garden-multifamily.json#e8	The High Cost of Producing Multifamily Housing in California (RAND RR-A3743-1, Ward & Schlake, 2025) - copy hosted by San Diego Housing Commission	RAND Corporation	109.12 USD/nrsf (2019)	high	https://sdhc.org/wp-content/uploads/2025/04/Att-2_RAND_RRA3743-1.pdf
residential/single-family.json#e10	Cost of Constructing a Home-2024 (Special Study for Housing Economics)	National Association of Home Builders (Eric Lynch)	26747 USD/unit (2024)	high	https://nahb.org/-/media/AB4EFC742624475A97A0A62189986FF8.ashx
residential/single-family.json#e3	Cost of Constructing a Home-2024 (Special Study for Housing Economics)	National Association of Home Builders (Eric Lynch)	text (2024)	high	https://nahb.org/-/media/AB4EFC742624475A97A0A62189986FF8.ashx
residential/single-family.json#e9	Cost of Constructing a Home-2024 (Special Study for Housing Economics)	National Association of Home Builders (Eric Lynch)	text (2024)	high	https://nahb.org/-/media/AB4EFC742624475A97A0A62189986FF8.ashx

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
residential/ townhomes.json#e1	Characteristics of New Housing — Median and Average Price per Square Foot of Floor Area in Attached New Single-Family Houses Sold (soldpricesqft_cust.xls)	U.S. Census Bureau, Survey of Construction	165.59 USD/ sf (2025)	medium	https://www.census.gov/construction/chars/xls/soldpricesqft_cust.xls
residential/ townhomes.json#e3	Characteristics of New Housing — Median and Average Sales Price of Attached New Single-Family Houses Sold (soldprice_cust.xls)	U.S. Census Bureau, Survey of Construction	398800 USD/unit (2025)	medium	https://www.census.gov/construction/chars/xls/soldprice_cust.xls
residential/ townhomes.json#e4	Issued Residential Building Permits — September 2025, Unincorporated Snohomish County	Snohomish County Planning and Development Services	183 USD/sf (2025)	medium	https://snohomishcountywa.gov/Archive.asp?ADID=7313

Sample output — revenue, land and exit-cap inputs are illustrative. Engine budget-engine-2.0.0.