Station Square — podium mixed-use, 2 phases

Austin, TX

TOTAL PROJECT COST	PER SF	PER ACRE	HARD / SOFT / LAND
$140,902,626	**$445.89**	**$44,032,071**	**70 / 23 / 7%**

COST SUMMARY

Construction hard cost	**$89,017,281**
FF&E	**$611,949**
Design + construction contingency	**$9,154,869**
Hard cost subtotal	**$98,784,098**
Soft costs	**$17,881,906**
Impact & tap fees	**$3,541,555**
Developer fee	**$4,850,940**
Financing (interest + fees)	**$5,055,379**
Soft cost contingency	**$1,065,947**
Soft cost subtotal	**$32,395,728**
Land & acquisition	**$9,722,800**
Total project cost	**$140,902,626**

BASIS

Location	**Austin, TX (factor 0.820)**
Gross building SF	**316,000**
Site acres	**3.20**
Cost per acre	**$44,032,071**
Research data version	**2026.0c737c8255**
Engine	**budget-engine-2.0.0**

All defaults come from the research data shipped with the app (2026.0c737c8255), escalated to the construction midpoint and adjusted to the project location. Values marked "Derived estimate — verify" have no direct published source.

Cost by Component

COMPONENT	TYPE	SIZE	HARD (INCL. FF&E, CONT.)	SOFT (INCL. FIN.)	LAND	TOTAL	PER PRIMARY UNIT	PER SF	RANGE CHECK
Residential over podium	Podium multifamily (5-over-1/2)	280 units	$93,562,266	$30,426,478	$1,237	$123,989,981	$442,821	$421.73	within ($250,000–$650,000)
Ground-floor retail	Retail strip center	22000 SF	$5,221,832	$1,969,250	$9,721,563	$16,912,645	$769	$768.76	within ($140–$420)
TOTAL			**$98,784,098**	**$32,395,728**	**$9,722,800**	**$140,902,626**			

SHARED ELEMENTS

SHARED ELEMENT	ALLOCATION	COST	SHARES
Structured parking (shared)	sf	$12,226,732	Residential over podium $11,375,504; Ground-floor retail $851,228

Cost by Phase

PHASE	START	MONTHS	MIDPOINT	ESCALATION	HARD	SOFT	LAND	TOTAL	LOAN	INTEREST
Phase 1 — podium + residential	2027-01	25	2028-02	6.6%	$94,500,745	$30,654,742	$1,237	$125,156,724	$75,094,034	$3,754,231
Phase 2 — retail fit-out	2029-02	12	2029-08	13.1%	$4,283,353	$1,740,986	$9,721,563	$15,745,902	$9,447,541	$455,733
TOTAL					**$98,784,098**	**$32,395,728**	**$9,722,800**	**$140,902,626**		

Line-Item Detail

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Residential over podium	Phase 1 — podium + residential	Construction	01 00 00	General Requirements	—	—	—	$8,998,619	—
Residential over podium	Phase 1 — podium + residential	Construction	03 00 00	Concrete — balance	—	—	—	$410,358	—
Residential over podium	Phase 1 — podium + residential	Construction	04 00 00	Masonry	—	—	—	$1,079,834	—
Residential over podium	Phase 1 — podium + residential	Construction	05 00 00	Metals	—	—	—	$2,159,669	—
Residential over podium	Phase 1 — podium + residential	Construction	06 00 00	Wood, Plastics & Composites	—	—	—	$10,078,454	—
Residential over podium	Phase 1 — podium + residential	Construction	07 00 00	Thermal & Moisture Protection	—	—	—	$3,959,393	—
Residential over podium	Phase 1 — podium + residential	Construction	08 00 00	Openings	—	—	—	$2,519,613	—
Residential over podium	Phase 1 — podium + residential	Construction	09 00 00	Finishes	—	—	—	$6,119,061	—
Residential over podium	Phase 1 — podium + residential	Construction	10 00 00	Specialties	—	—	—	$503,923	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Residential over podium	Phase 1 — podium + residential	Construction	11 00 00	Equipment	—	—	—	$1,583,757	—
Residential over podium	Phase 1 — podium + residential	Construction	12 00 00	Furnishings	—	—	—	$2,159,669	—
Residential over podium	Phase 1 — podium + residential	Construction	14 00 00	Conveying Equipment — balance	—	—	—	$921,845	—
Residential over podium	Phase 1 — podium + residential	Construction	21 00 00	Fire Suppression	—	—	—	$1,439,779	—
Residential over podium	Phase 1 — podium + residential	Construction	22 00 00	Plumbing	—	—	—	$5,039,227	—
Residential over podium	Phase 1 — podium + residential	Construction	23 00 00	HVAC	—	—	—	$3,599,448	—
Residential over podium	Phase 1 — podium + residential	Construction	26 00 00	Electrical	—	—	—	$6,119,061	—
Residential over podium	Phase 1 — podium + residential	Construction	27 00 00	Communications	—	—	—	$575,912	—
Residential over podium	Phase 1 — podium + residential	Construction	28 00 00	Electronic Safety & Security	—	—	—	$575,912	—
Residential over podium	Phase 1 — podium + residential	Construction	31 00 00	Earthwork	—	—	—	$1,799,724	—
Residential over podium	Phase 1 — podium + residential	Construction	32 00 00	Exterior Improvements	—	—	—	$1,295,801	—
Residential over podium	Phase 1 — podium + residential	Construction	33 00 00	Utilities	—	—	—	$863,867	—
Residential over podium	Phase 1 — podium + residential	Construction	03 00 00	Parking inside the concrete podium (grade / podium level) (within baseline)	280	space	$34,968.49	$9,791,177	—
Residential over podium	Phase 1 — podium + residential	Construction	14 00 00	Passenger elevators (6-7 stop) (within baseline)	3	ea	$174,842.45	$524,527	—
Residential over podium	Phase 1 — podium + residential	Construction	13 00 00	Podium amenity deck (pool, waterproofing, landscape over structure) (within baseline)	1	LS	$786,791.02	$786,791	—
Residential over podium	Phase 1 — podium + residential	FF&E	12 00 00	Furniture, fixtures & equipment	280	unit	$2,185.53	$611,949	—
Ground-floor retail	Phase 2 — retail fit-out	Construction	01 00 00	General Requirements	—	—	—	$270,506	—
Ground-floor retail	Phase 2 — retail fit-out	Construction	03 00 00	Concrete	—	—	—	$473,385	—
Ground-floor retail	Phase 2 — retail fit-out	Construction	04 00 00	Masonry	—	—	—	$135,253	—
Ground-floor retail	Phase 2 — retail fit-out	Construction	05 00 00	Metals	—	—	—	$405,759	—
Ground-floor	Phase 2 — retail fit-	Construction	06 00	Wood, Plastics & Composites	—	—	—	$33,813	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
retail	out		00						
Ground-floor retail	Phase 2 — retail fit-out	Construction	07 00 00	Thermal & Moisture Protection	—	—	—	$304,319	—
Ground-floor retail	Phase 2 — retail fit-out	Construction	08 00 00	Openings	—	—	—	$236,693	—
Ground-floor retail	Phase 2 — retail fit-out	Construction	09 00 00	Finishes	—	—	—	$101,440	—
Ground-floor retail	Phase 2 — retail fit-out	Construction	10 00 00	Specialties	—	—	—	$33,813	—
Ground-floor retail	Phase 2 — retail fit-out	Construction	21 00 00	Fire Suppression	—	—	—	$67,626	—
Ground-floor retail	Phase 2 — retail fit-out	Construction	22 00 00	Plumbing	—	—	—	$101,440	—
Ground-floor retail	Phase 2 — retail fit-out	Construction	23 00 00	HVAC	—	—	—	$135,253	—
Ground-floor retail	Phase 2 — retail fit-out	Construction	26 00 00	Electrical	—	—	—	$202,879	—
Ground-floor retail	Phase 2 — retail fit-out	Construction	27 00 00	Communications	—	—	—	$16,907	—
Ground-floor retail	Phase 2 — retail fit-out	Construction	28 00 00	Electronic Safety & Security	—	—	—	$16,907	—
Ground-floor retail	Phase 2 — retail fit-out	Construction	31 00 00	Earthwork	—	—	—	$169,066	—
Ground-floor retail	Phase 2 — retail fit-out	Construction	33 00 00	Utilities	—	—	—	$169,066	—
Ground-floor retail	Phase 2 — retail fit-out	Construction	32 00 00	On-site work incl. parking field (carve-out) (within baseline)	22,000	SF	$42.65	$938,312	—
Ground-floor retail	Phase 2 — retail fit-out	Specialty & site	10 00 00	Multi-tenant pylon sign	1	ea	$72,690.45	$72,690	—
Residential over podium	Phase 1 — podium + residential	Shared elements	03 00 00	Structured parking (shared) (share)	420	space	$29,111.27	$11,375,504	—
Ground-floor retail	Phase 1 — podium + residential	Shared elements	03 00 00	Structured parking (shared) (share)	420	space	$29,111.27	$851,228	—
Residential over podium	Phase 1 — podium + residential	Contingency	99 02 00	Design contingency	5	% of hard	—	$4,214,046	—
Residential over podium	Phase 1 — podium + residential	Contingency	99 03 00	Hard cost (construction) contingency	5	% of hard	—	$4,455,346	—
Residential over podium	Phase 1 — podium + residential	Soft costs	SC	Architecture & engineering (basic services, design + CA)	10	% of hard	—	$8,235,876	—
Residential over podium	Phase 1 — podium + residential	Soft costs	SC	Civil engineering, ALTA/topo survey, geotechnical report	1	% of hard	—	$1,267,058	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Residential over podium	Phase 1 — podium + residential	Soft costs	SC	Building permit & plan review fees (excl. impact / tap fees)	1	% of hard	—	$1,267,058	—
Residential over podium	Phase 1 — podium + residential	Soft costs	SC	Legal, accounting, cost certification	1	% of hard	—	$886,940	—
Residential over podium	Phase 1 — podium + residential	Soft costs	SC	Builder's risk insurance	1	% of hard	—	$506,823	—
Residential over podium	Phase 1 — podium + residential	Soft costs	SC	Owner's general liability / OCIP-OCP during construction	0	% of hard	—	$380,117	—
Residential over podium	Phase 1 — podium + residential	Soft costs	SC	Marketing, lease-up / rent-up (excl. commercial leasing commissions)	1	% of hard	—	$1,013,646	—
Residential over podium	Phase 1 — podium + residential	Soft costs	SC	Construction-loan title, closing & recording	1	% of hard	—	$506,823	—
Residential over podium	Phase 1 — podium + residential	Soft costs	SC	Special inspections, materials testing, commissioning	1	% of hard	—	$1,013,646	—
Residential over podium	Phase 1 — podium + residential	Soft costs	SC	Owner's representative / project management	2	% of hard	—	$1,900,587	—
Residential over podium	Phase 1 — podium + residential	Soft costs	SC	Third-party reports (appraisal, Phase I ESA, market study, PCA/CNA)	1	project	$20,500.00	$20,500	—
Residential over podium	Phase 1 — podium + residential	Impact & tap fees	SC	Total impact fees — multifamily unit	280	unit	$7,874.30	$2,204,804	—
Residential over podium	Phase 1 — podium + residential	Impact & tap fees	SC	Water capacity / tap / impact fee	168	EDU	$3,407.22	$572,413	—
Residential over podium	Phase 1 — podium + residential	Impact & tap fees	SC	Sewer (wastewater) capacity / tap / impact fee	168	EDU	$3,407.22	$572,413	—
Ground-floor retail	Phase 1 — podium + residential	Contingency	99 02 00	Design contingency	5	% of hard	—	$42,561	—
Ground-floor retail	Phase 1 — podium + residential	Contingency	99 03 00	Hard cost (construction) contingency	5	% of hard	—	$44,689	—
Ground-floor retail	Phase 1 — podium + residential	Soft costs	SC	Architecture & engineering (basic services, design + CA)	8	% of hard	—	$66,065	—
Ground-floor retail	Phase 1 — podium + residential	Soft costs	SC	Civil engineering, ALTA/topo survey, geotechnical report	1	% of hard	—	$10,164	—
Ground-floor retail	Phase 1 — podium + residential	Soft costs	SC	Building permit & plan review fees (excl. impact / tap fees)	1	% of hard	—	$10,164	—
Ground-floor retail	Phase 1 — podium + residential	Soft costs	SC	Legal, accounting, cost certification	1	% of hard	—	$7,115	—
Ground-floor retail	Phase 1 — podium + residential	Soft costs	SC	Builder's risk insurance	0	% of hard	—	$4,066	—
Ground-floor retail	Phase 1 — podium + residential	Soft costs	SC	Owner's general liability / OCIP-OCP during construction	0	% of hard	—	$3,049	—
Ground-floor	Phase 1 — podium	Soft costs	SC	Marketing, lease-up / rent-up (excl. commercial	1	% of hard	—	$8,131	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
retail	+ residential			leasing commissions)					
Ground-floor retail	Phase 1 — podium + residential	Soft costs	SC	Construction-loan title, closing & recording	0	% of hard	—	$4,066	—
Ground-floor retail	Phase 1 — podium + residential	Soft costs	SC	Special inspections, materials testing, commissioning	1	% of hard	—	$8,131	—
Ground-floor retail	Phase 1 — podium + residential	Soft costs	SC	Owner's representative / project management	2	% of hard	—	$15,246	—
Ground-floor retail	Phase 2 — retail fit-out	Contingency	99 02 00	Design contingency	5	% of hard	—	$194,256	—
Ground-floor retail	Phase 2 — retail fit-out	Contingency	99 03 00	Hard cost (construction) contingency	5	% of hard	—	$203,969	—
Ground-floor retail	Phase 2 — retail fit-out	Soft costs	SC	Architecture & engineering (basic services, design + CA)	8	% of hard	—	$301,532	—
Ground-floor retail	Phase 2 — retail fit-out	Soft costs	SC	Civil engineering, ALTA/topo survey, geotechnical report	1	% of hard	—	$46,390	—
Ground-floor retail	Phase 2 — retail fit-out	Soft costs	SC	Building permit & plan review fees (excl. impact / tap fees)	1	% of hard	—	$46,390	—
Ground-floor retail	Phase 2 — retail fit-out	Soft costs	SC	Legal, accounting, cost certification	1	% of hard	—	$32,473	—
Ground-floor retail	Phase 2 — retail fit-out	Soft costs	SC	Builder's risk insurance	0	% of hard	—	$18,556	—
Ground-floor retail	Phase 2 — retail fit-out	Soft costs	SC	Owner's general liability / OCIP-OCP during construction	0	% of hard	—	$13,917	—
Ground-floor retail	Phase 2 — retail fit-out	Soft costs	SC	Marketing, lease-up / rent-up (excl. commercial leasing commissions)	1	% of hard	—	$37,112	—
Ground-floor retail	Phase 2 — retail fit-out	Soft costs	SC	Construction-loan title, closing & recording	0	% of hard	—	$18,556	—
Ground-floor retail	Phase 2 — retail fit-out	Soft costs	SC	Special inspections, materials testing, commissioning	1	% of hard	—	$37,112	—
Ground-floor retail	Phase 2 — retail fit-out	Soft costs	SC	Owner's representative / project management	2	% of hard	—	$69,584	—
Ground-floor retail	Phase 2 — retail fit-out	Soft costs	SC	Third-party reports (appraisal, Phase I ESA, market study, PCA/CNA)	1	project	$20,500.00	$20,500	—
Ground-floor retail	Phase 2 — retail fit-out	Impact & tap fees	SC	Total impact fees — retail	22	1,000 SF	$7,020.26	$154,446	—
Ground-floor retail	Phase 2 — retail fit-out	Impact & tap fees	SC	Water capacity / tap / impact fee	6	EDU	$3,407.22	$18,740	—
Ground-floor retail	Phase 2 — retail fit-out	Impact & tap fees	SC	Sewer (wastewater) capacity / tap / impact fee	6	EDU	$3,407.22	$18,740	—
Residential over podium	Phase 1 — podium + residential	Contingency	SC	Soft cost contingency	5	% of soft	—	$1,017,435	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Ground-floor retail	Phase 1 — podium + residential	Contingency	SC	Soft cost contingency	5	% of soft	—	$6,810	—
Ground-floor retail	Phase 2 — retail fit-out	Contingency	SC	Soft cost contingency	5	% of soft	—	$41,702	—
Residential over podium	Phase 1 — podium + residential	Land	LAND	Land / acquisition	—	—	—	$1,209	—
Ground-floor retail	Phase 2 — retail fit-out	Land	LAND	Land / acquisition	—	—	—	$9,498,791	—
Residential over podium	Phase 1 — podium + residential	Land	LAND	Land closing costs	—	—	—	$24	—
Ground-floor retail	Phase 2 — retail fit-out	Land	LAND	Land closing costs	—	—	—	$189,976	—
Residential over podium	Phase 1 — podium + residential	Land	LAND	Land due diligence	—	—	—	$4	—
Ground-floor retail	Phase 2 — retail fit-out	Land	LAND	Land due diligence	—	—	—	$32,796	—
Residential over podium	Phase 1 — podium + residential	Soft costs	SC	Real estate taxes during construction	2	years	$13.30	$28	—
Ground-floor retail	Phase 2 — retail fit-out	Soft costs	SC	Real estate taxes during construction	1	years	$104,486.70	$104,487	—
Residential over podium	Phase 1 — podium + residential	Developer fee	DEV	Developer fee	4	% of cost excl. land	—	$4,597,137	—
Ground-floor retail	Phase 1 — podium + residential	Developer fee	DEV	Developer fee	4	% of cost excl. land	—	$43,259	—
Ground-floor retail	Phase 2 — retail fit-out	Developer fee	DEV	Developer fee	4	% of cost excl. land	—	$210,544	—
Residential over podium	Phase 1 — podium + residential	Financing	FIN	Construction loan interest (capitalized)	—	—	—	$3,719,233	—
Ground-floor retail	Phase 1 — podium + residential	Financing	FIN	Construction loan interest (capitalized)	—	—	—	$34,998	—
Residential over podium	Phase 1 — podium + residential	Financing	FIN	Construction loan fee	—	—	—	$743,940	—
Ground-floor retail	Phase 1 — podium + residential	Financing	FIN	Construction loan fee	—	—	—	$7,000	—
Ground-floor retail	Phase 2 — retail fit-out	Financing	FIN	Construction loan interest (capitalized)	—	—	—	$455,733	—
Ground-floor retail	Phase 2 — retail fit-out	Financing	FIN	Construction loan fee	—	—	—	$94,475	—
TOTAL				**Total project cost**				**$140,902,626**	

Draw Schedules

PHASE 1 — PODIUM + RESIDENTIAL — MONTHLY DRAWS

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE
2027-01	$0	$13,332,459	$1,237	$14,084,637	$0	$0	$0
2027-02	$372,583	$512,684	$0	$885,268	$0	$0	$0
2027-03	$1,111,874	$512,684	$0	$1,624,558	$0	$0	$0
2027-04	$1,833,630	$512,684	$0	$2,346,314	$0	$0	$0
2027-05	$2,526,468	$512,684	$0	$3,039,153	$0	$0	$0
2027-06	$3,179,463	$512,684	$0	$3,692,147	$0	$0	$0
2027-07	$3,782,315	$512,684	$0	$4,295,000	$0	$0	$0
2027-08	$4,325,518	$512,685	$0	$4,838,203	$0	$0	$0
2027-09	$4,800,505	$512,684	$0	$5,313,190	$0	$0	$0
2027-10	$5,199,786	$512,684	$0	$5,712,470	$0	$0	$0
2027-11	$5,517,062	$512,685	$0	$4,231,750	$1,797,996	$0	$1,797,996
2027-12	$5,747,331	$512,684	$0	$0	$6,260,016	$10,488	$8,068,500
2028-01	$5,886,961	$512,684	$0	$0	$6,399,646	$47,066	$14,515,212
2028-02	$5,933,751	$512,685	$0	$0	$6,446,435	$84,672	$21,046,320
2028-03	$5,886,961	$512,685	$0	$0	$6,399,646	$122,770	$27,568,736
2028-04	$5,747,331	$512,684	$0	$0	$6,260,016	$160,818	$33,989,569
2028-05	$5,517,062	$512,685	$0	$0	$6,029,747	$198,272	$40,217,588
2028-06	$5,199,786	$512,685	$0	$0	$5,712,470	$234,603	$46,164,661
2028-07	$4,800,505	$512,684	$0	$0	$5,313,190	$269,294	$51,747,144
2028-08	$4,325,518	$512,684	$0	$0	$4,838,203	$301,858	$56,887,205
2028-09	$3,782,315	$512,684	$0	$0	$4,295,000	$331,842	$61,514,047
2028-10	$3,179,463	$512,684	$0	$0	$3,692,147	$358,832	$65,565,026
2028-11	$2,526,468	$512,684	$0	$0	$3,039,153	$382,463	$68,986,641
2028-12	$1,833,630	$512,684	$0	$0	$2,346,314	$402,422	$71,735,378
2029-01	$1,111,874	$512,684	$0	$0	$1,624,558	$418,456	$73,778,393
2029-02	$372,583	$512,684	$0	$0	$885,268	$430,374	$75,094,034

PHASE 2 — RETAIL FIT-OUT — MONTHLY DRAWS

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE
2029-02	$0	$574,264	$9,721,563	$6,298,361	$4,091,941	$0	$4,091,941
2029-03	$72,976	$51,376	$0	$0	$124,352	$23,870	$4,240,163
2029-04	$213,954	$51,376	$0	$0	$265,331	$24,734	$4,530,228

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE
2029-05	$340,352	$51,376	$0	$0	$391,728	$26,426	$4,948,382
2029-06	$443,556	$51,376	$0	$0	$494,932	$28,866	$5,472,180
2029-07	$516,532	$51,376	$0	$0	$567,908	$31,921	$6,072,009
2029-08	$554,307	$51,376	$0	$0	$605,683	$35,420	$6,713,112
2029-09	$554,307	$51,376	$0	$0	$605,683	$39,160	$7,357,954
2029-10	$516,532	$51,376	$0	$0	$567,908	$42,921	$7,968,784
2029-11	$443,556	$51,376	$0	$0	$494,932	$46,485	$8,510,200
2029-12	$340,352	$51,376	$0	$0	$391,728	$49,643	$8,951,571
2030-01	$213,954	$51,376	$0	$0	$265,331	$52,218	$9,269,119
2030-02	$72,976	$51,376	$0	$0	$124,352	$54,070	$9,447,541

Sources & Assumptions

ASSUMPTIONS

Residential over podium — baseline price	**$305,000 / unit · Researched (residential/podium-multifamily.json)**
Residential over podium — factors	**regional 0.82 · quality 1 · size 0.9809 · escalation 1.0661**
Residential over podium — research note	**Four to five floors of Type III/V wood framing over a one- or two-level concrete podium holding parking, lobby, amenity and often retail. The concrete podium, elevators, Type III fire-retardant framing and urban sites put it ~1.5x garden cost per unit. Evidence: RLB city multifamily ranges, RSMeans 4-7 story, Florida HFA mid-rise factors, developer/contractor ranges and older architect ratios; no public elemental breakdown was found, so the CSI split is derived.**
Ground-floor retail — baseline price	**$185 / SF · Researched (commercial/retail-strip.json)**
Ground-floor retail — factors	**regional 0.82 · quality 1 · size 1.0103 · escalation 1.1307**
Ground-floor retail — research note	**Single-story multi-tenant strip center delivered as landlord shell (storefronts, demising walls, roof, utilities stubbed) with a large surface parking field. Sitework is a big share of cost. RLB 2026 gives strip-center ranges by city; RSMeans gives national store data; tenant fit-out is separate (Cushman in-line guide).**
Phase 1 — podium + residential — schedule	**2027-01, 25 months, midpoint 2028-02, escalation 6.61% (forecast rates from _indices/escalation.json)**
Phase 1 — podium + residential — financing	**LTC 60%, rate 7.00%, fee 1.00%**
Phase 2 — retail fit-out — schedule	**2029-02, 12 months, midpoint 2029-08, escalation 13.07% (forecast rates from _indices/escalation.json)**
Phase 2 — retail fit-out — financing	**LTC 60%, rate 7.00%, fee 1.00%**

SOURCES (58)

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_blocks/parking.json#e1	WGI releases 2026 parking structure cost outlook	National Parking Association / Parking & Mobility	33300 USD/space (2026)	high	https://www.parking-mobility.org/news/wgi-releases-2026-parking-structure-cost-outlook/

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
		(reporting WGI)			
_blocks/parking.json#e2	Parking structure construction cost up 6% in 2026	Building Design + Construction	33300 USD/space (2026)	high	https://www.bdcnetwork.com/building-sector-reports/transportation-parking-facilities/article/55403221/parking-structure-construction-cost-up-6-in-2026
_blocks/parking.json#e3	Parking Structure Cost Outlook for 2024	WGI	29900 USD/space (2024)	high	https://publications.wginc.com/hubfs/WGIs%20Parking%20Structure%20Cost%20Outlook%20for%202024.pdf
_blocks/parking.json#e4	New UCLA report looks into the high cost to build parking	Streetsblog California (reporting UCLA ITS, 'No Such Thing as Free Parking: Construction Costs in 17 U.S. Cities')	52000 USD/space (2025)	medium	https://cal.streetsblog.org/2026/03/02/new-ucla-report-looks-into-the-high-cost-to-build-parking
_blocks/signage.json#e2	Signage Cost for Business: How Much Should You Expect to Pay?	BlinkSigns	5000–15000 USD/ea (2023)	low	https://blinksigns.com/signage-cost-for-business-how-much-should-you-expect-to-pay/
_common/fees.json#e1	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	13627 USD/unit (2019)	high	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/fees.json#e2	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	6460 USD/unit (2019)	medium	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/fees.json#e3	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	8034 USD/unit (2019)	high	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/fees.json#e4	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	6760 USD/1000sf (2019)	high	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/fees.json#e9	It All Adds Up: The Cost of Housing Development Fees in Seven California Cities	Terner Center for Housing Innovation, UC Berkeley (March 2018)	12000–75000 USD/unit (2018)	high	https://ternercenter.berkeley.edu/wp-content/uploads/2020/08/Development_Fees_Report_Final_2.pdf
_common/financing.json#e1	Secured Overnight Financing Rate (SOFR)	Federal Reserve Bank of St. Louis (FRED)	0.039 pct (2026)	high	https://fred.stlouisfed.org/series/SOFR
_common/financing.json#e2	30-Day Average SOFR (SOFR30DAYAVG)	Federal Reserve Bank of St. Louis (FRED)	0.03889 pct (2026)	high	https://fred.stlouisfed.org/series/SOFR30DAYAVG
_common/financing.json#e3	Bank Prime Loan Rate (DPRIME)	Federal Reserve Bank of St. Louis (FRED)	0.07 pct (2026)	high	https://fred.stlouisfed.org/series/DPRIME

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_common/financing.json#e4	Federal Funds Target Range - Upper Limit (DFEDTARU)	Federal Reserve Bank of St. Louis (FRED)	0.0375–0.04 pct (2026)	high	https://fred.stlouisfed.org/series/DFEDTARU
_common/financing.json#e5	12 CFR Appendix A to Subpart A of Part 365 - Interagency Guidelines for Real Estate Lending Policies	Legal Information Institute, Cornell Law School (text of FDIC regulation)	0.8 pct	high	https://www.law.cornell.edu/cfr/text/12/appendix-A_to_subpart_A_of_part_365
_common/financing.json#e6	The July 2026 Senior Loan Officer Opinion Survey on Bank Lending Practices	Board of Governors of the Federal Reserve System	text (2026)	high	https://www.federalreserve.gov/data/sloos/sloos-202607.htm
_common/land-closing.json#e1	Title Rate Chart (effective March 1, 2026)	Texas Department of Insurance	5226 USD/policy (2026)	high	https://www.tdi.texas.gov/title/titlerates2026.html
_common/land-closing.json#e2	Real estate excise tax	Washington State Department of Revenue	0.0128 pct (2026)	high	https://dor.wa.gov/taxes-rates/other-taxes/real-estate-excise-tax
_common/land-closing.json#e3	Realty Transfer Tax	Pennsylvania Department of Revenue	0.01 pct (2026)	high	https://www.pa.gov/en/agencies/revenue/resources/tax-types-and-information/realty-transfer-tax.html
_common/land-closing.json#e4	Documentary Stamp Tax	Florida Department of Revenue	0.007 pct (2026)	high	https://floridarevenue.com/taxes/taxesfees/Pages/doc_stamp.aspx
_common/land-closing.json#e5	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	text (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e1	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0852 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e10	Builders Risk Insurance in 2026: What It Costs, Who Pays, and the Exclusions That Wreck Commercial Projects	Terrapin Construction Group	0.0035–0.009 pct (2026)	low	https://terrapincg.com/news/builders-risk-insurance-commercial-construction-cost-2026
_common/soft-costs.json#e11	Builders Risk Insurance in 2026: What It Costs, Who Pays, and the Exclusions That Wreck Commercial Projects	Terrapin Construction Group	0.0007–0.0019 pct (2026)	low	https://terrapincg.com/news/builders-risk-insurance-commercial-construction-cost-2026
_common/soft-	PHFA 2025	Pennsylvania	text (2025)	medium	https://www.phfa.org/forms/multifamily_application_guidelines/

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
costs.json#e13	Underwriting Application — Development Cost Limits (revised 1-17-25)	Housing Finance Agency			application/2025-2026-mai-07.pdf
_common/soft-costs.json#e14	What are Typical Developer Fees on a Multifamily Development?	HelloData	0.03–0.05 pct (2025)	low	https://www.hellodata.ai/help-articles/what-are-typical-developer-fees-on-a-multifamily-development
_common/soft-costs.json#e15	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	0.15 pct (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
_common/soft-costs.json#e16	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	0.15 pct (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e17	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	1200 USD/unit (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e18	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	500 USD/unit (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
_common/soft-costs.json#e19	Title Rate Chart (effective March 1, 2026)	Texas Department of Insurance	0.005226 pct (2026)	high	https://www.tdi.texas.gov/title/titlerates2026.html
_common/soft-costs.json#e2	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0988 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e20	Documentary Stamp Tax	Florida Department of Revenue	0.0035 pct (2026)	high	https://floridarevenue.com/taxes/taxesfees/Pages/doc_stamp.aspx
_common/soft-costs.json#e21	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.01 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e3	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29	Washington State Office of Financial Management	0.0716 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
	capital budget instructions)				
_common/soft-costs.json#e4	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	0.0483 pct (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e5	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.06 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e6	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.12 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e7	Building Valuation Data – August 2025	International Code Council (posted by City of Kirkland, WA)	0.0075 pct (2025)	low	https://www.kirklandwa.gov/files/sharedassets/public/v/2/development-services/pdfs/building-pdfs/icc-august-2025.pdf
_common/soft-costs.json#e8	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	175000 USD/project (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e9	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	150000 USD/project (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
commercial/retail-strip.json#e1	North America Quarterly Construction Cost Report, Q3 2026 (Indicative Construction Costs table)	Rider Levett Bucknall (RLB)	200–270 USD/sf (2026)	high	https://www.rlb.com/wp-content/uploads/sites/4/2026/09/Q3-2026-QCR.pdf
commercial/retail-strip.json#e2	North America Quarterly Construction Cost Report, Q3 2026 (Indicative Construction Costs table)	Rider Levett Bucknall (RLB)	135–220 USD/sf (2026)	high	https://www.rlb.com/wp-content/uploads/sites/4/2026/09/Q3-2026-QCR.pdf
commercial/retail-strip.json#e3	2022 Project Costs — 50 17 00 Project Costs per S.F.	Gordian / RSMeans	171 USD/sf (2022)	high	https://www.rsmeans.com/media/wysiwyg/quarterly_updates/2022-Project-Costs-per-Square-Foot.pdf
commercial/retail-strip.json#e4	Construction Cost Estimates for a Store, Retail in National, US (2019 RSMeans data)	Gordian / RSMeans	151.29 USD/sf (2019)	medium	https://www.rsmeans.com/model-pages/retail-store.aspx

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
commercial/retail-strip.json#e6	Construction Cost Trends / 2025 — Houston	Kirksey Architecture	16–22 USD/sf (2025)	medium	https://www.kirksey.com/CMSPages/GetFile.aspx?guid=1c8a21ff-de0e-4629-b9b0-7f38f62c502b
commercial/retail-strip.json#e7	Office building construction costs for 2026	Building Design + Construction (data: Gordian RSMeans)	253.63 USD/sf (2026)	medium	https://www.bdcnetwork.com/construction-costs/article/55389026/office-building-construction-costs-for-2026
residential/podium-multifamily.json#e1	Which multifamily product type is right for your site	LandSouth Construction	235–350 USD/sf (2026)	low	https://landsouth.com/which-multifamily-product-type-is-right-for-your-site/
residential/podium-multifamily.json#e13	Total Development Cost per Unit Limitation Template, Version 09-30-2026 (for all RFAs starting July 2023), 'Data' sheet	Florida Housing Finance Corporation	284000–311000 USD/unit (2026)	medium	https://www.floridahousing.org/docs/default-source/programs/developers-multifamily-programs/competitive/total-development-cost-per-unit-limitation-template-effective-september-30-2026-for-all-rfa-s-starting-july-2023.xlsx
residential/podium-multifamily.json#e14	Total Development Cost per Unit Limitation Template, Version 09-30-2026 (for all RFAs starting July 2023), 'Data' sheet	Florida Housing Finance Corporation	312000–339000 USD/unit (2026)	medium	https://www.floridahousing.org/docs/default-source/programs/developers-multifamily-programs/competitive/total-development-cost-per-unit-limitation-template-effective-september-30-2026-for-all-rfa-s-starting-july-2023.xlsx
residential/podium-multifamily.json#e15	Parking Structure Cost Outlook for 2024	WGI	29900 USD/space (2024)	high	https://publications.wginc.com/parking-structure-cost-outlook-for-2024
residential/podium-multifamily.json#e17	The High Cost of Producing Multifamily Housing in California (RAND RR-A3743-1, Ward & Schlake, 2025) - copy hosted by San Diego Housing Commission	RAND Corporation	0.19–0.33 ratio	high	https://sdhc.org/wp-content/uploads/2025/04/Att-2_RAND_RRA3743-1.pdf
residential/podium-multifamily.json#e18	Making apartments more affordable starts with understanding the costs of building them (Hoyt & Schuetz, May 5, 2020)	Brookings Institution	0.2–0.3 pct	medium	https://www.brookings.edu/research/making-apartments-more-affordable-starts-with-understanding-the-costs-of-building-them/
residential/podium-multifamily.json#e2	Garden vs mid-rise vs high-rise density economics	Apers	235–350 USD/sf (2026)	low	https://apers.app/learn/asset-classes/multifamily/garden-vs-midrise-vs-highrise-density-economics
residential/podium-multifamily.json#e3	Multi-Family Wood-Frame Construction Cost Per Unit (2026): Type V, Podium, and Mid-Rise	Terrapin Construction Group	310000–525000 USD/unit (2026)	low	https://terrapincg.com/news/multi-family-wood-frame-construction-cost-per-unit-2026

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
residential/podium-multifamily.json#e4	How Much Does It Cost to Build an Apartment Complex?	Gordian / RSMeans	210–475 USD/sf (2025)	medium	https://www.rsmeans.com/resources/how-much-does-it-cost-to-build-an-apartment-complex
residential/podium-multifamily.json#e5	RLB Construction Cost Report North America Q3 2026 (PDF), Indicative Construction Costs table	Rider Levett Bucknall	225–410 USD/sf (2026)	medium	https://www.rlb.com/wp-content/uploads/sites/4/2026/09/Q3-2026-QCR.pdf
residential/single-family.json#e10	Cost of Constructing a Home-2024 (Special Study for Housing Economics)	National Association of Home Builders (Eric Lynch)	26747 USD/ unit (2024)	high	https://nahb.org/-/media/AB4EFC742624475A97A0A62189986FF8.ashx

Sample output — revenue, land and exit-cap inputs are illustrative. Engine budget-engine-2.0.0.