Harbor Point — select-service hotel

Nashville, TN

TOTAL PROJECT COST	PER SF	PER KEY	HARD / SOFT / LAND
$30,605,903	**$398.10**	**$246,822**	**70 / 19 / 11%**

COST SUMMARY

Construction hard cost	**$17,213,433**
FF&E	**$2,336,729**
Design + construction contingency	**$1,881,213**
Hard cost subtotal	**$21,431,376**
Soft costs	**$3,205,509**
Impact & tap fees	**$547,248**
Developer fee	**$1,014,759**
Financing (interest + fees)	**$923,359**
Soft cost contingency	**$184,851**
Soft cost subtotal	**$5,875,727**
Land & acquisition	**$3,298,800**
Total project cost	**$30,605,903**

BASIS

Location	**Nashville, TN (factor 0.870)**
Gross building SF	**76,880**
Site acres	**2.48**
Cost per acre	**$12,341,090**
Research data version	**2026.0c737c8255**
Engine	**budget-engine-2.0.0**

All defaults come from the research data shipped with the app (2026.0c737c8255), escalated to the construction midpoint and adjusted to the project location. Values marked "Derived estimate — verify" have no direct published source.

Cost by Component

COMPONENT	TYPE	SIZE	HARD (INCL. FF&E, CONT.)	SOFT (INCL. FIN.)	LAND	TOTAL	PER PRIMARY UNIT	PER SF	RANGE CHECK
Harbor Point hotel	Select-service hotel	124 keys	$21,431,376	$5,875,727	$3,298,800	$30,605,903	$246,822	$398.10	within ($146,345–$334,502)
TOTAL			**$21,431,376**	**$5,875,727**	**$3,298,800**	**$30,605,903**			

Cost by Phase

PHASE	START	MONTHS	MIDPOINT	ESCALATION	HARD	SOFT	LAND	TOTAL	LOAN	INTEREST
Phase 1	2027-03	19	2028-01	6.3%	$21,431,376	$5,875,727	$3,298,800	$30,605,903	$18,363,542	$739,724
TOTAL					**$21,431,376**	**$5,875,727**	**$3,298,800**	**$30,605,903**		

Line-Item Detail

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Harbor Point hotel	Phase 1	Construction	01 00 00	General Requirements	—	—	—	$1,333,935	—
Harbor Point hotel	Phase 1	Construction	03 00 00	Concrete	—	—	—	$1,000,451	—
Harbor Point hotel	Phase 1	Construction	04 00 00	Masonry	—	—	—	$333,484	—
Harbor Point hotel	Phase 1	Construction	05 00 00	Metals	—	—	—	$666,968	—
Harbor Point hotel	Phase 1	Construction	06 00 00	Wood, Plastics & Composites	—	—	—	$1,834,161	—
Harbor Point hotel	Phase 1	Construction	07 00 00	Thermal & Moisture Protection	—	—	—	$1,000,451	—
Harbor Point hotel	Phase 1	Construction	08 00 00	Openings	—	—	—	$833,709	—
Harbor Point hotel	Phase 1	Construction	09 00 00	Finishes	—	—	—	$2,000,903	—
Harbor Point hotel	Phase 1	Construction	10 00 00	Specialties — balance	—	—	—	$312,538	—
Harbor Point hotel	Phase 1	Construction	11 00 00	Equipment	—	—	—	$333,484	—
Harbor Point hotel	Phase 1	Construction	12 00 00	Furnishings	—	—	—	$333,484	—
Harbor Point hotel	Phase 1	Construction	14 00 00	Conveying Equipment	—	—	—	$333,484	—
Harbor Point hotel	Phase 1	Construction	21 00 00	Fire Suppression	—	—	—	$333,484	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Harbor Point hotel	Phase 1	Construction	22 00 00	Plumbing	—	—	—	$1,333,935	—
Harbor Point hotel	Phase 1	Construction	23 00 00	HVAC	—	—	—	$1,167,193	—
Harbor Point hotel	Phase 1	Construction	26 00 00	Electrical	—	—	—	$1,333,935	—
Harbor Point hotel	Phase 1	Construction	27 00 00	Communications	—	—	—	$333,484	—
Harbor Point hotel	Phase 1	Construction	28 00 00	Electronic Safety & Security	—	—	—	$166,742	—
Harbor Point hotel	Phase 1	Construction	31 00 00	Earthwork	—	—	—	$500,226	—
Harbor Point hotel	Phase 1	Construction	32 00 00	Exterior Improvements	—	—	—	$666,968	—
Harbor Point hotel	Phase 1	Construction	33 00 00	Utilities	—	—	—	$500,226	—
Harbor Point hotel	Phase 1	Construction	10 00 00	Brand monument sign (within baseline)	1	ea	$20,945.82	$20,946	—
Harbor Point hotel	Phase 1	Specialty & site	01 00 00	Pre-opening, OS&E and working capital	124	key	$4,348.75	$539,245	—
Harbor Point hotel	Phase 1	FF&E	12 00 00	Furniture, fixtures & equipment	124	key	$18,844.59	$2,336,729	—
Harbor Point hotel	Phase 1	Contingency	99 02 00	Design contingency	5	% of hard	—	$860,672	—
Harbor Point hotel	Phase 1	Contingency	99 03 00	Hard cost (construction) contingency	5	% of hard	—	$1,020,542	—
Harbor Point hotel	Phase 1	Soft costs	SC	Architecture & engineering (basic services, design + CA)	8	% of hard	—	$1,517,326	—
Harbor Point hotel	Phase 1	Soft costs	SC	Civil engineering, ALTA/topo survey, geotechnical report	1	% of hard	—	$233,435	—
Harbor Point hotel	Phase 1	Soft costs	SC	Building permit & plan review fees (excl. impact / tap fees)	1	% of hard	—	$233,435	—
Harbor Point hotel	Phase 1	Soft costs	SC	Legal, accounting, cost certification	1	% of hard	—	$163,404	—
Harbor Point hotel	Phase 1	Soft costs	SC	Builder's risk insurance	0	% of hard	—	$93,374	—
Harbor Point hotel	Phase 1	Soft costs	SC	Owner's general liability / OCIP-OCP during construction	0	% of hard	—	$70,030	—
Harbor Point hotel	Phase 1	Soft costs	SC	Marketing, lease-up / rent-up (excl. commercial leasing commissions)	1	% of hard	—	$186,748	—
Harbor Point	Phase	Soft costs	SC	Construction-loan title, closing & recording	0	% of hard	—	$93,374	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
hotel	1								
Harbor Point hotel	Phase 1	Soft costs	SC	Special inspections, materials testing, commissioning	1	% of hard	—	$186,748	—
Harbor Point hotel	Phase 1	Soft costs	SC	Owner's representative / project management	2	% of hard	—	$350,152	—
Harbor Point hotel	Phase 1	Soft costs	SC	Third-party reports (appraisal, Phase I ESA, market study, PCA/CNA)	1	project	$21,750.00	$21,750	—
Harbor Point hotel	Phase 1	Impact & tap fees	SC	Total impact fees — hotel room	124	key	$3,357.05	$416,274	—
Harbor Point hotel	Phase 1	Impact & tap fees	SC	Water capacity / tap / impact fee	19	EDU	$3,407.22	$65,487	—
Harbor Point hotel	Phase 1	Impact & tap fees	SC	Sewer (wastewater) capacity / tap / impact fee	19	EDU	$3,407.22	$65,487	—
Harbor Point hotel	Phase 1	Contingency	SC	Soft cost contingency	5	% of soft	—	$184,851	—
Harbor Point hotel	Phase 1	Land	LAND	Land / acquisition	—	—	—	$3,200,000	—
Harbor Point hotel	Phase 1	Land	LAND	Land closing costs	—	—	—	$64,000	—
Harbor Point hotel	Phase 1	Land	LAND	Land due diligence	—	—	—	$34,800	—
Harbor Point hotel	Phase 1	Soft costs	SC	Real estate taxes during construction	2	years	$35,200.00	$55,733	—
Harbor Point hotel	Phase 1	Developer fee	DEV	Developer fee	4	% of cost excl. land	—	$1,014,759	—
Harbor Point hotel	Phase 1	Financing	FIN	Construction loan interest (capitalized)	—	—	—	$739,724	—
Harbor Point hotel	Phase 1	Financing	FIN	Construction loan fee	—	—	—	$183,635	—
TOTAL				**Total project cost**				**$30,605,903**	

Draw Schedules

PHASE 1 — MONTHLY DRAWS

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE
2027-03	$0	$2,389,789	$3,298,800	$5,872,224	$0	$0	$0
2027-04	$146,148	$134,873	$0	$281,021	$0	$0	$0
2027-05	$434,457	$134,873	$0	$569,330	$0	$0	$0
2027-06	$710,916	$134,873	$0	$845,789	$0	$0	$0

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE
2027-07	$967,983	$134,873	$0	$1,102,855	$0	$0	$0
2027-08	$1,198,645	$134,873	$0	$1,333,518	$0	$0	$0
2027-09	$1,396,612	$134,873	$0	$1,531,485	$0	$0	$0
2027-10	$1,556,483	$134,873	$0	$706,139	$985,216	$0	$985,216
2027-11	$1,673,897	$134,873	$0	$0	$1,808,770	$5,747	$2,799,733
2027-12	$1,745,651	$134,873	$0	$0	$1,880,524	$16,332	$4,696,589
2028-01	$1,769,789	$134,873	$0	$0	$1,904,662	$27,397	$6,628,647
2028-02	$1,745,651	$134,873	$0	$0	$1,880,524	$38,667	$8,547,838
2028-03	$1,673,897	$134,873	$0	$0	$1,808,770	$49,862	$10,406,470
2028-04	$1,556,483	$134,873	$0	$0	$1,691,356	$60,704	$12,158,530
2028-05	$1,396,612	$134,873	$0	$0	$1,531,485	$70,925	$13,760,939
2028-06	$1,198,645	$134,873	$0	$0	$1,333,518	$80,272	$15,174,730
2028-07	$967,983	$134,873	$0	$0	$1,102,855	$88,519	$16,366,104
2028-08	$710,916	$134,873	$0	$0	$845,789	$95,469	$17,307,362
2028-09	$434,458	$134,873	$0	$0	$569,330	$100,960	$17,977,652
2028-10	$146,148	$134,873	$0	$0	$281,021	$104,870	$18,363,542

Sources & Assumptions

ASSUMPTIONS

Harbor Point hotel — baseline price	**$146,345 / key · Researched (hospitality/hotel-select-service.json)**
Harbor Point hotel — factors	**regional 0.87 · quality 1 · size 0.994 · escalation 1.0626**
Harbor Point hotel — research note	**Branded 4–5 story select/limited-service hotel (Hampton / Courtyard class) of ~80–160 keys with breakfast area, small meeting room, fitness and pool; cost is driven by guestroom count, framing system (wood vs. concrete/steel) and market. Data quality is good: four editions of the HVS U.S. Hotel Development Cost Survey (2022–2025 data) give national per-key medians by component, cross-checked with RLB Q2 2026 3-star $/SF and an HVS feasibility budget. HVS building costs include permits, engineering and hard contingency, so they are scaled to our hard-cost definition.**
Phase 1 — schedule	**2027-03, 19 months, midpoint 2028-01, escalation 6.26% (forecast rates from _indices/escalation.json)**
Phase 1 — financing	**LTC 60%, rate 7.00%, fee 1.00%**

SOURCES (58)

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_common/fees.json#e1	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	13627 USD/unit (2019)	high	https://www.impactfees.com/publications%20pdf/2019survey.pdf

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_common/fees.json#e2	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	6460 USD/unit (2019)	medium	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/fees.json#e3	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	8034 USD/unit (2019)	high	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/fees.json#e5	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	5408 USD/1000sf (2019)	high	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/financing.json#e1	Secured Overnight Financing Rate (SOFR)	Federal Reserve Bank of St. Louis (FRED)	0.039 pct (2026)	high	https://fred.stlouisfed.org/series/SOFR
_common/financing.json#e2	30-Day Average SOFR (SOFR30DAYAVG)	Federal Reserve Bank of St. Louis (FRED)	0.03889 pct (2026)	high	https://fred.stlouisfed.org/series/SOFR30DAYAVG
_common/financing.json#e3	Bank Prime Loan Rate (DPRIME)	Federal Reserve Bank of St. Louis (FRED)	0.07 pct (2026)	high	https://fred.stlouisfed.org/series/DPRIME
_common/financing.json#e4	Federal Funds Target Range - Upper Limit (DFEDTARU)	Federal Reserve Bank of St. Louis (FRED)	0.0375–0.04 pct (2026)	high	https://fred.stlouisfed.org/series/DFEDTARU
_common/financing.json#e5	12 CFR Appendix A to Subpart A of Part 365 - Interagency Guidelines for Real Estate Lending Policies	Legal Information Institute, Cornell Law School (text of FDIC regulation)	0.8 pct	high	https://www.law.cornell.edu/cfr/text/12/appendix-A_to_subpart_A_of_part_365
_common/financing.json#e6	The July 2026 Senior Loan Officer Opinion Survey on Bank Lending Practices	Board of Governors of the Federal Reserve System	text (2026)	high	https://www.federalreserve.gov/data/sloos/sloos-202607.htm
_common/land-closing.json#e1	Title Rate Chart (effective March 1, 2026)	Texas Department of Insurance	5226 USD/policy (2026)	high	https://www.tdi.texas.gov/title/titlerates2026.html
_common/land-closing.json#e2	Real estate excise tax	Washington State Department of Revenue	0.0128 pct (2026)	high	https://dor.wa.gov/taxes-rates/other-taxes/real-estate-excise-tax
_common/land-closing.json#e3	Realty Transfer Tax	Pennsylvania Department of Revenue	0.01 pct (2026)	high	https://www.pa.gov/en/agencies/revenue/resources/tax-types-and-information/realty-transfer-tax.html
_common/land-closing.json#e4	Documentary Stamp Tax	Florida Department of Revenue	0.007 pct (2026)	high	https://floridarevenue.com/taxes/taxesfees/Pages/doc_stamp.aspx
_common/land-closing.json#e5	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	text (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e1	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0852 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e10	Builders Risk Insurance in 2026: What It Costs, Who Pays, and the Exclusions That Wreck Commercial Projects	Terrapin Construction Group	0.0035–0.009 pct (2026)	low	https://terrapincg.com/news/builders-risk-insurance-commercial-construction-cost-2026
_common/soft-	Builders Risk Insurance in	Terrapin	0.0007–	low	https://terrapincg.com/news/builders-risk-insurance-commercial-

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
costs.json#e11	2026: What It Costs, Who Pays, and the Exclusions That Wreck Commercial Projects	Construction Group	0.0019 pct (2026)		construction-cost-2026
_common/soft-costs.json#e13	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	text (2025)	medium	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e14	What are Typical Developer Fees on a Multifamily Development?	HelloData	0.03–0.05 pct (2025)	low	https://www.hellodata.ai/help-articles/what-are-typical-developer-fees-on-a-multifamily-development
_common/soft-costs.json#e15	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	0.15 pct (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
_common/soft-costs.json#e16	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	0.15 pct (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e17	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	1200 USD/unit (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e18	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	500 USD/unit (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
_common/soft-costs.json#e19	Title Rate Chart (effective March 1, 2026)	Texas Department of Insurance	0.005226 pct (2026)	high	https://www.tdi.texas.gov/title/titlerates2026.html
_common/soft-costs.json#e2	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0988 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e20	Documentary Stamp Tax	Florida Department of Revenue	0.0035 pct (2026)	high	https://floridarevenue.com/taxes/taxesfees/Pages/doc_stamp.aspx
_common/soft-costs.json#e21	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.01 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e3	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0716 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e4	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	0.0483 pct (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e5	Board of Commissioners agenda item — Edneyville Elementary School proposal	Henderson County, North Carolina	0.06 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
	(Feb 15, 2017)				
_common/soft-costs.json#e6	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.12 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e7	Building Valuation Data – August 2025	International Code Council (posted by City of Kirkland, WA)	0.0075 pct (2025)	low	https://www.kirklandwa.gov/files/sharedassets/public/v/2/development-services/pdfs/building-pdfs/icc-august-2025.pdf
_common/soft-costs.json#e8	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	175000 USD/project (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e9	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	150000 USD/project (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
hospitality/hotel-select-service.json#e1	HVS U.S. Hotel Development Cost Survey 2026	HVS	126900 USD/key (2025)	high	https://www.hvs.com/article/10509-HVS-US-Hotel-Development-Cost-Survey-2026
hospitality/hotel-select-service.json#e11	Hotel, 4-7 Story with Brick Veneer / Reinforced Concrete — square foot model	Gordian RSMeans	197.45 USD/sf (2019)	medium	https://www.rsmeans.com/model-pages/hotel-4-7-story
hospitality/hotel-select-service.json#e12	HVS U.S. Hotel Development Cost Survey 2026	HVS	18321 USD/key (2025)	high	https://www.hvs.com/article/10509-HVS-US-Hotel-Development-Cost-Survey-2026
hospitality/hotel-select-service.json#e13	HVS U.S. Hotel Development Cost Survey 2026	HVS	16079 USD/key (2025)	high	https://www.hvs.com/article/10509-HVS-US-Hotel-Development-Cost-Survey-2026
hospitality/hotel-select-service.json#e14	HVS U.S. Hotel Development Cost Survey 2025	HVS	22929 USD/key (2024)	high	https://www.hvs.com/article/10219-hvs-us-hotel-development-cost-survey-2025
hospitality/hotel-select-service.json#e15	Feasibility Study — Proposed Limited-Service Hotel, Murrieta, California (May 2022)	HVS for City of Murrieta	17000 USD/key (2022)	high	https://www.murrietaca.gov/DocumentCenter/View/7349/HVS-Feasibility-Study-2022---Proposed-Limited-Service-Hotel-PDF
hospitality/hotel-select-service.json#e16	HVS U.S. Hotel Development Cost Survey 2026	HVS	21002 USD/key (2025)	high	https://www.hvs.com/article/10509-HVS-US-Hotel-Development-Cost-Survey-2026
hospitality/hotel-select-service.json#e17	HVS U.S. Hotel Development Cost Survey 2026	HVS	19896 USD/key (2025)	high	https://www.hvs.com/article/10509-HVS-US-Hotel-Development-Cost-Survey-2026
hospitality/hotel-select-service.json#e18	HVS U.S. Hotel Development Cost Survey 2025	HVS	24833 USD/key (2024)	high	https://www.hvs.com/article/10219-hvs-us-hotel-development-cost-survey-2025
hospitality/hotel-select-service.json#e19	Feasibility Study — Proposed Limited-Service Hotel, Murrieta, California (May 2022)	HVS for City of Murrieta	30000 USD/key (2022)	high	https://www.murrietaca.gov/DocumentCenter/View/7349/HVS-Feasibility-Study-2022---Proposed-Limited-Service-Hotel-PDF

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
hospitality/hotel-select-service.json#e2	HVS U.S. Hotel Development Cost Survey 2026	HVS	141143 USD/key (2025)	high	https://www.hvs.com/article/10509-HVS-US-Hotel-Development-Cost-Survey-2026
hospitality/hotel-select-service.json#e20	HVS U.S. Hotel Development Cost Survey 2026	HVS	3561 USD/key (2025)	high	https://www.hvs.com/article/10509-HVS-US-Hotel-Development-Cost-Survey-2026
hospitality/hotel-select-service.json#e21	HVS U.S. Hotel Development Cost Survey 2026	HVS	2900 USD/key (2025)	high	https://www.hvs.com/article/10509-HVS-US-Hotel-Development-Cost-Survey-2026
hospitality/hotel-select-service.json#e22	HVS U.S. Hotel Development Cost Survey 2025	HVS	5894 USD/key (2024)	high	https://www.hvs.com/article/10219-hvs-us-hotel-development-cost-survey-2025
hospitality/hotel-select-service.json#e23	Feasibility Study — Proposed Limited-Service Hotel, Murrieta, California (May 2022)	HVS for City of Murrieta	4000 USD/key (2022)	high	https://www.murrietaca.gov/DocumentCenter/View/7349/HVS-Feasibility-Study-2022---Proposed-Limited-Service-Hotel-PDF
hospitality/hotel-select-service.json#e3	HVS U.S. Hotel Development Cost Survey 2025	HVS	159636 USD/key (2024)	high	https://www.hvs.com/article/10219-hvs-us-hotel-development-cost-survey-2025
hospitality/hotel-select-service.json#e31	Hotel Cost Estimating Guide 2021	Nehmer and HVS Design	11948–17563 USD/ea (2021)	medium	https://www.hvs.com/WebContent/bookstore/HVS%20Hotel%20Cost%20Estimating%20Guide%202021.pdf
hospitality/hotel-select-service.json#e4	HVS U.S. Hotel Development Cost Survey 2025	HVS	111846 USD/key (2024)	high	https://www.hvs.com/article/10219-hvs-us-hotel-development-cost-survey-2025
hospitality/hotel-select-service.json#e5	HVS U.S. Hotel Development Cost Survey 2024	HVS	161216 USD/key (2023)	high	https://www.hvs.com/article/9999-hvs-us-hotel-development-cost-survey-2024
hospitality/hotel-select-service.json#e6	HVS U.S. Hotel Development Cost Survey 2023	HVS	161853 USD/key (2022)	high	https://www.hvs.com/article/9704-hvs-us-hotel-development-cost-survey-2023
hospitality/hotel-select-service.json#e7	Feasibility Study — Proposed Limited-Service Hotel, Murrieta, California (May 2022)	HVS for City of Murrieta	120000 USD/key (2022)	high	https://www.murrietaca.gov/DocumentCenter/View/7349/HVS-Feasibility-Study-2022---Proposed-Limited-Service-Hotel-PDF
hospitality/hotel-select-service.json#e8	North America Quarterly Construction Cost Report, Q2 2026	Rider Levett Bucknall	406 USD/sf (2026)	medium	https://www.rlb.com/wp-content/uploads/sites/4/2026/06/Q2-2026-QCR_7.7.2026.pdf
residential/single-family.json#e10	Cost of Constructing a Home-2024 (Special Study for Housing Economics)	National Association of Home Builders (Eric Lynch)	26747 USD/unit (2024)	high	https://nahb.org/-/media/AB4EFC742624475A97A0A62189986FF8.ashx

Sample output — revenue, land and exit-cap inputs are illustrative. Engine budget-engine-2.0.0.