I-20 Logistics Center — bulk warehouse

Dallas–Fort Worth, TX

TOTAL PROJECT COST	PER SF	PER SF	HARD / SOFT / LAND
$47,072,339	**$147.10**	**$147**	**67 / 20 / 14%**

COST SUMMARY

Construction hard cost	**$28,675,226**
FF&E	**$0**
Design + construction contingency	**$2,638,121**
Hard cost subtotal	**$31,313,347**
Soft costs	**$4,138,492**
Impact & tap fees	**$1,897,427**
Developer fee	**$1,510,583**
Financing (interest + fees)	**$1,398,783**
Soft cost contingency	**$415,307**
Soft cost subtotal	**$9,360,592**
Land & acquisition	**$6,398,400**
Total project cost	**$47,072,339**

BASIS

Location	**Dallas-Fort Worth, TX (factor 0.840)**
Gross building SF	**320,000**
Site acres	**24.00**
Cost per acre	**$1,961,347**
Research data version	**2026.0c737c8255**
Engine	**budget-engine-2.0.0**

All defaults come from the research data shipped with the app (2026.0c737c8255), escalated to the construction midpoint and adjusted to the project location. Values marked "Derived estimate — verify" have no direct published source.

Cost by Component

COMPONENT	TYPE	SIZE	HARD (INCL. FF&E, CONT.)	SOFT (INCL. FIN.)	LAND	TOTAL	PER PRIMARY UNIT	PER SF	RANGE CHECK
Building A	Warehouse / distribution	320000 SF	$31,313,347	$9,360,592	$6,398,400	$47,072,339	$147	$147.10	within ($80–$230)
TOTAL			**$31,313,347**	**$9,360,592**	**$6,398,400**	**$47,072,339**			

Cost by Phase

PHASE	START	MONTHS	MIDPOINT	ESCALATION	HARD	SOFT	LAND	TOTAL	LOAN	INTEREST
Phase 1	2027-03	18	2027-12	5.9%	$31,313,347	$9,360,592	$6,398,400	$47,072,339	$28,243,404	$1,116,349
TOTAL					**$31,313,347**	**$9,360,592**	**$6,398,400**	**$47,072,339**		

Line-Item Detail

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Building A	Phase 1	Construction	01 00 00	General Requirements	—	—	—	$2,855,918	—
Building A	Phase 1	Construction	03 00 00	Concrete	—	—	—	$6,283,020	—
Building A	Phase 1	Construction	05 00 00	Metals	—	—	—	$3,141,510	—
Building A	Phase 1	Construction	07 00 00	Thermal & Moisture Protection	—	—	—	$1,999,143	—
Building A	Phase 1	Construction	08 00 00	Openings	—	—	—	$1,142,367	—
Building A	Phase 1	Construction	09 00 00	Finishes	—	—	—	$571,184	—
Building A	Phase 1	Construction	10 00 00	Specialties	—	—	—	$285,592	—
Building A	Phase 1	Construction	21 00 00	Fire Suppression — balance	—	—	—	$8,160	—
Building A	Phase 1	Construction	22 00 00	Plumbing	—	—	—	$428,388	—
Building A	Phase 1	Construction	23 00 00	HVAC	—	—	—	$713,980	—
Building A	Phase 1	Construction	26 00 00	Electrical	—	—	—	$1,570,755	—
Building A	Phase 1	Construction	27 00 00	Communications	—	—	—	$142,796	—
Building A	Phase 1	Construction	28 00 00	Electronic Safety & Security	—	—	—	$285,592	—
Building A	Phase	Construction	31 00	Earthwork	—	—	—	$2,284,735	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
	1		00						
Building A	Phase 1	Construction	32 00 00	Exterior Improvements — balance	—	—	—	$3,171,905	—
Building A	Phase 1	Construction	33 00 00	Utilities	—	—	—	$1,713,551	—
Building A	Phase 1	Construction	11 00 00	Dock door package (9×10 insulated door, 30k-lb hydraulic leveler, seal, bumpers, dock light) (within baseline)	43	ea	$16,014.59	$681,581	—
Building A	Phase 1	Construction	21 00 00	ESFR sprinkler system incl. fire pump allowance (within baseline)	320,000	SF	$3.56	$1,138,816	—
Building A	Phase 1	Construction	32 00 00	Trailer parking stalls (heavy-duty concrete, 12×55 ft) (within baseline)	32	space	$8,007.30	$256,234	—
Building A	Phase 1	Contingency	99 02 00	Design contingency	4	% of hard	—	$1,147,009	—
Building A	Phase 1	Contingency	99 03 00	Hard cost (construction) contingency	5	% of hard	—	$1,491,112	—
Building A	Phase 1	Soft costs	SC	Architecture & engineering (basic services, design + CA)	7	% of hard	—	$1,947,347	—
Building A	Phase 1	Soft costs	SC	Civil engineering, ALTA/topo survey, geotechnical report	1	% of hard	—	$299,592	—
Building A	Phase 1	Soft costs	SC	Building permit & plan review fees (excl. impact / tap fees)	1	% of hard	—	$299,592	—
Building A	Phase 1	Soft costs	SC	Legal, accounting, cost certification	1	% of hard	—	$209,714	—
Building A	Phase 1	Soft costs	SC	Builder's risk insurance	0	% of hard	—	$119,837	—
Building A	Phase 1	Soft costs	SC	Owner's general liability / OCIP-OCP during construction	0	% of hard	—	$89,878	—
Building A	Phase 1	Soft costs	SC	Marketing, lease-up / rent-up (excl. commercial leasing commissions)	1	% of hard	—	$239,674	—
Building A	Phase 1	Soft costs	SC	Construction-loan title, closing & recording	0	% of hard	—	$119,837	—
Building A	Phase 1	Soft costs	SC	Special inspections, materials testing, commissioning	1	% of hard	—	$239,674	—
Building A	Phase 1	Soft costs	SC	Owner's representative / project management	2	% of hard	—	$449,388	—
Building A	Phase 1	Soft costs	SC	Third-party reports (appraisal, Phase I ESA, market study, PCA/CNA)	1	project	$21,000.00	$21,000	—
Building A	Phase 1	Impact & tap fees	SC	Total impact fees — industrial	320	1,000 SF	$4,225.85	$1,352,272	—
Building A	Phase 1	Impact & tap fees	SC	Water capacity / tap / impact fee	80	EDU	$3,407.22	$272,578	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Building A	Phase 1	Impact & tap fees	SC	Sewer (wastewater) capacity / tap / impact fee	80	EDU	$3,407.22	$272,578	—
Building A	Phase 1	Contingency	SC	Soft cost contingency	7	% of soft	—	$415,307	—
Building A	Phase 1	Land	LAND	Land / acquisition	—	—	—	$6,240,000	—
Building A	Phase 1	Land	LAND	Land closing costs	—	—	—	$124,800	—
Building A	Phase 1	Land	LAND	Land due diligence	—	—	—	$33,600	—
Building A	Phase 1	Soft costs	SC	Real estate taxes during construction	2	years	$68,640.00	$102,960	—
Building A	Phase 1	Developer fee	DEV	Developer fee	4	% of cost excl. land	—	$1,510,583	—
Building A	Phase 1	Financing	FIN	Construction loan interest (capitalized)	—	—	—	$1,116,349	—
Building A	Phase 1	Financing	FIN	Construction loan fee	—	—	—	$282,434	—
TOTAL				**Total project cost**				**$47,072,339**	

Draw Schedules

PHASE 1 — MONTHLY DRAWS

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE
2027-03	$0	$4,255,244	$6,398,400	$10,936,078	$0	$0	$0
2027-04	$237,860	$205,920	$0	$443,780	$0	$0	$0
2027-05	$706,353	$205,920	$0	$912,273	$0	$0	$0
2027-06	$1,153,384	$205,920	$0	$1,359,304	$0	$0	$0
2027-07	$1,565,369	$205,920	$0	$1,771,290	$0	$0	$0
2027-08	$1,929,792	$205,920	$0	$2,135,712	$0	$0	$0
2027-09	$2,235,579	$205,920	$0	$1,270,498	$1,171,001	$0	$1,171,001
2027-10	$2,473,439	$205,920	$0	$0	$2,679,359	$6,831	$3,857,191
2027-11	$2,636,145	$205,920	$0	$0	$2,842,065	$22,500	$6,721,756
2027-12	$2,718,753	$205,920	$0	$0	$2,924,673	$39,210	$9,685,640
2028-01	$2,718,753	$205,920	$0	$0	$2,924,673	$56,500	$12,666,812
2028-02	$2,636,145	$205,920	$0	$0	$2,842,065	$73,890	$15,582,767
2028-03	$2,473,439	$205,920	$0	$0	$2,679,359	$90,899	$18,353,026

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE
2028-04	$2,235,579	$205,920	$0	$0	$2,441,499	$107,059	$20,901,585
2028-05	$1,929,792	$205,920	$0	$0	$2,135,712	$121,926	$23,159,223
2028-06	$1,565,369	$205,920	$0	$0	$1,771,290	$135,095	$25,065,608
2028-07	$1,153,384	$205,920	$0	$0	$1,359,304	$146,216	$26,571,128
2028-08	$706,353	$205,920	$0	$0	$912,273	$154,998	$27,638,399
2028-09	$237,860	$205,920	$0	$0	$443,780	$161,224	$28,243,404

Sources & Assumptions

ASSUMPTIONS

Building A — baseline price	**$100 / SF · Researched (industrial/warehouse-distribution.json)**
Building A — factors	**regional 0.84 · quality 1 · size 1.0072 · escalation 1.0592**
Building A — research note	**Bulk tilt-wall or precast distribution (32–40' clear) is one of the cheapest building types per SF; cost is driven by building size (fixed costs spread over more SF), slab/structure spec, clear height, dock-door count and the size of the truck courts and trailer parking. Data quality is good: Cushman & Wakefield publishes an annual model-building guide (2026: $78–$144 psf by size) and RLB publishes metro ranges, but the two differ in scope and basis, so the default leans on C&W for big-box product and uses RLB for the spread.**
Phase 1 — schedule	**2027-03, 18 months, midpoint 2027-12, escalation 5.92% (forecast rates from _indices/escalation.json)**
Phase 1 — financing	**LTC 60%, rate 7.00%, fee 1.00%**

SOURCES (50)

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_blocks/building-systems.json#e3	How Much Does a Commercial Fire Sprinkler System Cost?	ThePricer	1.5–3 USD/sf (2026)	low	https://www.thepricer.org/commercial-fire-sprinkler-system-cost/
_blocks/building-systems.json#e4	How Much Does a Commercial Fire Sprinkler System Cost?	ThePricer	4–9 USD/sf (2026)	low	https://www.thepricer.org/commercial-fire-sprinkler-system-cost/
_blocks/paving.json#e7	Item Average Unit Cost, From 2025/09/01 to 2026/08/31, Statewide (historical-item-averages-statewide-12-months)	Florida Department of Transportation	82 USD/sy (2026)	medium	https://fdotwww.blob.core.windows.net/sitefinity/docs/default-source/fpo/fpc/reports/historicalitemaveragecost/moving/statewide/pdf/historical-item-averages-statewide-12-months.pdf?sfvrsn=32501f5b_15
_blocks/paving.json#e8	Weighted Average Unit Prices from 6/25/2025 to 6/24/2026	Arkansas Department of Transportation, Program Management Division	67.98 USD/sy (2025)	high	https://media.ark.org/ardot/June-24-2026-Weighted-Averages-Prices.pdf
_common/fees.json#e1	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	13627 USD/unit (2019)	high	https://www.impactfees.com/publications%20pdf/2019survey.pdf

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_common/fees.json#e2	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	6460 USD/ unit (2019)	medium	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/fees.json#e6	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	3942 USD/1000sf (2019)	high	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/ financing.json#e1	Secured Overnight Financing Rate (SOFR)	Federal Reserve Bank of St. Louis (FRED)	0.039 pct (2026)	high	https://fred.stlouisfed.org/series/SOFR
_common/ financing.json#e2	30-Day Average SOFR (SOFR30DAYAVG)	Federal Reserve Bank of St. Louis (FRED)	0.03889 pct (2026)	high	https://fred.stlouisfed.org/series/SOFR30DAYAVG
_common/ financing.json#e3	Bank Prime Loan Rate (DPRIME)	Federal Reserve Bank of St. Louis (FRED)	0.07 pct (2026)	high	https://fred.stlouisfed.org/series/DPRIME
_common/ financing.json#e4	Federal Funds Target Range - Upper Limit (DFEDTARU)	Federal Reserve Bank of St. Louis (FRED)	0.0375–0.04 pct (2026)	high	https://fred.stlouisfed.org/series/DFEDTARU
_common/ financing.json#e5	12 CFR Appendix A to Subpart A of Part 365 - Interagency Guidelines for Real Estate Lending Policies	Legal Information Institute, Cornell Law School (text of FDIC regulation)	0.8 pct	high	https://www.law.cornell.edu/cfr/text/12/appendix-A_to_subpart_A_of_part_365
_common/ financing.json#e6	The July 2026 Senior Loan Officer Opinion Survey on Bank Lending Practices	Board of Governors of the Federal Reserve System	text (2026)	high	https://www.federalreserve.gov/data/sloos/sloos-202607.htm
_common/land-closing.json#e1	Title Rate Chart (effective March 1, 2026)	Texas Department of Insurance	5226 USD/ policy (2026)	high	https://www.tdi.texas.gov/title/titlerates2026.html
_common/land-closing.json#e2	Real estate excise tax	Washington State Department of Revenue	0.0128 pct (2026)	high	https://dor.wa.gov/taxes-rates/other-taxes/real-estate-excise-tax
_common/land-closing.json#e3	Realty Transfer Tax	Pennsylvania Department of Revenue	0.01 pct (2026)	high	https://www.pa.gov/en/agencies/revenue/resources/tax-types-and-information/realty-transfer-tax.html
_common/land-closing.json#e4	Documentary Stamp Tax	Florida Department of Revenue	0.007 pct (2026)	high	https://floridarevenue.com/taxes/taxesfees/Pages/doc_stamp.aspx
_common/land-closing.json#e5	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	text (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e1	Chapter 08: Architect/ Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0852 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e10	Builders Risk Insurance in 2026: What It Costs, Who Pays, and the Exclusions That Wreck Commercial Projects	Terrapin Construction Group	0.0035–0.009 pct (2026)	low	https://terrapincg.com/news/builders-risk-insurance-commercial-construction-cost-2026
_common/soft-costs.json#e11	Builders Risk Insurance in 2026: What It Costs, Who Pays, and the Exclusions That	Terrapin Construction Group	0.0007–0.0019 pct (2026)	low	https://terrapincg.com/news/builders-risk-insurance-commercial-construction-cost-2026

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
	Wreck Commercial Projects				
_common/soft-costs.json#e13	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	text (2025)	medium	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e14	What are Typical Developer Fees on a Multifamily Development?	HelloData	0.03–0.05 pct (2025)	low	https://www.hellodata.ai/help-articles/what-are-typical-developer-fees-on-a-multifamily-development
_common/soft-costs.json#e15	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	0.15 pct (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
_common/soft-costs.json#e16	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	0.15 pct (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e17	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	1200 USD/unit (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e18	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	500 USD/unit (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
_common/soft-costs.json#e19	Title Rate Chart (effective March 1, 2026)	Texas Department of Insurance	0.005226 pct (2026)	high	https://www.tdi.texas.gov/title/titlerates2026.html
_common/soft-costs.json#e2	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0988 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e20	Documentary Stamp Tax	Florida Department of Revenue	0.0035 pct (2026)	high	https://floridarevenue.com/taxes/taxesfees/Pages/doc_stamp.aspx
_common/soft-costs.json#e21	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.01 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e3	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0716 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e4	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	0.0483 pct (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e5	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.06 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-	Board of Commissioners	Henderson County,	0.12 pct	high	https://www.hendersoncountync.gov/sites/default/files/archives/

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
costs.json#e6	agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	North Carolina	(2017)		Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e7	Building Valuation Data – August 2025	International Code Council (posted by City of Kirkland, WA)	0.0075 pct (2025)	low	https://www.kirklandwa.gov/files/sharedassets/public/v/2/development-services/pdfs/building-pdfs/icc-august-2025.pdf
_common/soft-costs.json#e8	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	175000 USD/project (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e9	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	150000 USD/project (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
industrial/warehouse-distribution.json#e1	2026 Americas Industrial Construction Cost Guide (landing page)	Cushman & Wakefield	87 USD/sf (2026)	high	https://www.cushmanwakefield.com/en/united-states/insights/industrial-construction-cost-guide
industrial/warehouse-distribution.json#e10	Quarterly Construction Cost Report 2026 Third Quarter (North America)	Rider Levett Bucknall	155–245 USD/sf (2026)	high	https://www.rlb.com/wp-content/uploads/sites/4/2026/09/Q3-2026-QCR.pdf
industrial/warehouse-distribution.json#e11	Quarterly Construction Cost Report 2026 Third Quarter (North America)	Rider Levett Bucknall	150–230 USD/sf (2026)	high	https://www.rlb.com/wp-content/uploads/sites/4/2026/09/Q3-2026-QCR.pdf
industrial/warehouse-distribution.json#e12	Warehouse Construction Cost Model (Brick Veneer / Reinforced Concrete)	Gordian RSMeans	119.27 USD/sf (2019)	medium	https://www.rsmeans.com/model-pages/warehouse
industrial/warehouse-distribution.json#e13	Tilt-Up Concrete Construction Cost Per Square Foot (2026)	Terrapin Construction Group	115–185 USD/sf (2026)	low	https://terrapincg.com/news/tilt-up-concrete-construction-cost-per-square-foot-2026
industrial/warehouse-distribution.json#e2	2026 Americas Industrial Construction Cost Guide (landing page)	Cushman & Wakefield	78 USD/sf (2026)	high	https://www.cushmanwakefield.com/en/united-states/insights/industrial-construction-cost-guide
industrial/warehouse-distribution.json#e3	2026 Americas Industrial Construction Cost Guide (landing page)	Cushman & Wakefield	144 USD/sf (2026)	high	https://www.cushmanwakefield.com/en/united-states/insights/industrial-construction-cost-guide
industrial/warehouse-distribution.json#e5	Industrial Construction Costs Rise Across Americas	CRE Daily	0.34–0.37 pct (2026)	medium	https://www.credaily.com/?p=223266
industrial/warehouse-distribution.json#e7	Quarterly Construction Cost Report 2026 Third Quarter (North America)	Rider Levett Bucknall	140–228 USD/sf (2026)	medium	https://www.rlb.com/wp-content/uploads/sites/4/2026/09/Q3-2026-QCR.pdf
industrial/warehouse-distribution.json#e8	Quarterly Construction Cost Report 2026 Third Quarter (North America)	Rider Levett Bucknall	75–155 USD/sf (2026)	high	https://www.rlb.com/wp-content/uploads/sites/4/2026/09/Q3-2026-QCR.pdf
industrial/warehouse-distribution.json#e9	Quarterly Construction Cost Report 2026 Third Quarter (North America)	Rider Levett Bucknall	85–170 USD/sf (2026)	high	https://www.rlb.com/wp-content/uploads/sites/4/2026/09/Q3-2026-QCR.pdf

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
residential/single-family.json#e10	Cost of Constructing a Home-2024 (Special Study for Housing Economics)	National Association of Home Builders (Eric Lynch)	26747 USD/ unit (2024)	high	https://nahb.org/-/media/AB4EFC742624475A97A0A62189986FF8.ashx

Sample output — revenue, land and exit-cap inputs are illustrative. Engine budget-engine-2.0.0.