Desert Ridge MOB

Phoenix, AZ

TOTAL PROJECT COST	PER SF	PER SF	HARD / SOFT / LAND
$33,869,764	**$752.66**	**$753**	**71 / 21 / 8%**

COST SUMMARY

Construction hard cost	**$19,581,081**
FF&E	**$1,732,183**
Design + construction contingency	**$2,731,712**
Hard cost subtotal	**$24,044,976**
Soft costs	**$4,335,069**
Impact & tap fees	**$358,558**
Developer fee	**$1,158,836**
Financing (interest + fees)	**$1,048,427**
Soft cost contingency	**$232,298**
Soft cost subtotal	**$7,133,189**
Land & acquisition	**$2,691,600**
Total project cost	**$33,869,764**

BASIS

Location	**Phoenix, AZ (factor 0.990)**
Gross building SF	**45,000**
Site acres	**4.09**
Cost per acre	**$8,279,276**
Research data version	**2026.7c60a42879**
Engine	**budget-engine-2.0.0**

All defaults come from the research data shipped with the app (2026.7c60a42879), escalated to the construction midpoint and adjusted to the project location. Values marked "Derived estimate — verify" have no direct published source.

Cost by Component

COMPONENT	TYPE	SIZE	HARD (INCL. FF&E, CONT.)	SOFT (INCL. FIN.)	LAND	TOTAL	PER PRIMARY UNIT	PER SF	RANGE CHECK
Medical office building	Medical office building	45000 SF	$24,044,976	$7,133,189	$2,691,600	$33,869,764	$753	$752.66	within ($261–$1,202)
TOTAL			**$24,044,976**	**$7,133,189**	**$2,691,600**	**$33,869,764**			

Cost by Phase

PHASE	START	MONTHS	MIDPOINT	ESCALATION	HARD	SOFT	LAND	TOTAL	LOAN	INTEREST
Phase 1	2027-03	20	2028-01	6.3%	$24,044,976	$7,133,189	$2,691,600	$33,869,764	$20,321,859	$845,209
TOTAL					**$24,044,976**	**$7,133,189**	**$2,691,600**	**$33,869,764**		

Line-Item Detail

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Medical office building	Phase 1	Construction	01 00 00	General Requirements	—	—	—	$1,709,476	—
Medical office building	Phase 1	Construction	03 00 00	Concrete	—	—	—	$1,329,592	—
Medical office building	Phase 1	Construction	04 00 00	Masonry	—	—	—	$379,884	—
Medical office building	Phase 1	Construction	05 00 00	Metals	—	—	—	$1,329,592	—
Medical office building	Phase 1	Construction	06 00 00	Wood, Plastics & Composites	—	—	—	$759,767	—
Medical office building	Phase 1	Construction	07 00 00	Thermal & Moisture Protection	—	—	—	$1,139,651	—
Medical office building	Phase 1	Construction	08 00 00	Openings	—	—	—	$1,329,592	—
Medical office building	Phase 1	Construction	09 00 00	Finishes	—	—	—	$2,279,301	—
Medical office building	Phase 1	Construction	10 00 00	Specialties	—	—	—	$379,884	—
Medical office building	Phase 1	Construction	21 00 00	Fire Suppression	—	—	—	$379,884	—
Medical office building	Phase 1	Construction	22 00 00	Plumbing	—	—	—	$1,329,592	—
Medical office building	Phase 1	Construction	23 00 00	HVAC	—	—	—	$2,279,301	—
Medical office building	Phase 1	Construction	26 00 00	Electrical	—	—	—	$1,899,418	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Medical office building	Phase 1	Construction	27 00 00	Communications	—	—	—	$379,884	—
Medical office building	Phase 1	Construction	28 00 00	Electronic Safety & Security	—	—	—	$189,942	—
Medical office building	Phase 1	Construction	31 00 00	Earthwork	—	—	—	$379,884	—
Medical office building	Phase 1	Construction	33 00 00	Utilities	—	—	—	$379,884	—
Medical office building	Phase 1	Construction	32 00 00	On-site work incl. surface parking (carve-out) (within baseline)	45,000	SF	$32.99	$1,484,593	—
Medical office building	Phase 1	Construction	14 00 00	Hydraulic passenger/stretcher elevator (within baseline)	2	ea	$120,980.85	$241,962	—
Medical office building	Phase 1	FF&E	12 00 00	Furniture, fixtures & equipment	45,000	SF	$38.49	$1,732,183	—
Medical office building	Phase 1	Contingency	99 02 00	Design contingency	7	% of hard	—	$1,370,676	—
Medical office building	Phase 1	Contingency	99 03 00	Hard cost (construction) contingency	6	% of hard	—	$1,361,036	—
Medical office building	Phase 1	Soft costs	SC	Architecture & engineering (basic services, design + CA)	10	% of hard	—	$2,067,705	—
Medical office building	Phase 1	Soft costs	SC	Civil engineering, ALTA/topo survey, geotechnical report	1	% of hard	—	$318,108	—
Medical office building	Phase 1	Soft costs	SC	Building permit & plan review fees (excl. impact / tap fees)	1	% of hard	—	$318,108	—
Medical office building	Phase 1	Soft costs	SC	Legal, accounting, cost certification	1	% of hard	—	$222,676	—
Medical office building	Phase 1	Soft costs	SC	Builder's risk insurance	1	% of hard	—	$127,243	—
Medical office building	Phase 1	Soft costs	SC	Owner's general liability / OCIP-OCP during construction	0	% of hard	—	$95,433	—
Medical office building	Phase 1	Soft costs	SC	Marketing, lease-up / rent-up (excl. commercial leasing commissions)	1	% of hard	—	$254,487	—
Medical office building	Phase 1	Soft costs	SC	Construction-loan title, closing & recording	1	% of hard	—	$127,243	—
Medical office building	Phase 1	Soft costs	SC	Special inspections, materials testing, commissioning	1	% of hard	—	$254,487	—
Medical office building	Phase 1	Soft costs	SC	Owner's representative / project management	2	% of hard	—	$477,163	—
Medical office building	Phase 1	Soft costs	SC	Third-party reports (appraisal, Phase I ESA, market study, PCA/CNA)	1	project	$24,750.00	$24,750	—
Medical office	Phase	Impact & tap	SC	Total impact fees — office	45	1,000 SF	$5,610.30	$252,464	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
building	1	fees							
Medical office building	Phase 1	Impact & tap fees	SC	Water capacity / tap / impact fee	11	EDU	$4,838.18	$54,430	—
Medical office building	Phase 1	Impact & tap fees	SC	Sewer (wastewater) capacity / tap / impact fee	11	EDU	$4,592.44	$51,665	—
Medical office building	Phase 1	Contingency	SC	Soft cost contingency	5	% of soft	—	$232,298	—
Medical office building	Phase 1	Land	LAND	Land / acquisition	—	—	—	$2,600,000	—
Medical office building	Phase 1	Land	LAND	Land closing costs	—	—	—	$52,000	—
Medical office building	Phase 1	Land	LAND	Land due diligence	—	—	—	$39,600	—
Medical office building	Phase 1	Soft costs	SC	Real estate taxes during construction	2	years	$28,600.00	$47,667	—
Medical office building	Phase 1	Developer fee	DEV	Developer fee	4	% of cost excl. land	—	$1,158,836	—
Medical office building	Phase 1	Financing	FIN	Construction loan interest (capitalized)	—	—	—	$845,209	—
Medical office building	Phase 1	Financing	FIN	Construction loan fee	—	—	—	$203,219	—
TOTAL				**Total project cost**				**$33,869,764**	

Draw Schedules

PHASE 1 — MONTHLY DRAWS

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE
2027-03	$0	$2,864,554	$2,691,600	$5,759,372	$0	$0	$0
2027-04	$148,017	$161,010	$0	$309,027	$0	$0	$0
2027-05	$440,406	$161,010	$0	$601,416	$0	$0	$0
2027-06	$721,950	$161,010	$0	$882,961	$0	$0	$0
2027-07	$985,718	$161,010	$0	$1,146,729	$0	$0	$0
2027-08	$1,225,214	$161,010	$0	$1,386,225	$0	$0	$0
2027-09	$1,434,542	$161,010	$0	$1,595,552	$0	$0	$0
2027-10	$1,608,546	$161,010	$0	$1,769,556	$0	$0	$0
2027-11	$1,742,942	$161,010	$0	$97,068	$1,806,884	$0	$1,806,884
2027-12	$1,834,422	$161,010	$0	$0	$1,995,432	$10,540	$3,812,856

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE
2028-01	$1,880,731	$161,010	$0	$0	$2,041,742	$22,242	$5,876,840
2028-02	$1,880,732	$161,010	$0	$0	$2,041,742	$34,282	$7,952,863
2028-03	$1,834,422	$161,010	$0	$0	$1,995,432	$46,392	$9,994,687
2028-04	$1,742,942	$161,010	$0	$0	$1,903,953	$58,302	$11,956,942
2028-05	$1,608,546	$161,010	$0	$0	$1,769,556	$69,749	$13,796,247
2028-06	$1,434,542	$161,010	$0	$0	$1,595,552	$80,478	$15,472,277
2028-07	$1,225,214	$161,010	$0	$0	$1,386,225	$90,255	$16,948,757
2028-08	$985,718	$161,010	$0	$0	$1,146,729	$98,868	$18,194,353
2028-09	$721,950	$161,010	$0	$0	$882,961	$106,134	$19,183,448
2028-10	$440,406	$161,010	$0	$0	$601,416	$111,903	$19,896,767
2028-11	$148,017	$161,010	$0	$0	$309,027	$116,064	$20,321,859

Sources & Assumptions

ASSUMPTIONS

Medical office building — baseline price	**$418 / SF · Researched (commercial/medical-office.json)**
Medical office building — factors	**regional 0.99 · quality 1 · size 0.9906 · escalation 1.0626**
Medical office building — research note	**Outpatient medical office (physician suites, exam rooms, light procedure and imaging) delivered complete: shell plus typical medical build-out with heavier HVAC, plumbing at every exam room and higher electrical density. Public data disagree widely — RSMeans national project data (~$250/SF in 2022) vs. Cumming 2025 metro ranges ($400–1,050) — so the mid is a reasoned blend; verify against a local estimate.**
Phase 1 — schedule	**2027-03, 20 months, midpoint 2028-01, escalation 6.26% (forecast rates from _indices/escalation.json)**
Phase 1 — financing	**LTC 60%, rate 7.00%, fee 1.00%**

SOURCES (40)

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_blocks/building-systems.json#e1	How Much Does Elevator Installation Cost?	ThePricer	75000–350000 USD/ea (2026)	low	https://www.thepricer.org/elevator-installation-costs/
_common/fees.json#e1	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	13627 USD/unit (2019)	high	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/fees.json#e2	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	6460 USD/unit (2019)	medium	https://www.impactfees.com/publications%20pdf/2019survey.pdf
_common/fees.json#e5	National Impact Fee Survey: 2019	Duncan Associates (Clancy Mullen)	5408 USD/1000sf (2019)	high	https://www.impactfees.com/publications%20pdf/2019survey.pdf

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_common/financing.json#e1	Secured Overnight Financing Rate (SOFR)	Federal Reserve Bank of St. Louis (FRED)	0.039 pct (2026)	high	https://fred.stlouisfed.org/series/SOFR
_common/financing.json#e2	30-Day Average SOFR (SOFR30DAYAVG)	Federal Reserve Bank of St. Louis (FRED)	0.03889 pct (2026)	high	https://fred.stlouisfed.org/series/SOFR30DAYAVG
_common/financing.json#e3	Bank Prime Loan Rate (DPRIME)	Federal Reserve Bank of St. Louis (FRED)	0.07 pct (2026)	high	https://fred.stlouisfed.org/series/DPRIME
_common/financing.json#e4	Federal Funds Target Range - Upper Limit (DFEDTARU)	Federal Reserve Bank of St. Louis (FRED)	0.0375–0.04 pct (2026)	high	https://fred.stlouisfed.org/series/DFEDTARU
_common/financing.json#e5	12 CFR Appendix A to Subpart A of Part 365 - Interagency Guidelines for Real Estate Lending Policies	Legal Information Institute, Cornell Law School (text of FDIC regulation)	0.8 pct	high	https://www.law.cornell.edu/cfr/text/12/appendix-A_to_subpart_A_of_part_365
_common/financing.json#e6	The July 2026 Senior Loan Officer Opinion Survey on Bank Lending Practices	Board of Governors of the Federal Reserve System	text (2026)	high	https://www.federalreserve.gov/data/sloos/sloos-202607.htm
_common/land-closing.json#e1	Title Rate Chart (effective March 1, 2026)	Texas Department of Insurance	5226 USD/policy (2026)	high	https://www.tdi.texas.gov/title/titlerates2026.html
_common/land-closing.json#e2	Real estate excise tax	Washington State Department of Revenue	0.0128 pct (2026)	high	https://dor.wa.gov/taxes-rates/other-taxes/real-estate-excise-tax
_common/land-closing.json#e3	Realty Transfer Tax	Pennsylvania Department of Revenue	0.01 pct (2026)	high	https://www.pa.gov/en/agencies/revenue/resources/tax-types-and-information/realty-transfer-tax.html
_common/land-closing.json#e4	Documentary Stamp Tax	Florida Department of Revenue	0.007 pct (2026)	high	https://floridarevenue.com/taxes/taxesfees/Pages/doc_stamp.aspx
_common/land-closing.json#e5	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	text (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e1	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0852 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e10	Builders Risk Insurance in 2026: What It Costs, Who Pays, and the Exclusions That Wreck Commercial Projects	Terrapin Construction Group	0.0035–0.009 pct (2026)	low	https://terrapincg.com/news/builders-risk-insurance-commercial-construction-cost-2026
_common/soft-costs.json#e11	Builders Risk Insurance in 2026: What It Costs, Who Pays, and the Exclusions That Wreck Commercial Projects	Terrapin Construction Group	0.0007–0.0019 pct (2026)	low	https://terrapincg.com/news/builders-risk-insurance-commercial-construction-cost-2026
_common/soft-costs.json#e13	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	text (2025)	medium	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-	What are Typical Developer	HelloData	0.03–0.05 pct	low	https://www.hellodata.ai/help-articles/what-are-typical-developer-

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
costs.json#e14	Fees on a Multifamily Development?		(2025)		fees-on-a-multifamily-development
_common/soft-costs.json#e15	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	0.15 pct (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
_common/soft-costs.json#e16	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	0.15 pct (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e17	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	1200 USD/unit (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e18	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	500 USD/unit (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
_common/soft-costs.json#e19	Title Rate Chart (effective March 1, 2026)	Texas Department of Insurance	0.005226 pct (2026)	high	https://www.tdi.texas.gov/title/titlerates2026.html
_common/soft-costs.json#e2	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0988 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e20	Documentary Stamp Tax	Florida Department of Revenue	0.0035 pct (2026)	high	https://floridarevenue.com/taxes/taxesfees/Pages/doc_stamp.aspx
_common/soft-costs.json#e21	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.01 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e3	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0716 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e4	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	0.0483 pct (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e5	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.06 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e6	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.12 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e7	Building Valuation Data – August 2025	International Code Council (posted by City of Kirkland, WA)	0.0075 pct (2025)	low	https://www.kirklandwa.gov/files/sharedassets/public/v/2/development-services/pdfs/building-pdfs/icc-august-2025.pdf
_common/soft-	PHFA 2025 Underwriting	Pennsylvania Housing	175000 USD/	high	https://www.phfa.org/forms/multifamily_application_guidelines/

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
costs.json#e8	Application — Development Cost Limits (revised 1-17-25)	Finance Agency	project (2025)		application/2025-2026-mai-07.pdf
_common/soft-costs.json#e9	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	150000 USD/ project (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
commercial/ medical-office.json#e1	Market Analysis Q4 2025 — Typical Construction Cost Range (Cost Per Unit 2025)	Cumming Group	450–690 USD/ sf (2025)	high	https://cumming-group.com/wp-content/uploads/2025/12/CummingGroup_Q4_2025_MarketingAnalysis_2.13.26.pdf
commercial/ medical-office.json#e2	2022 Project Costs — 50 17 00 Project Costs per S.F.	Gordian / RSMeans	250 USD/sf (2022)	high	https://www.rsmeans.com/media/wysiwyg/quarterly_updates/2022-Project-Costs-per-Square-Foot.pdf
commercial/ medical-office.json#e3	Construction Cost Estimates for a Medical Office, 1 Story in National, US (2019 RSMeans data)	Gordian / RSMeans	217.02 USD/sf (2019)	medium	https://www.rsmeans.com/model-pages/medical-office-1-story.aspx
commercial/ medical-office.json#e4	Construction Cost Estimates for a Medical Office, 1 Story in National, US (2019 RSMeans data)	Gordian / RSMeans	0.09 pct	medium	https://www.rsmeans.com/model-pages/medical-office-1-story.aspx
commercial/ medical-office.json#e5	Construction Cost Trends / 2025 — Houston	Kirksey Architecture	14–20 USD/sf (2025)	medium	https://www.kirksey.com/CMSPages/GetFile.aspx?guid=1c8a21ff-de0e-4629-b9b0-7f38f62c502b

Sample output — revenue, land and exit-cap inputs are illustrative. Engine budget-engine-2.0.0.