Fulton Market office TI

Chicago, IL

TOTAL PROJECT COST	PER SF	PER SF	HARD / SOFT / LAND
$8,621,399	**$391.88**	**$392**	**85 / 15 / 0%**

COST SUMMARY

Construction hard cost	**$4,731,691**
FF&E	**$1,779,614**
Design + construction contingency	**$776,416**
Hard cost subtotal	**$7,287,721**
Soft costs	**$811,607**
Impact & tap fees	**$0**
Developer fee	**$325,596**
Financing (interest + fees)	**$155,895**
Soft cost contingency	**$40,580**
Soft cost subtotal	**$1,333,678**
Land & acquisition	**$0**
Total project cost	**$8,621,399**

BASIS

Location	**Chicago, IL (factor 1.210)**
Gross building SF	**22,000**
Site acres	**—**
Cost per acre	**—**
Research data version	**2026.7c60a42879**
Engine	**budget-engine-2.0.0**

All defaults come from the research data shipped with the app (2026.7c60a42879), escalated to the construction midpoint and adjusted to the project location. Values marked "Derived estimate — verify" have no direct published source.

Cost by Component

COMPONENT	TYPE	SIZE	HARD (INCL. FF&E, CONT.)	SOFT (INCL. FIN.)	LAND	TOTAL	PER PRIMARY UNIT	PER SF	RANGE CHECK
Tenant improvement — floors 6–7	Office tenant improvement	22000 SF	$7,287,721	$1,333,678	$0	$8,621,399	$392	$391.88	within ($90–$450)
TOTAL			**$7,287,721**	**$1,333,678**	**$0**	**$8,621,399**			

Cost by Phase

PHASE	START	MONTHS	MIDPOINT	ESCALATION	HARD	SOFT	LAND	TOTAL	LOAN	INTEREST
Phase 1	2027-03	11	2027-09	4.9%	$7,287,721	$1,333,678	$0	$8,621,399	$5,172,840	$104,166
TOTAL					**$7,287,721**	**$1,333,678**	**$0**	**$8,621,399**		

Line-Item Detail

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Tenant improvement — floors 6–7	Phase 1	Construction	01 00 00	General Requirements	—	—	—	$442,716	—
Tenant improvement — floors 6–7	Phase 1	Construction	06 00 00	Wood, Plastics & Composites	—	—	—	$268,067	—
Tenant improvement — floors 6–7	Phase 1	Construction	08 00 00	Openings	—	—	—	$434,593	—
Tenant improvement — floors 6–7	Phase 1	Construction	09 00 00	Finishes	—	—	—	$808,261	—
Tenant improvement — floors 6–7	Phase 1	Construction	10 00 00	Specialties	—	—	—	$150,280	—
Tenant improvement — floors 6–7	Phase 1	Construction	21 00 00	Fire Suppression	—	—	—	$101,540	—
Tenant improvement — floors 6–7	Phase 1	Construction	22 00 00	Plumbing	—	—	—	$162,465	—
Tenant improvement — floors 6–7	Phase 1	Construction	23 00 00	HVAC	—	—	—	$755,460	—
Tenant improvement — floors 6–7	Phase 1	Construction	26 00 00	Electrical	—	—	—	$771,707	—
Tenant improvement — floors 6–7	Phase 1	Construction	27 00 00	Communications	—	—	—	$105,602	—
Tenant improvement — floors 6–7	Phase 1	Construction	28 00 00	Electronic Safety & Security	—	—	—	$60,924	—
Tenant improvement — floors 6–7	Phase 1	Specialty & site	27 00 00	Low-voltage cabling, AV and security	22,000	SF	$30.46	$670,078	—
Tenant improvement — floors 6–7	Phase 1	FF&E	12 00 00	Furniture, fixtures & equipment	22,000	SF	$80.89	$1,779,614	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Tenant improvement — floors 6–7	Phase 1	Contingency	99 02 00	Design contingency	5	% of hard	—	$236,585	—
Tenant improvement — floors 6–7	Phase 1	Contingency	99 03 00	Hard cost (construction) contingency	8	% of hard	—	$539,831	—
Tenant improvement — floors 6–7	Phase 1	Soft costs	SC	Architecture & engineering (basic services, design + CA)	6	% of hard	—	$379,016	—
Tenant improvement — floors 6–7	Phase 1	Soft costs	SC	Civil engineering, ALTA/topo survey, geotechnical report	1	% of hard	—	$58,310	—
Tenant improvement — floors 6–7	Phase 1	Soft costs	SC	Building permit & plan review fees (excl. impact / tap fees)	1	% of hard	—	$58,310	—
Tenant improvement — floors 6–7	Phase 1	Soft costs	SC	Legal, accounting, cost certification	1	% of hard	—	$40,817	—
Tenant improvement — floors 6–7	Phase 1	Soft costs	SC	Builder's risk insurance	0	% of hard	—	$23,324	—
Tenant improvement — floors 6–7	Phase 1	Soft costs	SC	Owner's general liability / OCIP-OCP during construction	0	% of hard	—	$17,493	—
Tenant improvement — floors 6–7	Phase 1	Soft costs	SC	Marketing, lease-up / rent-up (excl. commercial leasing commissions)	1	% of hard	—	$46,648	—
Tenant improvement — floors 6–7	Phase 1	Soft costs	SC	Construction-loan title, closing & recording	0	% of hard	—	$23,324	—
Tenant improvement — floors 6–7	Phase 1	Soft costs	SC	Special inspections, materials testing, commissioning	1	% of hard	—	$46,648	—
Tenant improvement — floors 6–7	Phase 1	Soft costs	SC	Owner's representative / project management	1	% of hard	—	$87,465	—
Tenant improvement — floors 6–7	Phase 1	Soft costs	SC	Third-party reports (appraisal, Phase I ESA, market study, PCA/CNA)	1	project	$30,250.00	$30,250	—
Tenant improvement — floors 6–7	Phase 1	Contingency	SC	Soft cost contingency	5	% of soft	—	$40,580	—
Tenant improvement — floors 6–7	Phase 1	Developer fee	DEV	Developer fee	4	% of cost excl. land	—	$325,596	—
Tenant improvement — floors 6–7	Phase 1	Financing	FIN	Construction loan interest (capitalized)	—	—	—	$104,166	—
Tenant improvement — floors 6–7	Phase 1	Financing	FIN	Construction loan fee	—	—	—	$51,728	—
TOTAL				**Total project cost**				**$8,621,399**	

Draw Schedules

PHASE 1 — MONTHLY DRAWS

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE
2027-03	$0	$485,070	$0	$536,798	$0	$0	$0
2027-04	$147,602	$62,974	$0	$210,576	$0	$0	$0
2027-05	$430,848	$62,974	$0	$493,822	$0	$0	$0
2027-06	$679,189	$62,974	$0	$742,163	$0	$0	$0
2027-07	$872,507	$62,974	$0	$935,481	$0	$0	$0
2027-08	$995,139	$62,974	$0	$529,720	$528,393	$0	$528,393
2027-09	$1,037,151	$62,974	$0	$0	$1,100,125	$3,082	$1,631,600
2027-10	$995,139	$62,974	$0	$0	$1,058,113	$9,518	$2,699,231
2027-11	$872,507	$62,974	$0	$0	$935,481	$15,746	$3,650,457
2027-12	$679,189	$62,974	$0	$0	$742,163	$21,294	$4,413,915
2028-01	$430,848	$62,974	$0	$0	$493,822	$25,748	$4,933,485
2028-02	$147,602	$62,974	$0	$0	$210,576	$28,779	$5,172,840

Sources & Assumptions

ASSUMPTIONS

Tenant improvement — floors 6–7 — baseline price	**$150 / SF · Researched (commercial/office-ti.json)**
Tenant improvement — floors 6–7 — factors	**regional 1.21 · quality 1 · size 0.9698 · escalation 1.0488**
Tenant improvement — floors 6–7 — research note	**Interior build-out of office space in an existing shell: partitions, ceilings, finishes, doors, millwork, distribution MEP and fire protection. Cost swings with density of enclosed offices, glass, millwork and MEP intensity; data quality is good (Cushman 42-city guide, Kirksey Texas surveys, Cumming metros, JLL).**
Phase 1 — schedule	**2027-03, 11 months, midpoint 2027-09, escalation 4.88% (forecast rates from _indices/escalation.json)**
Phase 1 — financing	**LTC 60%, rate 7.00%, fee 1.00%**

SOURCES (34)

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_common/financing.json#e1	Secured Overnight Financing Rate (SOFR)	Federal Reserve Bank of St. Louis (FRED)	0.039 pct (2026)	high	https://fred.stlouisfed.org/series/SOFR
_common/financing.json#e2	30-Day Average SOFR (SOFR30DAYAVG)	Federal Reserve Bank of St. Louis (FRED)	0.03889 pct (2026)	high	https://fred.stlouisfed.org/series/SOFR30DAYAVG
_common/financing.json#e3	Bank Prime Loan Rate (DPRIME)	Federal Reserve Bank of St. Louis (FRED)	0.07 pct (2026)	high	https://fred.stlouisfed.org/series/DPRIME
_common/financing.json#e4	Federal Funds Target Range - Upper Limit (DFEDTARU)	Federal Reserve Bank of St. Louis (FRED)	0.0375–0.04 pct (2026)	high	https://fred.stlouisfed.org/series/DFEDTARU
_common/financing.json#e5	12 CFR Appendix A to Subpart A of Part 365 - Interagency	Legal Information Institute, Cornell Law	0.8 pct	high	https://www.law.cornell.edu/cfr/text/12/appendix-A_to_subpart_A_of_part_365

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
	Guidelines for Real Estate Lending Policies	School (text of FDIC regulation)			
_common/financing.json#e6	The July 2026 Senior Loan Officer Opinion Survey on Bank Lending Practices	Board of Governors of the Federal Reserve System	text (2026)	high	https://www.federalreserve.gov/data/sloos/sloos-202607.htm
_common/soft-costs.json#e1	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0852 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e10	Builders Risk Insurance in 2026: What It Costs, Who Pays, and the Exclusions That Wreck Commercial Projects	Terrapin Construction Group	0.0035–0.009 pct (2026)	low	https://terrapincg.com/news/builders-risk-insurance-commercial-construction-cost-2026
_common/soft-costs.json#e11	Builders Risk Insurance in 2026: What It Costs, Who Pays, and the Exclusions That Wreck Commercial Projects	Terrapin Construction Group	0.0007–0.0019 pct (2026)	low	https://terrapincg.com/news/builders-risk-insurance-commercial-construction-cost-2026
_common/soft-costs.json#e14	What are Typical Developer Fees on a Multifamily Development?	HelloData	0.03–0.05 pct (2025)	low	https://www.hellodata.ai/help-articles/what-are-typical-developer-fees-on-a-multifamily-development
_common/soft-costs.json#e15	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	0.15 pct (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
_common/soft-costs.json#e16	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	0.15 pct (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e17	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	1200 USD/unit (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e18	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	500 USD/unit (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
_common/soft-costs.json#e19	Title Rate Chart (effective March 1, 2026)	Texas Department of Insurance	0.005226 pct (2026)	high	https://www.tdi.texas.gov/title/titlerates2026.html
_common/soft-costs.json#e2	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0988 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e20	Documentary Stamp Tax	Florida Department of Revenue	0.0035 pct (2026)	high	https://floridarevenue.com/taxes/taxesfees/Pages/doc_stamp.aspx
_common/soft-costs.json#e21	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.01 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e3	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital	Washington State Office of Financial Management	0.0716 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
	budget instructions)				
_common/soft-costs.json#e4	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	0.0483 pct (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e5	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.06 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e6	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.12 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e7	Building Valuation Data – August 2025	International Code Council (posted by City of Kirkland, WA)	0.0075 pct (2025)	low	https://www.kirklandwa.gov/files/sharedassets/public/v/2/development-services/pdfs/building-pdfs/icc-august-2025.pdf
_common/soft-costs.json#e8	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	175000 USD/project (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e9	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	150000 USD/project (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
commercial/office-ti.json#e1	Construction Cost Trends / 2025 — Houston	Kirksey Architecture	107–140 USD/sf (2025)	high	https://www.kirksey.com/CMSPages/GetFile.aspx?guid=1c8a21ff-de0e-4629-b9b0-7f38f62c502b
commercial/office-ti.json#e10	U.S. & Canada Office Fit-Out Cost Guide (Q1 2026 pricing)	JLL	0.1–0.12 pct	medium	https://www.jll.com/en-ca/guides/us-canada-office-fit-out-cost-guide-2025
commercial/office-ti.json#e2	Construction Cost Trends / 2025 — Dallas	Kirksey Architecture	108–133 USD/sf (2025)	high	https://www.kirksey.com/CMSPages/GetFile.aspx?guid=c5a9a83b-478c-495a-a4b2-cbb2a99377dc
commercial/office-ti.json#e3	Construction Cost Trends / 2025 — Austin	Kirksey Architecture	114–148 USD/sf (2025)	high	https://www.kirksey.com/CMSPages/GetFile.aspx?guid=7cfddae4-aa86-4325-b4d1-2084432c2273
commercial/office-ti.json#e4	U.S. Office Fit Out Cost Guide (2026)	Cushman & Wakefield	108.03–219.32 USD/sf (2026)	high	https://www.cushmanwakefield.com/en/united-states/insights/office-fit-out-cost-guide
commercial/office-ti.json#e5	U.S. Office Fit Out Cost Guide (2026)	Cushman & Wakefield	330.92 USD/sf (2026)	high	https://www.cushmanwakefield.com/en/united-states/insights/office-fit-out-cost-guide
commercial/office-ti.json#e6	U.S. Office Fit Out Cost Guide (2026)	Cushman & Wakefield	text (2026)	high	https://www.cushmanwakefield.com/en/united-states/insights/office-fit-out-cost-guide
commercial/office-ti.json#e8	Market Analysis Q4 2025 — Typical Construction Cost Range (Cost Per Unit 2025)	Cumming Group	160–340 USD/sf (2025)	high	https://cumming-group.com/wp-content/uploads/2025/12/CummingGroup_Q4_2025_MarketingAnalysis_2.13.26.pdf
commercial/office-	Construction Cost Trends / 2025	Kirksey Architecture	30–85 USD/	high	https://www.kirksey.com/CMSPages/GetFile.aspx?

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
ti.json#e9	— Dallas		sf (2025)		guid=c5a9a83b-478c-495a-a4b2-cbb2a99377dc

Sample output — revenue, land and exit-cap inputs are illustrative. Engine budget-engine-2.0.0.