Hill Country event barn & retreat (Custom)

Texas (statewide factor)

TOTAL PROJECT COST	PER SF	PER LS	HARD / SOFT / LAND
$9,381,122	**—**	**$9,381,122**	**68 / 16 / 16%**

COST SUMMARY

Construction hard cost	**$5,675,761**
FF&E	**$0**
Design + construction contingency	**$730,754**
Hard cost subtotal	**$6,406,515**
Soft costs	**$946,588**
Impact & tap fees	**$0**
Developer fee	**$295,981**
Financing (interest + fees)	**$224,806**
Soft cost contingency	**$46,431**
Soft cost subtotal	**$1,513,807**
Land & acquisition	**$1,460,800**
Total project cost	**$9,381,122**

BASIS

Location	**Texas (factor 0.820)**
Gross building SF	**—**
Site acres	**18.00**
Cost per acre	**$521,173**
Research data version	**2026.0c737c8255**
Engine	**budget-engine-2.0.0**

All defaults come from the research data shipped with the app (2026.0c737c8255), escalated to the construction midpoint and adjusted to the project location. Values marked "Derived estimate — verify" have no direct published source.

Cost by Component

COMPONENT	TYPE	SIZE	HARD (INCL. FF&E, CONT.)	SOFT (INCL. FIN.)	LAND	TOTAL	PER PRIMARY UNIT	PER SF	RANGE CHECK
Event barn & retreat	Custom (built from blocks)	1 LS	$6,406,515	$1,513,807	$1,460,800	$9,381,122	$9,381,122	—	within ($0–$1,000,000,000,000)
TOTAL			**$6,406,515**	**$1,513,807**	**$1,460,800**	**$9,381,122**			

Cost by Phase

PHASE	START	MONTHS	MIDPOINT	ESCALATION	HARD	SOFT	LAND	TOTAL	LOAN	INTEREST
Phase 1	2027-03	14	2027-10	5.2%	$6,406,515	$1,513,807	$1,460,800	$9,381,122	$5,628,673	$168,519
TOTAL					**$6,406,515**	**$1,513,807**	**$1,460,800**	**$9,381,122**		

Line-Item Detail

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Event barn & retreat	Phase 1	Building blocks	13 00 00	Pre-engineered metal building (PEMB), erected and enclosed, light interior fit	9,000	SF	$90.60	$815,400	—
Event barn & retreat	Phase 1	Building blocks	09 00 00	Tenant improvement — standard (Gen 1 corporate office fit-out, hard cost)	9,000	SF	$139.78	$1,258,046	—
Event barn & retreat	Phase 1	Building blocks	32 00 00	Site development, typical commercial pad - all-in on-site (grading, utilities, paving, storm, lighting, landscaping)	6	acre	$224,342.96	$1,346,058	—
Event barn & retreat	Phase 1	Building blocks	13 00 00	Restroom building (prefab or site-built, park/amenity)	900	SF	$676.47	$608,825	—
Event barn & retreat	Phase 1	Building blocks	13 00 00	Pavilion / shade structure (open-sided roofed)	3,500	SF	$70.44	$246,553	—
Event barn & retreat	Phase 1	Building blocks	32 00 00	Surface parking (asphalt, per space incl. drive aisles)	180	space	$5,862.75	$1,055,296	—
Event barn & retreat	Phase 1	Building blocks	33 00 00	Septic system, conventional (1,000-1,500 gal tank + gravity drainfield; small building)	2	ea	$17,257.15	$34,514	—
Event barn & retreat	Phase 1	Building blocks	33 00 00	Water well, drilled (300-600 ft) with pump, pitless adapter, pressure tank - small non-community system	1	ea	$38,828.59	$38,829	—
Event barn & retreat	Phase 1	Building blocks	11 00 00	Commercial kitchen equipment package, installed (per SF of kitchen area)	1,200	SF	$138.06	$165,669	—
Event barn & retreat	Phase 1	Building blocks	10 00 00	Monument sign (ground-mounted, masonry/aluminum base, illuminated)	1	ea	$21,571.44	$21,571	—
Event barn & retreat	Phase 1	Building blocks	01 00 00	Owner-supplied lighting package	1	LS	$85,000.00	$85,000	—
Event barn & retreat	Phase 1	Contingency	99 02 00	Design contingency	8	% of hard	—	$425,682	—
Event barn & retreat	Phase 1	Contingency	99 03 00	Hard cost (construction) contingency	5	% of hard	—	$305,072	—

COMPONENT	PHASE	GROUP	CODE	LINE	QTY	UNIT	RATE	AMOUNT	EDITED
Event barn & retreat	Phase 1	Soft costs	SC	Architecture & engineering (basic services, design + CA)	8	% of hard	—	$440,507	—
Event barn & retreat	Phase 1	Soft costs	SC	Civil engineering, ALTA/topo survey, geotechnical report	1	% of hard	—	$67,770	—
Event barn & retreat	Phase 1	Soft costs	SC	Building permit & plan review fees (excl. impact / tap fees)	1	% of hard	—	$67,770	—
Event barn & retreat	Phase 1	Soft costs	SC	Legal, accounting, cost certification	1	% of hard	—	$47,439	—
Event barn & retreat	Phase 1	Soft costs	SC	Builder's risk insurance	0	% of hard	—	$27,108	—
Event barn & retreat	Phase 1	Soft costs	SC	Owner's general liability / OCIP-OCP during construction	0	% of hard	—	$20,331	—
Event barn & retreat	Phase 1	Soft costs	SC	Marketing, lease-up / rent-up (excl. commercial leasing commissions)	1	% of hard	—	$54,216	—
Event barn & retreat	Phase 1	Soft costs	SC	Construction-loan title, closing & recording	0	% of hard	—	$27,108	—
Event barn & retreat	Phase 1	Soft costs	SC	Special inspections, materials testing, commissioning	1	% of hard	—	$54,216	—
Event barn & retreat	Phase 1	Soft costs	SC	Owner's representative / project management	2	% of hard	—	$101,655	—
Event barn & retreat	Phase 1	Soft costs	SC	Third-party reports (appraisal, Phase I ESA, market study, PCA/CNA)	1	project	$20,500.00	$20,500	—
Event barn & retreat	Phase 1	Contingency	SC	Soft cost contingency	5	% of soft	—	$46,431	—
Event barn & retreat	Phase 1	Land	LAND	Land / acquisition	—	—	—	$1,400,000	—
Event barn & retreat	Phase 1	Land	LAND	Land closing costs	—	—	—	$28,000	—
Event barn & retreat	Phase 1	Land	LAND	Land due diligence	—	—	—	$32,800	—
Event barn & retreat	Phase 1	Soft costs	SC	Real estate taxes during construction	1	years	$15,400.00	$17,967	—
Event barn & retreat	Phase 1	Developer fee	DEV	Developer fee	4	% of cost excl. land	—	$295,981	—
Event barn & retreat	Phase 1	Financing	FIN	Construction loan interest (capitalized)	—	—	—	$168,519	—
Event barn & retreat	Phase 1	Financing	FIN	Construction loan fee	—	—	—	$56,287	—
TOTAL				**Total project cost**				**$9,381,122**	

Draw Schedules

PHASE 1 — MONTHLY DRAWS

MONTH	HARD	SOFT	LAND	EQUITY	LOAN DRAW	INTEREST	LOAN BALANCE
2027-03	$0	$549,108	$1,460,800	$2,066,195	$0	$0	$0
2027-04	$80,312	$52,850	$0	$133,162	$0	$0	$0
2027-05	$236,910	$52,849	$0	$289,759	$0	$0	$0
2027-06	$381,628	$52,849	$0	$434,477	$0	$0	$0
2027-07	$507,209	$52,849	$0	$560,059	$0	$0	$0
2027-08	$607,357	$52,850	$0	$268,797	$391,410	$0	$391,410
2027-09	$677,050	$52,849	$0	$0	$729,899	$2,283	$1,123,592
2027-10	$712,792	$52,850	$0	$0	$765,641	$6,554	$1,895,788
2027-11	$712,792	$52,849	$0	$0	$765,641	$11,059	$2,672,488
2027-12	$677,049	$52,850	$0	$0	$729,899	$15,590	$3,417,976
2028-01	$607,357	$52,849	$0	$0	$660,206	$19,938	$4,098,121
2028-02	$507,209	$52,849	$0	$0	$560,059	$23,906	$4,682,085
2028-03	$381,628	$52,849	$0	$0	$434,477	$27,312	$5,143,875
2028-04	$236,910	$52,850	$0	$0	$289,759	$30,006	$5,463,640
2028-05	$80,312	$52,849	$0	$0	$133,162	$31,871	$5,628,673

Sources & Assumptions

ASSUMPTIONS

Event barn & retreat — baseline price	**$0 / LS · Derived estimate — verify (marine-other/custom.json)**
Event barn & retreat — factors	**regional 0.82 · quality 1 · size 1 · escalation 1.0523**
Event barn & retreat — research note	**A Custom component has no baseline price of its own: its hard cost is the sum of the building blocks the user adds (each priced from data/research/_blocks with its own sources) plus any hand-priced items. Soft costs, contingencies, fees and financing use the shared norms in data/research/_common.**
Phase 1 — schedule	**2027-03, 14 months, midpoint 2027-10, escalation 5.23% (forecast rates from _indices/escalation.json)**
Phase 1 — financing	**LTC 60%, rate 7.00%, fee 1.00%**

SOURCES (52)

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_blocks/amenities.json#e13	Legislation ID 26-23 — Large Park Restroom construction contract	City of Fresno	608363 USD/ea (2025)	high	https://agendas.fresno.gov/en/legislation/id-26-23-20726

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_blocks/ amenities.json#e14	Design, Manufacture, and Install a Prefabricated Restroom Building — City Council Regular Meeting (Dec 19, 2024)	City of Savannah, GA	264927 USD/ea (2024)	high	https://agenda.savannahga.gov/publishing/december-19-2024-city-council-regular-meeting/1471_10896.html
_blocks/ amenities.json#e23	Pergola Cost	Fixr	5700–30000 USD/ea (2022)	low	https://www.fixr.com/costs/build-pergola
_blocks/ parking.json#e5	Project Cost Sheet - Creation of E-1 Surface Parking Lot (Project 24134001)	University of Central Florida, Facilities Planning & Construction	15505 USD/ space (2025)	medium	https://fp.ucf.edu/wp-content/uploads/projects/costs/2026/24134001%20Creation%20of%20E-1%20Surface%20Parking%20Lot.pdf
_blocks/ parking.json#e6	The Costs of Parking in Hawai'i (August 2020)	Ulupono Initiative (cost estimates by Rider Levett Bucknall; land by PBR Hawaii)	42000 USD/ space (2020)	medium	https://www.ulupono.com/media/ivcfs2pu/the-cost-of-parking-in-hawaii-report-2020-08.pdf
_blocks/ parking.json#e7	How much does it cost to build a parking garage?	Fixr.com	5000 USD/ space (2022)	low	https://www.fixr.com/costs/build-parking-garage
_blocks/ parking.json#e8	WGI releases 2026 parking structure cost outlook	National Parking Association / Parking & Mobility (reporting WGI)	31400 USD/ space (2025)	high	https://www.parking-mobility.org/news/wgi-releases-2026-parking-structure-cost-outlook/
_blocks/ paving.json#e1	Item Average Unit Cost, From 2025/09/01 to 2026/08/31, Statewide (historical-item-averages-statewide-12-months)	Florida Department of Transportation	136.23 USD/ton (2026)	high	https://fdotwww.blob.core.windows.net/sitefinity/docs/default-source/fpo/fpc/reports/historicalitemaveragecost/moving/statewide/pdf/historical-item-averages-statewide-12-months.pdf?sfvrsn=32501f5b_15
_blocks/ paving.json#e2	Item Average Unit Cost, From 2025/09/01 to 2026/08/31, Statewide (historical-item-averages-statewide-12-months)	Florida Department of Transportation	17.5 USD/ sy (2026)	high	https://fdotwww.blob.core.windows.net/sitefinity/docs/default-source/fpo/fpc/reports/historicalitemaveragecost/moving/statewide/pdf/historical-item-averages-statewide-12-months.pdf?sfvrsn=32501f5b_15
_blocks/ paving.json#e4	Item Average Unit Cost, From 2025/09/01 to 2026/08/31, Statewide (historical-item-averages-	Florida Department of Transportation	38.56 USD/lf (2026)	high	https://fdotwww.blob.core.windows.net/sitefinity/docs/default-source/fpo/fpc/reports/historicalitemaveragecost/moving/statewide/pdf/historical-item-averages-statewide-12-months.pdf?sfvrsn=32501f5b_15

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
	statewide-12-months)				
_blocks/signage.json#e1	Monument Signs for Businesses: A Complete Guide	AlphaGraphics Conroe	5000–150000 USD/ea (2026)	low	https://www.alphagraphics.com/us-texas-conroe-us723/blog/blog-list/2026/07/monument-signs-for-businesses-a-complete-guide
_blocks/site-work.json#e3	Item Average Unit Cost, From 2025/09/01 to 2026/08/31, Statewide (historical-item-averages-statewide-12-months)	Florida Department of Transportation	6.81 USD/cy (2026)	high	https://fdotwww.blob.core.windows.net/sitefinity/docs/default-source/fpo/fpc/reports/historicalitemaveragecost/moving/statewide/pdf/historical-item-averages-statewide-12-months.pdf?sfvrsn=32501f5b_15
_blocks/vertical-building.json#e1	RLB Construction Cost Report North America Q3 2026	Rider Levett Bucknall	190–285 USD/sf (2026)	high	https://www.rlb.com/wp-content/uploads/sites/4/2026/09/Q3-2026-QCR.pdf
_blocks/vertical-building.json#e19	Factory, 1 Story Construction Cost Model	Gordian RSMeans	115.78 USD/sf (2019)	low	https://www.rsmeans.com/model-pages/factory-1-story
_blocks/vertical-building.json#e2	RLB Construction Cost Report North America Q3 2026	Rider Levett Bucknall	195–285 USD/sf (2026)	high	https://www.rlb.com/wp-content/uploads/sites/4/2026/09/Q3-2026-QCR.pdf
_blocks/vertical-building.json#e20	Office Fit Out Cost Guide 2026 (Americas)	Cushman & Wakefield	162 USD/sf (2026)	high	https://digital.cushmanwakefield.com/fitoutcostguide-03-2026-amer-regional-en-content-pds-office/
_blocks/vertical-building.json#e21	Office Fit Out Cost Guide 2026 (Americas)	Cushman & Wakefield	196 USD/sf (2026)	high	https://digital.cushmanwakefield.com/fitoutcostguide-03-2026-amer-regional-en-content-pds-office/
_blocks/vertical-building.json#e23	Office Fit Out Cost Guide 2026 | US	Cushman & Wakefield	108.26 USD/sf (2026)	high	https://www.cushmanwakefield.com/en/united-states/insights/office-fit-out-cost-guide
_blocks/vertical-building.json#e24	Office Fit Out Cost Guide 2026 (Americas)	Cushman & Wakefield	213.28 USD/sf (2026)	medium	https://digital.cushmanwakefield.com/fitoutcostguide-03-2026-amer-regional-en-content-pds-office/
_blocks/vertical-building.json#e3	RLB Construction Cost Report North America Q3 2026	Rider Levett Bucknall	205–305 USD/sf (2026)	high	https://www.rlb.com/wp-content/uploads/sites/4/2026/09/Q3-2026-QCR.pdf
_blocks/vertical-building.json#e7	RLB Construction Cost Report North America Q3 2026	Rider Levett Bucknall	155–245 USD/sf (2026)	high	https://www.rlb.com/wp-content/uploads/sites/4/2026/09/Q3-2026-QCR.pdf
_common/financing.json#e1	Secured Overnight Financing Rate (SOFR)	Federal Reserve Bank of St. Louis (FRED)	0.039 pct (2026)	high	https://fred.stlouisfed.org/series/SOFR
_common/financing.json#e2	30-Day Average SOFR (SOFR30DAYAVG)	Federal Reserve Bank of St. Louis (FRED)	0.03889 pct (2026)	high	https://fred.stlouisfed.org/series/SOFR30DAYAVG
_common/	Bank Prime Loan	Federal Reserve	0.07 pct	high	https://fred.stlouisfed.org/series/DPRIME

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
financing.json#e3	Rate (DPRIME)	Bank of St. Louis (FRED)	(2026)		
_common/financing.json#e4	Federal Funds Target Range - Upper Limit (DFEDTARU)	Federal Reserve Bank of St. Louis (FRED)	0.0375–0.04 pct (2026)	high	https://fred.stlouisfed.org/series/DFEDTARU
_common/financing.json#e5	12 CFR Appendix A to Subpart A of Part 365 - Interagency Guidelines for Real Estate Lending Policies	Legal Information Institute, Cornell Law School (text of FDIC regulation)	0.8 pct	high	https://www.law.cornell.edu/cfr/text/12/appendix-A_to_subpart_A_of_part_365
_common/financing.json#e6	The July 2026 Senior Loan Officer Opinion Survey on Bank Lending Practices	Board of Governors of the Federal Reserve System	text (2026)	high	https://www.federalreserve.gov/data/sloos/sloos-202607.htm
_common/land-closing.json#e1	Title Rate Chart (effective March 1, 2026)	Texas Department of Insurance	5226 USD/policy (2026)	high	https://www.tdi.texas.gov/title/titlerates2026.html
_common/land-closing.json#e2	Real estate excise tax	Washington State Department of Revenue	0.0128 pct (2026)	high	https://dor.wa.gov/taxes-rates/other-taxes/real-estate-excise-tax
_common/land-closing.json#e3	Realty Transfer Tax	Pennsylvania Department of Revenue	0.01 pct (2026)	high	https://www.pa.gov/en/agencies/revenue/resources/tax-types-and-information/realty-transfer-tax.html
_common/land-closing.json#e4	Documentary Stamp Tax	Florida Department of Revenue	0.007 pct (2026)	high	https://floridarevenue.com/taxes/taxesfees/Pages/doc_stamp.aspx
_common/land-closing.json#e5	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	text (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e1	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0852 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e10	Builders Risk Insurance in 2026: What It Costs, Who Pays, and the Exclusions That Wreck Commercial Projects	Terrapin Construction Group	0.0035–0.009 pct (2026)	low	https://terrapincg.com/news/builders-risk-insurance-commercial-construction-cost-2026

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_common/soft-costs.json#e11	Builders Risk Insurance in 2026: What It Costs, Who Pays, and the Exclusions That Wreck Commercial Projects	Terrapin Construction Group	0.0007–0.0019 pct (2026)	low	https://terrapincg.com/news/builders-risk-insurance-commercial-construction-cost-2026
_common/soft-costs.json#e13	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	text (2025)	medium	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e14	What are Typical Developer Fees on a Multifamily Development?	HelloData	0.03–0.05 pct (2025)	low	https://www.hellodata.ai/help-articles/what-are-typical-developer-fees-on-a-multifamily-development
_common/soft-costs.json#e15	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	0.15 pct (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
_common/soft-costs.json#e16	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	0.15 pct (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e17	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	1200 USD/unit (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e18	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	500 USD/unit (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf
_common/soft-costs.json#e19	Title Rate Chart (effective March 1, 2026)	Texas Department of Insurance	0.005226 pct (2026)	high	https://www.tdi.texas.gov/title/titlerates2026.html
_common/soft-costs.json#e2	Chapter 08: Architect/Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0988 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e20	Documentary Stamp Tax	Florida Department of Revenue	0.0035 pct (2026)	high	https://floridarevenue.com/taxes/taxesfees/Pages/doc_stamp.aspx

REF	SOURCE	PUBLISHER	VALUE	CONFIDENCE	URL
_common/soft-costs.json#e21	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.01 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e3	Chapter 08: Architect/ Engineer Fee Guidelines and Fee Schedule (2027-29 capital budget instructions)	Washington State Office of Financial Management	0.0716 pct (2026)	high	https://ofm.wa.gov/budget/state-budget-2027-29/instructions/capital/chapter-08/
_common/soft-costs.json#e4	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	0.0483 pct (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e5	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.06 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e6	Board of Commissioners agenda item — Edneyville Elementary School proposal (Feb 15, 2017)	Henderson County, North Carolina	0.12 pct (2017)	high	https://www.hendersoncountync.gov/sites/default/files/archives/Meetings/Board_of_Commissioners/agenda170215/DI.B.pdf
_common/soft-costs.json#e7	Building Valuation Data – August 2025	International Code Council (posted by City of Kirkland, WA)	0.0075 pct (2025)	low	https://www.kirklandwa.gov/files/sharedassets/public/v/2/development-services/pdfs/building-pdfs/icc-august-2025.pdf
_common/soft-costs.json#e8	PHFA 2025 Underwriting Application — Development Cost Limits (revised 1-17-25)	Pennsylvania Housing Finance Agency	175000 USD/ project (2025)	high	https://www.phfa.org/forms/multifamily_application_guidelines/application/2025-2026-mai-07.pdf
_common/soft-costs.json#e9	2025-2026 Delaware State Housing Authority Low Income Housing Tax Credit Guidelines	Delaware State Housing Authority	150000 USD/ project (2025)	high	https://www.destatehousing.com/wp-content/uploads/2026/06/2025-2026-LIHTC-Guidelines.pdf

Sample output — revenue, land and exit-cap inputs are illustrative. Engine budget-engine-2.0.0.